



# PLANNING COMMISSION

Planning & Development Services Department • 201 N. Stone Ave. • Tucson, AZ 85701

**DATE:** December 7, 2011

**TO:** Planning Commission

**FROM:** Ernie Duarte  
Executive Secretary

**SUBJECT:** Proposed Unified Development Code: Articles 4 (Zones) and 6  
(Dimensional Standards and Measurements)

**Issue** – This item is for discussion by the Planning Commission in a Study Session.

The Unified Development Code (UDC) is a simplification and reformat of the City's Land Use Code (LUC).

The City's consultant, Clarion Associates, has completed preliminary drafts of all eleven articles of the UDC. Staff has completed their initial review of Articles 4 and 6 and revised the articles to address several issues. Preliminary final drafts of each article, as well as disposition reports, are attached.

**Recommendation** – Staff recommends continued review of these and upcoming draft articles for the next several months.

## **Background**

**Land Use Code Simplification and Reformat Project (Project).** The purpose of the Project is to, in general, simplify and reformat the City's LUC, Development Standards, and Chapter 23A Procedures so that they are more user-friendly. The Project's goals are to:

- Consolidate procedures;
- Clarify vagueness;
- Emphasize simplicity;
- Reduce need for cross-referencing (i.e. reduce page flipping) and redundancy;
- Use a simplified numbering system;
- Replace the development designator system with simpler dimensions by zone;
- Provide new language necessary for the transition from LUC to UDC; and,
- Acknowledge that other items may require revision during the project.

The Project requires the preparation of three separate, but interrelated documents:

*Unified Development Code (UDC).* The UDC establishes, among other requirements, the zoning regulations and review and approval procedures applicable to development and uses of land within the City of Tucson. Clarion Associates, the consultant contracted by the City to

prepare the UDC, has completed a draft UDC (see Attachment A for a summary of the UDC's eleven articles). Staff is reviewing the draft and is in the process of preparing the next draft for review by the Planning Commission and the public.

*Administrative Manual.* The Administrative Manual includes application submittal requirements, development review fees, and the City Development Review Committee procedure. The contents of the Administrative Manual are primarily from the City's Development Standards. Staff is responsible for preparing the Administrative Manual. The Administrative Manual will be presented to the Planning Commission for their consideration in the fall or winter 2011.

*Technical Manual.* The Technical Manual includes engineering-related site standards, such as solid waste collection, street design, and detention/retention standards. Staff is responsible for preparing the Technical Manual. The Technical Manual will be presented to the Planning Commission for their consideration in the fall or winter 2011.

The UDC, Administrative Manual, and Technical Manual will eventually replace the codes currently in effect, i.e. the Land Use Code, Development Standards, and Chapter 23A, as the governing zoning regulations within the City of Tucson.

#### Article 4: Zones (Attachment B)

##### *Summary – Article 4:*

- Provides purpose statements for each base zone;
- Identifies the permitted uses and special exception land uses for each zone;
- Establishes use specific standards for certain uses; and,
- Establishes standards for accessory and temporary land uses.

##### *Significant Differences Between the LUC and the Proposed UDC.*

1. The permitted uses, special exception land uses, and use-specific standards have been reorganized into a table format; and,
2. The permitted use table has been expanded to include subtypes, which are currently not easily identifiable in the LUC.

*Issue Requiring Further Consideration.* [Note: The following are issues raised by staff and stakeholders during the initial review of each article. Revisions to future drafts of these articles may be made to address these issues if the revision is within the scope of this project and is not controversial. Those issues not addressed through the UDC process will be documented for possible amendments after the UDC is adopted.]

1. Relocate the general restrictions and exceptions currently in the purpose statement section of Article 4 to the Use-Specific Standard section or another section where they will be more visible (Staff);
2. The proposed tables are easier to read; however, the tables need to indicate when other restrictions or compatibility requirements apply (Staff & LUC Committee);
3. Clarify the term “family dwelling” in the permitted use table so that users can more easily determine whether single- and/or multi-family are permitted (Staff);
4. Update the development standards pertaining to assisted living facilities to reflect changes in the market (LUC Committee);
5. Consider putting the definitions of uses in Article 4 so that all use-related information is consolidated into one section; and therefore, reduces the need to cross-reference (LUC Committee member);
6. Revise dimensional use-specific standards as needed when the numbers in Article 6 are finalized (Staff); and,
7. Evaluate use-specific standards for possible revision or deletion of overly restrictive, difficult to enforce, or outdated standards (Staff and LUC Committee).

Article 6: Dimensional Standards and Measurements (Attachment C)

*Purpose* – Article 6 provides the general dimensional standards that apply to principal and accessory structures for each zoning district in the city and the method for measuring the dimensional standards to ensure consistent application of the standards.

*Significant Differences Between the LUC and the Proposed UDC.*

1. The Development Designator is proposed to be replaced with zone-based dimensional standards (see below for more details);
2. The current method for calculating residential density is not included in the UDC because it reflects the Development Designator system;
3. The design features included in calculating lot coverage is simplified in the proposal to include roofed buildings and structures only. The proposal no longer includes vehicle use areas (e.g. driveways) in the calculation. To compensate for this, the proposal reduces maximum permitted lot coverage by 5%;
4. The method for measuring building height is proposed to be changed from design grade elevation to average finished grade. The proposed method is the same as that used by Pima County, which has proven to be far less problematic than the method the City currently uses;
5. The term “perimeter yard” is proposed to be replaced with “side, rear, and front yard”;
6. Setbacks from street simplified [e.g. established and developing area distinctions no longer required; measured from property line or future MS&R ROW line, whichever is applicable, rather than current requirement (i.e. back of curb or outside edge of the nearest adjacent travel lane)]; and,

7. The proposal introduces a Development Compatibility Standards to mitigate more intense use when adjacent to certain residential uses (see below for more details).

*Summary of the Proposed Zone-Based Dimensional Standards* – Currently, a project’s dimensional standards are based on the proposed use via the use’s Development Designator. The Development Designator makes redevelopment and changes of use problematic and overly complicated because fine distinctions are made between uses. To address these issues, dimensional standards based on the project’s zone are being proposed to replace the Development Designator. A zone-based dimensional standard is the conventional method used by most cities;

The proposed dimensional standards are based on an evaluation of the dimensional standards in effect prior to the LUC when a zone-based method was used and the Development Designator (or close approximation) representing a majority of the permitted uses in each zone.

When the Development Designator for a particular use is significantly different from the proposed zone-based dimensional standard, the current designator standard will be incorporated into the use-specific standards (i.e. exceptions to the zone-based dimensional standard).

A comparison of the current and proposed dimensional standards using hypothetical examples is attached (Attachment D).

*Summary of the Proposed Development Compatibility Standards* – Staff proposes the addition of Development Compatibility Standards to mitigate excessive visual, noise, odor, vibration intrusion, and other similar public health and safety concerns that may be created by new development projects on adjacent, existing residential properties.

The proposed Development Compatibility Standards apply as follows:

1. Except within a UOD, IID, PAD, PCD, or FLD, the Development Compatibility Standards of this section shall apply when the proposed development is adjacent to attached dwelling units (e.g. townhouses and condominiums) in a subdivision or a detached dwelling unit. For the purposes of this section, these types of dwelling units are referred to as “affected properties”; and,
2. For projects within a UOD, IID, PAD, PCD, or FLD, the Development Compatibility Standards shall apply only when the proposed development is adjacent to affected properties outside the planned development or subdivision boundaries.

When applicable, projects are required to comply with the following:

1. The proposed project's setback from the affected property line shall be increased by 1' for every 1' of height the project is greater than 20'; and,
2. When less than 30 feet from the affected property line, the following is required of the proposed structure:
  - A. Windows on upper floors shall be located or treated to reduce views into adjacent affected property; and,
  - B. Balconies shall be oriented away from the affected property or screened.
3. Loading zones, garbage disposal facilities, parking lots, outdoor dining areas, and other potential nuisance areas shall be mitigated using screening, orienting the nuisance away from affected properties, or other architectural or landscaping treatments.

*Issues with Article 6 Requiring Further Consideration.* [Note: The following are issues raised by staff and stakeholders during the initial review of each article. Revisions to future drafts of these articles may be made to address these issues if the revision is within the scope of this project and is not controversial. Those issues not addressed through the UDC process will be documented for possible amendments to adopted UDC.]

1. Add and clarify dimensional standards for non-residential uses permitted in residential zones;
2. Clarify in table when the standard is based on number of units permitted by lot or residential density;
3. Should the residential density measurement criteria be included;
4. Clarify applicability of the DCS (Staff): 1) Revise to clarify the DCS does not apply within new planned subdivisions; 2) Townhouses and condos should not trigger the DCS because they typically serve as the transition (i.e. buffer) between single-family detached and non-residential uses. The DCS shouldn't apply in all situations, particularly when they will impede or further constrain infill development such as along corridors where lots are already difficult to redevelop because of shallow lot size (LUC Committee member);
5. The DCS restrictions are not adequately counterbalanced by incentives (LUC Committee members);
6. Add and clarify dimensional standards for non-residential uses permitted in residential zones (Staff);
7. Clarify in table when the standard is based on number of units permitted by lot or residential density (Staff);
8. Further simplify the average finished grade height measurement method to take elevation readings from the corners of the proposed structure only rather than at 5' intervals around the perimeter of the structure (LUC Committee);
9. Maximum permitted wall/fence height when two abutting properties the wall/fence is separating have different elevations (LUC Committee member);
10. The front yard setback for uses along major corridors should be revised to 0' to facilitate transit- and pedestrian-oriented development (LUC Committee);

11. A more gradual increase in building heights from the commercial (75' in C-3) to OCR zones (140' in OCR-1) is needed. (LUC Committee); and,
12. Revise the Principal Land Use (Sec. 6.6) section to distinguish how the standards apply for "horizontal" and "vertical" projects (Staff);

**Attachments:**

Attachment A – Summary of the Unified Development Code

Attachment B – Article 4: Zones (October Draft)

Attachment C – Article 6: Dimensional Standards and Measurements (October Draft)


Attachment D – Comparison Between the Development Designator and Proposed Zone-Based Dimensional Standards

S:\Land Use Code Revision\UDC\Planning Commission

## ATTACHMENT A


### Summary of the Unified Development Code

Article	Title
1	<b>General Provisions</b> (scope/applicability, severability, relationship to other ordinances, etc.)
2	<b>Review Authorities</b> (who makes decisions, scope of powers of decision-making bodies with summary table)
3	<b>General Procedures</b> (procedures for each review or permit type, e.g., rezonings and variances, with summary tables and flow charts)
4	<b>Zones</b> (listing of all zoning districts, permitted uses, use specific standards, accessory and temporary uses)
5	<b>Overlay Zones</b> (standards for special overlays)
6	<b>Dimensional Standards and Measurements</b> (height, setback, and similar dimensions; rules for measurements)
7	<b>Development Standards</b> (standards such as parking, loading, landscaping, native plant preservation)
8	<b>Subdivision Standards</b> (standards for subdivisions)
9	<b>Nonconformities</b> (provisions for nonconforming uses, structures, and lots)
10	<b>Enforcement and Penalties</b> (zoning enforcement standards and procedures)
11	<b>Definitions and Rules of Construction</b> (comprehensive set of definitions for use classes and other items)



**ATTACHMENT B**

**ARTICLE 4: ZONES**



**CITY OF TUCSON  
UNIFIED DEVELOPMENT CODE**

**PRELIMINARY FINAL PUBLIC DRAFT – OCTOBER 2011**

**CONTENTS**

**ARTICLE 4: ZONES**

<b>4.1. PURPOSE .....</b>	<b>5</b>
<b>4.2. ESTABLISHMENT OF BOUNDARIES.....</b>	<b>5</b>
<b>4.3. CATEGORIES OF LAND USES.....</b>	<b>5</b>
4.3.1. Permitted Land Uses.....	5
4.3.2. Special Exception Land Uses.....	5
4.3.3. Accessory Land Uses .....	5
<b>4.4. ORGANIZATION OF LAND USES .....</b>	<b>5</b>
<b>4.5. MORE RESTRICTIVE ZONING .....</b>	<b>6</b>
<b>4.6. ZONING OF LAND ANNEXED INTO THE CITY .....</b>	<b>7</b>
<b>4.7. BASE ZONES.....</b>	<b>7</b>
4.7.1. Institutional Reserve (IR).....	7
A. Purpose .....	7
B. Exceptions.....	7
4.7.2. Rural Homestead Zone (RH) .....	7
A. Purpose .....	7
B. Exceptions.....	7
4.7.3. Suburban Ranch Zone (SR) .....	8
A. Purpose .....	8
4.7.4. Suburban Homestead Zone (SH) .....	8
A. Purpose .....	8
4.7.5. Residence Zone (RX-1) .....	8
A. Purpose .....	8
4.7.6. Residence Zone (RX-2) .....	8
A. Purpose .....	8
4.7.7. Residence Zone (R-1).....	8
A. Purpose .....	8
4.7.8. Residence Zone (R-2).....	8
A. Purpose .....	8
4.7.9. Residence Zone (R-3).....	9
A. Purpose .....	9
4.7.10. Mobile Home Zone (MH-1) .....	9
A. Purpose .....	9
4.7.11. Mobile Home Zone (MH-2) .....	9
A. Purpose .....	9
4.7.12. Office Zone (O-1).....	9
A. Purpose .....	9
B. General Restrictions .....	9
4.7.13. Office Zone (O-2).....	10
A. Purpose .....	10

B.	General Restrictions .....	10
<b>4.7.14.</b>	<b>Office Zone (O-3).....</b>	<b>10</b>
A.	Purpose .....	10
B.	General Restrictions .....	11
<b>4.7.15.</b>	<b>Rural Village Center Zone (RVC) .....</b>	<b>11</b>
A.	Purpose .....	11
B.	General Restrictions .....	11
<b>4.7.16.</b>	<b>Neighborhood Commercial Zone (NC).....</b>	<b>12</b>
A.	Purpose .....	12
B.	General Restrictions .....	12
C.	Exception .....	12
<b>4.7.17.</b>	<b>Commercial Zone (C-1).....</b>	<b>12</b>
A.	Purpose .....	12
B.	General Restrictions .....	12
<b>4.7.18.</b>	<b>Commercial Zone (C-2).....</b>	<b>13</b>
A.	Purpose .....	13
B.	General Restrictions .....	13
<b>4.7.19.</b>	<b>Commercial Zone (C-3).....</b>	<b>13</b>
A.	Purpose .....	13
<b>4.7.20.</b>	<b>Parking Zone (P).....</b>	<b>13</b>
A.	Purpose .....	13
<b>4.7.21.</b>	<b>Recreational Vehicle Zone (RV).....</b>	<b>13</b>
A.	Purpose .....	13
B.	General Restrictions .....	14
<b>4.7.22.</b>	<b>Office/Commercial/Residential Zone (OCR-1).....</b>	<b>14</b>
A.	Purpose .....	14
<b>4.7.23.</b>	<b>Office/Commercial/Residential Zone (OCR-2).....</b>	<b>14</b>
A.	Purpose .....	14
<b>4.7.24.</b>	<b>Mixed Use Zone (MU).....</b>	<b>14</b>
A.	Purpose .....	14
<b>4.7.25.</b>	<b>Park Industrial Zone (P-1).....</b>	<b>14</b>
A.	Purpose .....	14
B.	General Restrictions .....	14
<b>4.7.26.</b>	<b>Light Industrial Zone (I-1).....</b>	<b>15</b>
A.	Purpose .....	15
B.	General Restrictions .....	15
<b>4.7.27.</b>	<b>Heavy Industrial Zone (I-2).....</b>	<b>15</b>
A.	Purpose .....	15
B.	General Restrictions .....	15
<b>4.7.28.</b>	<b>Open Space Zone (OS).....</b>	<b>16</b>
A.	Purpose .....	16
B.	Applicability .....	16
C.	General Restrictions .....	17
D.	Open Space Requirements .....	17
<b>4.8.</b>	<b>USE TABLE.....</b>	<b>18</b>
<b>4.8.1.</b>	<b>Permitted Uses: Rural and Suburban Residential Zones .....</b>	<b>19</b>
<b>4.8.2.</b>	<b>Permitted Uses: Urban Residential Zones .....</b>	<b>23</b>
<b>4.8.3.</b>	<b>Permitted Uses: Special Purpose Zones .....</b>	<b>26</b>
<b>4.8.4.</b>	<b>Permitted Uses: Commercial Zones.....</b>	<b>29</b>
<b>4.8.5.</b>	<b>Permitted Uses: Office and Mixed use Zones .....</b>	<b>35</b>
<b>4.8.6.</b>	<b>Permitted Uses: Industrial Zones.....</b>	<b>41</b>

<b>4.9.</b>	<b>USE-SPECIFIC STANDARDS</b> .....	<b>46</b>
<b>4.9.1.</b>	<b>General</b> .....	<b>46</b>
	A. Purpose.....	46
	B. Applicability.....	46
<b>4.9.2.</b>	<b>Agricultural Use Group</b> .....	<b>46</b>
	A. Animal Production.....	46
	B. Crop Production.....	47
	C. Stockyard Operation.....	47
<b>4.9.3.</b>	<b>Civic Use Group</b> .....	<b>48</b>
	A. Cemetery.....	48
	B. Correctional Use.....	48
	C. Cultural Use.....	49
	D. Educational Uses.....	50
	E. Postsecondary Institutions.....	51
	F. Religious Use.....	51
<b>4.9.4.</b>	<b>Commercial Services Use Group</b> .....	<b>52</b>
	A. Administrative and Professional Office.....	52
	B. Adult Day Care.....	52
	C. Alcoholic Beverage Service and Entertainment (Bar).....	52
	D. Animal Service.....	53
	E. Artisan Residence.....	53
	F. Automotive - Service and Repair (Major and Minor).....	54
	G. Billboards.....	54
	H. Child Care in Residential and Office Zones.....	55
	I. Communications.....	57
	J. Construction Service.....	57
	K. Entertainment.....	57
	L. Financial Service.....	58
	M. Food Service (Restaurant).....	58
	N. Funeral Service.....	59
	O. Medical Service.....	59
	P. Medical Service in Residential and Office Zones.....	59
	Q. Major Medical Service and Outpatient Medical Service, Accessory.....	60
	R. Office Zone Compatibility Standards.....	60
	S. "P" Parking Zone Standards.....	60
	T. Personal Service.....	60
	U. Research and Product Development.....	61
	V. Restaurant with accessory Bar.....	61
	W. Technical Service.....	62
	X. Trade Service and Repair (Major and Minor).....	62
	Y. Transportation Service, Air Carrier.....	62
	Z. Travelers' Accommodation, Campsite.....	63
	AA. Travelers' Accommodations, Lodging.....	63
	BB. Travelers' Accommodation, Lodging, Accessory Uses.....	63
<b>4.9.5.</b>	<b>Industrial Use Group</b> .....	<b>65</b>
	A. Craftwork Manufacturing.....	65
	B. Extraction.....	65
	C. Manufacturing and Industrial (General, Heavy Equipment, Precision, Primary)....	65
	D. Motion Picture Industry.....	66
	E. Perishable Goods Manufacturing.....	67
	F. Radioactive Materials Restrictions.....	67
	G. Salvaging and Recycling.....	67

4.9.6. Recreation Use Group .....	69
A. Golf Course .....	69
B. Commercial Recreation.....	70
4.9.7. Residential Use Group .....	71
A. Artist Studio/Residence in I-1 .....	71
B. Family Dwelling.....	71
C. Family Dwelling / Mobile Home Dwelling as Accessory Use in Industrial Zones...	72
D. Home Occupation: Day Care.....	72
E. Home Occupation: General Application.....	73
F. Home Occupation: Group Dwelling.....	74
G. Home Occupation: Travelers' Accommodation, Lodging .....	74
H. Mobile Home Dwelling Accessory Uses.....	75
I. Residential Care Services .....	76
4.9.8. Restricted Adult Activities Use Group .....	78
A. Restricted Adult Activities.....	78
4.9.9. Retail Trade Use Group .....	78
A. Food and Beverage Sales .....	78
B. General Merchandise Sales .....	79
C. Heavy Equipment Sales.....	79
D. Large Retail Establishment Design Standards.....	79
E. Medical Marijuana.....	84
F. Swap Meets and Auctions.....	87
G. Vehicle Rental and Sales.....	87
4.9.10. Storage Use Group .....	88
A. Commercial Storage .....	88
B. Hazardous Material Storage.....	88
C. Personal Storage .....	89
4.9.11. Utilities Use Group .....	90
A. Distribution System .....	90
B. Renewable Energy Generation .....	90
C. Sanitation System .....	92
4.9.12. Wholesaling Use Group .....	92
4.9.13. Generally Applied Standards .....	92
A. Access.....	92
B. Hours .....	92
C. Lighting .....	92
D. Noise .....	92
E. Outdoor Activity.....	92
F. Screening.....	92
<b>4.10. ACCESSORY USES AND BUILDINGS .....</b>	<b>93</b>
4.10.1. Accessory Uses .....	93
4.10.2. Accessory Buildings.....	93
4.10.3. Specifically Within Residential Zones .....	93
4.10.4. Specifically Within Nonresidential Zones.....	94
<b>4.11. TEMPORARY USE OR BUILDING.....</b>	<b>95</b>
4.11.1. Qualification for Permit.....	95
4.11.2. Bond Required .....	96
4.11.3. Refund .....	96
4.11.4. Removal.....	96
4.11.5. Forfeiture.....	96
4.11.6. Time Limit .....	96

---

## ARTICLE 4: ZONES

---

### 4.1. PURPOSE

The Zones described in this article are established to regulate and separate the locations of land uses as appropriate.

### 4.2. ESTABLISHMENT OF BOUNDARIES

The boundaries of each zone shall be determined and defined in accordance with the provisions of the Unified Development Code (UDC).

### 4.3. CATEGORIES OF LAND USES

Each zone allows for three categories of land uses: permitted land uses, special exception land uses, and accessory land uses.

#### 4.3.1. PERMITTED LAND USES

The permitted land uses for each zone are identified in Tables 4.8-1 through 4.8-6. These permitted land uses are subject to Article 6: Dimensional Standards and Measurements, Article 7: Development Standards and any additional conditions listed for each use in this code.

#### 4.3.2. SPECIAL EXCEPTION LAND USES

Special exception land uses for each zone are identified in Tables 4.8-1 through 4.8-6. Special exception land uses shall be approved through a Special Exception Land Use procedure if the use complies with all applicable requirements of Article 6: Dimensional Standards and Measurements, Article 7: Development Standards and any additional conditions listed for the use in this code.

#### 4.3.3. ACCESSORY LAND USES

The general standards applicable to accessory uses and buildings are contained in Sec. 4.10. Uses permitted as accessory land uses shall be those that are incidental to, subordinate to, or necessary for the operation of the principal permitted land use. Accessory uses shall be developed according to the same development requirements as the Principal Use, except as modified by applicable use-specific standards in Sec. 4.9 and the provisions of Sec. 4.10. All proposed applications for accessory uses shall be submitted for zoning compliance review and approval. Examples of accessory uses include: residences with guest houses, restaurants with bars, and churches with columbarium.

### 4.4. ORGANIZATION OF LAND USES

The permitted and special exception land use categories are organized by Land Use Group, Land Use Class, and Land Use Type. The Land Use Group identifies the primary activity for informational referencing. The Land Use Class and Land Use Type (if any), listed under the Land Use Group, identify permitted uses within each zone. Land Use Groups are defined in Article 11 of the UDC.

#### **4.5. MORE RESTRICTIVE ZONING**

Within the UDC, reference is made to "more restrictive zoning" in applying development standards. For the purpose of application, this phrase shall apply in the following order, which lists the zones from the most restrictive (OS) to the least restrictive (I-2).

- "OS" Open Space Zone
- "IR" Institutional Reserve Zone
- "RH" Rural Homestead Zone
- "SR" Suburban Ranch Zone
- "SH" Suburban Homestead Zone
- "RX-1" Residence Zone
- "RX-2" Residence Zone
- "R-1" Residence Zone
- "R-2" Residence Zone
- "MH-1" Mobile Home Zone
- "MH-2" Mobile Home Zone
- "R-3" Residence Zone
- "O-1" Office Zone
- "O-2" Office Zone
- "O-3" Office Zone
- "P" Parking Zone
- "RV" Recreational Vehicle Zone
- "NC" Neighborhood Commercial Zone
- "RVC" Rural Village Center Zone
- "C-1" Commercial Zone
- "C-2" Commercial Zone
- "C-3" Commercial Zone
- "MU" Mixed Use Zone
- "OCR-1" Office/Commercial/Residential Zone
- "OCR-2" Office/Commercial/Residential Zone
- "P-I" Park Industrial Zone
- "I-1" Light Industrial Zone
- "I-2" Heavy Industrial Zone

#### **4.6. ZONING OF LAND ANNEXED INTO THE CITY<sup>1</sup>**

The applicable zoning standards on land annexed into the city, unless otherwise stipulated in the annexation ordinance, shall continue to be the county zoning standards applicable to the property prior to annexation until such time they are replaced by city standards. City zoning standards shall be placed on annexed land within six months of the date of annexation. Zoning standards, zones, overlay zones, and City Zoning Maps are extended to the annexed land through a Mayor and Council Special Exception Procedure, Sec. 3.xxx.

#### **4.7. BASE ZONES**

The following base zones and specific standards are established in the city.

##### **4.7.1. INSTITUTIONAL RESERVE (IR)**

###### **A. Purpose**

The purpose of this zone is to identify lands in federal, state, city, county, and other public ownership that are natural reserves or wildlife refuge reserves. It is expected that these lands will remain reserves. However, should these lands be proposed for development with other land uses, the following standards apply. This zone is solely to provide comparable zoning for annexed areas and is not intended for rezoning.

###### **B. Exceptions**

Parcels of less than 36 acres, recorded prior to December 1, 1985, conforming to the minimum lot size requirements in effect on the date of recording, shall be deemed non-conforming.

##### **4.7.2. RURAL HOMESTEAD ZONE (RH)**

###### **A. Purpose**

This zone is intended to preserve the character and encourage the orderly growth of rural areas. It is intended to encourage rural development in areas lacking facilities for urban development and to provide for commercial and industrial development only where appropriate and necessary to serve the needs of the rural area. This zone is solely to provide comparable zoning for annexed areas and is not intended for rezoning.

###### **B. Exceptions**

Parcels of less than 180,000 square feet, recorded prior to December 1, 1985, conforming to the minimum parcel size requirements at the date of recording, shall be deemed non-conforming.

<sup>1</sup> Text from LUC Sec. 1.2.9.

<sup>3</sup> Text from LUC Sec. 2.2.4.1.

**4.7.3. SUBURBAN RANCH ZONE (SR)<sup>3</sup>**

**A. Purpose**

This zone provides for very low density, large lot, single-family, residential development and suburban ranch uses. Uses that would adversely affect the open space, agricultural, or natural characteristics of this zone shall not be permitted.

**4.7.4. SUBURBAN HOMESTEAD ZONE (SH)<sup>4</sup>**

**A. Purpose**

This zone provides for low density, large lot, single-family, residential development and suburban ranch uses. This zone is solely to provide comparable zoning for annexed areas and is not intended for rezoning.

**B. General Restrictions**

Buildings and structures used for the Motion Picture Industry Use must be setback at least 100 feet from the boundary of the site.

**4.7.5. RESIDENCE ZONE (RX-1)<sup>5</sup>**

**A. Purpose**

This zone provides for suburban, low density, single-family, residential development and other compatible neighborhood uses.

**4.7.6. RESIDENCE ZONE (RX-2)<sup>6</sup>**

**A. Purpose**

This zone provides for suburban, low density, single-family, residential development and other compatible neighborhood uses.

**4.7.7. RESIDENCE ZONE (R-1)<sup>7</sup>**

**A. Purpose**

This zone provides for urban, low density, single-family, residential development, together with schools, parks, and other public services necessary for a satisfactory urban residential environment.

**4.7.8. RESIDENCE ZONE (R-2)<sup>8</sup>**

**A. Purpose**

This zone provides for medium density, single-family and multifamily, residential development, together with schools, parks, and other public services necessary for an urban residential environment.

---

<sup>4</sup> Text from LUC Sec. 2.2.6.1.

<sup>5</sup> Text from LUC Sec. 2.3.2.1.

<sup>6</sup> Text from LUC Sec. 2.3.3.1.

<sup>7</sup> Text from LUC Sec. 2.3.4.1.

<sup>8</sup> Text from LUC Sec. 2.3.5.1.

**4.7.9. RESIDENCE ZONE (R-3)<sup>9</sup>**

**A. Purpose**

This zone provides for high density, residential development and compatible uses.

**4.7.10. MOBILE HOME ZONE (MH-1)<sup>10</sup>**

**A. Purpose**

This zone provides for low to medium density, residential development primarily in mobile home buildings on individual lots and within mobile home parks. Civic, educational, recreational, and religious uses shall also be permitted to provide for an urban residential environment.

**4.7.11. MOBILE HOME ZONE (MH-2)<sup>11</sup>**

**A. Purpose**

This zone provides for medium density, residential development in mobile home buildings on individual lots and within mobile home parks. Civic, educational, recreational, and religious uses shall also be permitted to provide for an urban residential environment.

**4.7.12. OFFICE ZONE (O-1)<sup>12</sup>**

**A. Purpose**

This zone provides for administrative and professional office uses that will complement the residential environment. Development within this zone typically consists of office conversions from existing residential uses fronting on major streets and new construction of small-scale office projects. Consolidation of lots is encouraged in order to reduce curb cuts on arterial streets and to assure compliance with the design and development standards of this zone.

**B. General Restrictions<sup>13</sup>**

The following restrictions shall apply to all uses and development in this zone.

1. Drive-through services shall not be permitted.
2. All land use activities, except vehicular use areas, shall be conducted entirely within an enclosed building unless specifically provided otherwise.
3. All **nonresidential** land use activities shall:
  - a. Restrict hours of operation from 7:00 a.m. to 10:00 p.m.
  - b. Comply with the requirements of the Tucson Code, Chapter 6, Section 6-101, Outdoor Lighting Code. Outdoor lighting utilized in conjunction with the use shall be located and directed so as to eliminate glare toward streets and adjoining R-3 or more restrictive zoning.

<sup>9</sup> Text from LUC Sec. 2.3.6.1.

<sup>10</sup> Text from LUC Sec. 2.3.7.1.

<sup>11</sup> Text from LUC Sec. 2.3.8.1.

<sup>12</sup> Text from LUC Sec. 2.4.1.1.

<sup>13</sup> Text from LUC Sec. 2.4.1.6.

- c. Comply with the requirements of the Tucson Code, Chapter 16, Section 16-31, Noise, and be located within an enclosed building. There shall be no openings on the side of the building adjacent to R-3 or more restrictive zoning.

**4.7.13. OFFICE ZONE (O-2)<sup>14</sup>**

**A. Purpose**

This zone provides for office, medical, civic, and other land uses that provide reasonable compatibility with adjoining residential uses. Typical development within this zone is two-story office or medical projects.

**B. General Restrictions**

The following restrictions shall apply to all uses and development in this zone.

1. Drive-through services shall not be permitted.
2. All land use activities, except vehicular use areas, shall be conducted entirely within an enclosed building unless specifically provided otherwise.
3. All **nonresidential** land uses shall:
  - a. Provide access from a paved public street on the Major Streets and Routes (MS&R) Plan.
  - b. Restrict hours of operation from 7:00 a.m. to 10:00 p.m.
  - c. Comply with the requirements of the Tucson Code, Chapter 6, Section 6-101, Outdoor Lighting Code. Any outdoor lighting utilized in conjunction with the use shall be located and directed so as to eliminate glare toward streets and adjoining R-3 or more restrictive zoning.
  - d. Comply with the requirements of the Tucson Code, Chapter 16, Section 16-31, Noise, and be located within an enclosed building with no openings on the side of the building adjacent to R-3 or more restrictive zoning.

**4.7.14. OFFICE ZONE (O-3)<sup>15</sup>**

**A. Purpose**

This zone provides for mid-rise office development and other land uses that provide reasonable compatibility with adjoining residential uses.

<sup>14</sup> Text from LUC Sec. 2.4.2.1.

<sup>15</sup> Text from LUC Sec. 2.4.3.1.

**B. General Restrictions<sup>16</sup>**

The following restrictions shall apply to all uses and development in this zone.

1. Drive-through services shall not be permitted.
2. All land use activities, except vehicular use areas, shall be conducted entirely within an enclosed building unless specifically provided otherwise.

**4.7.15. RURAL VILLAGE CENTER ZONE (RVC)<sup>17</sup>**

**A. Purpose**

The purpose of this zone is to provide retail shopping facilities, planned and designed for the convenience and necessity of a suburban or rural neighborhood. Rural village centers shall be developed according to an approved site plan and located in accordance with adopted neighborhood, community, or area plans. The standards are designed to maintain the suburban character of duly designated commercial areas located along designated Scenic Routes and to provide safe ingress and egress to and from the village center. This zone is solely to provide for comparable zoning for areas annexed into the City limits and is not intended for rezoning.

**B. General Restrictions**

The following restrictions shall apply to all uses and development in this zone.

1. Drive-through or drive-in services shall not be permitted unless specifically provided for the land use.
2. All land use activities except vehicular use areas shall be conducted entirely within an enclosed building unless specifically provided otherwise.
3. The maximum area of each RVC zone shall not exceed 20 acres.

<sup>16</sup> Text from LUC Sec. 2.4.3.6.

<sup>17</sup> Text from LUC Sec. 2.5.1.1.

**4.7.16. NEIGHBORHOOD COMMERCIAL ZONE (NC)<sup>18</sup>**

**A. Purpose**

This zone provides for low-intensity, small-scale, commercial and office uses that are compatible in size and design with adjacent residential uses. Residential and other related uses shall be permitted.

**B. General Restrictions<sup>19</sup>**

The following standards shall apply to all uses and development in this zone.

1. Drive-through or drive-in services shall not be permitted.
2. All land use activities, except the Residential Use Group, shall be conducted entirely within an enclosed building unless specifically provided otherwise in the Use Specific Standards. Vehicular use areas are not required to be located within enclosed buildings.
3. All land use activities, except the Residential Use Group, shall be restricted to hours of operation of 7:00 a.m. to 10:00 p.m.
4. All nonresidential development and nonresidential exterior remodeling that require a building permit shall be reviewed and approved by the Design Review Board (DRB) for architectural and site design compatibility with the surrounding residential area. Refer to Sec. 4.9.4.R.7 for DRB review standards.
5. All land uses shall be limited to 2,000 square feet of GFA, except Family Dwelling and Educational Uses. Mixed use or multi-tenant developments are limited to 10,000 square feet of GFA. A tenant within a mixed use development is limited to 2,000 square feet of GFA. Outdoor activity areas permitted in this zone shall be included in the GFA limitations.

**C. Exception**

On authorization of rezoning of property to the NC zone, Mayor and Council may approve land uses that will be located in existing buildings or portions thereof that exceed the limitation of 2,000 square feet of gross floor area per use or the limitations restricting mixed use or multi-tenant development to 10,000 square feet of gross floor area. The gross floor area for any such exception shall neither be increased nor enlarged following initial authorization, and the right to exceed the gross floor area restrictions shall be terminated if discontinued or abandoned.

**4.7.17. COMMERCIAL ZONE (C-1)**

**A. Purpose**

This zone provides for low-intensity, commercial and other uses that are compatible with adjacent residential uses. Residential and other related uses shall be permitted.

**B. General Restrictions**

The following restrictions shall apply to all uses and development in this zone.

<sup>18</sup> Text from LUC Sec. 2.5.2.1.

<sup>19</sup> Text from LUC Sec. 2.5.2.6.

1. Drive-through services shall be prohibited except as listed below:
  - a. Commercial Services and Retail Trade Uses may provide one drive-through lane.
  - b. Financial Services Use may provide two drive-through lanes and one Automated Teller Machine (ATM) service lane.
  
2. All land use activities shall be conducted entirely within an enclosed building, except as listed below:
  - a. Civic Use Group: Cemetery, Education Elementary & Secondary Schools;
  - b. Commercial Use Group: Medical Services Extended Health Care;
  - c. Recreation Use Group: Golf Course, Parks and Recreation; and
  - d. Vehicular Use Area.

**4.7.18. COMMERCIAL ZONE (C-2)**

**A. Purpose**

This zone provides for general commercial uses that serve the community and region. Residential and other related uses shall also be permitted.

**B. General Restrictions**

The Land uses in the Commercial Services, Industrial, Restricted Adult Activities, and Wholesaling Use Groups shall be conducted entirely within an enclosed building unless modified by Use Specific Standards.

**4.7.19. COMMERCIAL ZONE (C-3)<sup>22</sup>**

**A. Purpose**

This zone provides for mid-rise development of general commercial uses that serve the community and region, located downtown or in other major activity center areas. Residential and other related uses shall also be permitted.

**4.7.20. PARKING ZONE (P)<sup>23</sup>**

**A. Purpose**

This zone provides for off-street motor vehicle parking within residential areas to serve land uses in another zone.

**4.7.21. RECREATIONAL VEHICLE ZONE (RV)<sup>24</sup>**

**A. Purpose**

---

<sup>22</sup> Text from LUC Sec. 2.5.5.1.

<sup>23</sup> Text from LUC Sec. 2.5.6.1.

<sup>24</sup> Text from LUC Sec. 2.5.7.1.

The purpose of this zone is to provide for development of short-term occupancy recreational vehicle parks and campsites while ensuring reasonable compatibility with adjoining properties by establishing special requirements.

**B. General Restrictions<sup>25</sup>**

Storage buildings shall not be permitted in this zone as accessory to each individual unit space; however, they shall be permitted as part of the common use facility.

**4.7.22. OFFICE/COMMERCIAL/RESIDENTIAL ZONE (OCR-1)<sup>26</sup>**

**A. Purpose**

The purpose of this zone is to provide for high-rise development that serves the community and region and is located in major activity centers or at transit centers. A mixture of development types is encouraged, including office, commercial, and high-density residential uses.

**4.7.23. OFFICE/COMMERCIAL/RESIDENTIAL ZONE (OCR-2)<sup>27</sup>**

**A. Purpose**

The purpose of this zone is to provide for high-rise development that serves the community and region and is located in major activity centers. A mixture of development types is encouraged, including office, commercial, and high-density residential uses.

**4.7.24. MIXED USE ZONE (MU)**

**A. Purpose**

This zone is solely to provide for comparable zoning for areas annexed into the City limits and is not intended for rezoning.

**4.7.25. PARK INDUSTRIAL ZONE (P-1)<sup>29</sup>**

**A. Purpose**

This zone provides for corporate business centers and for wholesaling and manufacturing activities that can be carried on in an unobtrusive, controlled manner.

**B. General Restrictions<sup>30</sup>**

The following restrictions shall apply to land uses and development in this zone.

1. Radioactive Material Restrictions, see Sec. 4.9.5.F.
2. On land uses in the Industrial Use Group, traffic circulation shall be designed so that access to the site is from a major street or from a local street that is not

<sup>25</sup> Text from LUC Sec. 2.5.7.4.

<sup>26</sup> Text from LUC Section 2.6.1.1.

<sup>27</sup> Text from LUC Section 2.6.2.1.

<sup>29</sup> Text from LUC Section 2.7.1.1.

<sup>30</sup> Text from LUC Section 2.7.1.6.

an internal residential neighborhood street and that does not provide access to residentially zoned areas unless no alternative exists.

3. Buildings and structures in the Motion Picture Industry Use must be setback at least 100 feet from the boundary of the site.
4. Accessory Retail trade use is limited to products that are wholesaled, manufactured, or stored on the premises and limited to 25 percent of the total floor area but not to exceed 2,500 square feet in the use groups below:
  - a. Industrial
  - b. Storage
  - c. Wholesaling

**4.7.26. LIGHT INDUSTRIAL ZONE (I-1)** <sup>31</sup>

**A. Purpose**

This zone provides for industrial uses that do not have offensive characteristics in addition to land uses permitted in more restrictive nonresidential zones.

**B. General Restrictions**<sup>32</sup>

The following restrictions shall apply to all land uses and development in this zone.

1. Radioactive Material Restrictions, see Sec. 4.9.5.F.
2. On land uses in the Industrial Use Group, traffic circulation shall be designed so that access to the site is from a major street or from a local street that is not an internal residential neighborhood street and that does not provide access to residentially zoned areas unless no alternative exists.
3. Buildings and structures in the Motion Picture Industry Use must be setback at least 100 feet from the boundary of the site.

**4.7.27. HEAVY INDUSTRIAL ZONE (I-2)** <sup>33</sup>

**A. Purpose**

This zone provides for industrial uses that are generally nuisances, making them incompatible with most other land use. These nuisances may be in the form of air pollutants; excessive noise, traffic, glare, or vibration; noxious odors; the use of hazardous materials; or unsightly appearance.

**B. General Restrictions**<sup>34</sup>

The following restrictions shall apply to all land uses and development in this zone.

1. Radioactive Material Restrictions, see Sec. 4.9.5.F.
2. On land uses in the Industrial Use Group, traffic circulation shall be designed so that access to the site is from a major street or from a local street that is not

<sup>31</sup> Text from LUC Section 2.7.2.1.

<sup>32</sup> Text from LUC Section 2.7.2.6.

<sup>33</sup> Text from LUC Section 2.7.3.1.

<sup>34</sup> Text from LUC Section 2.7.3.6.

an internal residential neighborhood street and that does not provide access to residentially zoned areas unless no alternative exists.

3. The uses listed below must be at least 300 feet from any non-industrial zone, except where the use of the non-industrial zone property is railroad or freeway right-of-way:
  - a. Extraction
  - b. Hazardous Material Manufacturing
  - c. Perishable Good Manufacturing
  - d. Primary Manufacturing
  - e. Refining
  - f. Salvaging and Recycling

#### 4.7.28. OPEN SPACE ZONE (OS)

##### A. Purpose<sup>35</sup>

The purpose of the Open Space (OS) zone is to designate both public and private open space resources in order to:

1. Preserve significant natural resources and open spaces, such as areas of undisturbed native vegetation, major rock outcrops, major ridges and peaks, riparian habitats, and valuable vegetated wash segments.
2. Promote restoration of open space to provide visual, recreational, and habitat amenities.
3. Preserve vestiges of the natural desert landscape and provide opportunities for hiking, horseback riding, bicycling, and more passive recreation in a natural setting.
4. Contribute to the preservation of wildlife habitat, especially interconnected areas that foster the free movement of wildlife within the city.
5. Promote a continued economic benefit to the region by protecting open space areas for the visual and recreational enjoyment of residents and visitors alike.
6. Provide a mechanism for recognizing and protecting public and private lands that have been designated for preservation by the property owner.

##### B. Applicability<sup>36</sup>

The OS zone may be applied to both public and private lands that warrant protection as open space. The OS zone may be applied to land only with the express written consent of the property owner(s).

<sup>35</sup> Text from LUC Section 2.9.1.1.

<sup>36</sup> Text from LUC Section 2.9.1.2.

**1. Dedications and Donations**

The OS zone may be applied by the City to land that is preserved by acquisition, an easement, or dedication, and/or donation to the City or other entity, for the purpose of keeping the land as permanent natural open space.

**2. Fee Waiver**

Fees for a rezoning application to the OS zone shall be waived.

**C. General Restrictions<sup>37</sup>**

The following restrictions shall apply to all land uses and development in this zone.

1. Unpaved or paved trails or paths shall be permitted for use only by pedestrians, non-motorized bicycles, and horses. Limited access is permitted for maintenance vehicles only. Use by all-terrain vehicles is prohibited.
2. Picnic areas, sitting areas, equestrian trail nodes, scenic lookouts, shade structures, and rest rooms shall be permitted, subject to minimal disturbance of the natural open space. Grills in the picnic areas and overnight camping are not permitted, unless located in an area that fire vehicles can access without impact on the natural open space.
3. Access driveways and parking areas shall be permitted in conjunction with the Open Space Requirements in Sec. 4.7.28.D.1 and 2, subject to minimal disturbance of the natural open space.
4. Drainage-way facilities and utility easements shall be re-vegetated to be consistent with the surrounding natural vegetation.
5. All new utilities shall be underground.

**D. Open Space Requirements<sup>38</sup>**

1. The disturbed area shall be clearly identified and the balance of the property protected during construction. All impervious surfaces, buildings, utility or drainage corridors, and structures shall be contained within the disturbed area identified on the approved site plan.
2. Whenever a portion of the property is disturbed by the construction of a permitted use or has been cleared of vegetation, the disturbed area shall be re-vegetated in conformance with an approved re-vegetation plan using plants native to the site and the immediately surrounding area. Re-vegetation shall be at a similar density to the natural surroundings.
3. The minimum width of property zoned OS shall be 40 feet, and the minimum contiguous area for OS is 4,000 square feet, unless the OS property connects to another perpetual, dedicated open space or trails resource.

<sup>37</sup> Text from LUC Section 2.9.1.4.

<sup>38</sup> Text from LUC Section 2.9.1.5.

#### **4.8. USE TABLE**

The following use tables, Tables 4.8-1 through 4.8-6, establishes permitted and special exceptions uses in the City of Tucson. Use-specific standards that apply to uses in certain zones are included in the far right column of each table.

Land Use Groups are further defined to include Land Use Classes and Land Use Types. For example, the "Civic Land Use Group" may contain multiple "Correctional Use" Land Use Classes. The "Correctional Use" Class may contain "Supervision Facilities" or "Custodial Facilities" Land Use Types. The differentiation of types allows for increased use-specific standards and dimensional standards.

DRAFT

4.8.1. PERMITTED USES: RURAL AND SUBURBAN RESIDENTIAL ZONES

<b>TABLE 4.8-1: PERMITTED USES– RURAL AND SUBURBAN RESIDENTIAL ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
LAND USE	RH	SR	SH	RX-1	RX-2	USE SPECIFIC STANDARDS
<b>Agricultural Land Use Group With Land Use Class/Type:</b>						
Animal Production (Excludes Stockyard)	P	P	P	P		RH: 4.9.2.A.1.a, 2.b,3.b SR: 4.9.2.A.1.a, 2.b,3.a SH: 4.9.2.A.1.b, 2.b, 2.c, 3.b RX-1: 4.9.2.A.1.a, 2.a, 2.b., 3.a
Animal Production Commercial Stables Only		P	P			SR: 4.9.2.A.1.b, 2.b SH: 4.9.2.A.1.b, 2.c
Animal Production Hog Ranch Only	S [1]					RH: 4.9.2.A.3.d
Animal Production Feedlot for Stockyard Only	S [1]					RH: 4.9.2.C.1
Animal Production Stable or Riding School Only	P					RH: 4.9.2.A.1.b, 2.b, 4.b
Crop Production	P	P	P	P	P	RH, SR, SH, RX-1, RX-2: 4.9.2.B.1
Crop Production with accessory Food & Beverage Sales	P	P	P			4.9.2.B.1 and RH: 4.9.9.A.2.a, 3-8 SR, SH: 4.9.9.A.1, 2.c, 3, 4, 7
General Farming	P	P	P	P		4.9.2.B.1 and: RH: 4.9.2.A.1.a, 2.b, 3.b SR: 4.9.2.A.1.a, 2.b, 3.a SH: 4.9.2.A.1.b, 2.b, 2.c, 3.b RX-1: 4.9.2.A.1.b, 2.a, 2.b, 3.a
<b>Civic Land Use Group With Land Use Class/Type:</b>						
Cemetery	S [1]		S [1]			RH: 4.9.3.A.3 SH: 4.9.3.A.2
Correctional Supervision Facility		S [1]				4.9.3.B.1.b, 2.a, 3.a, 4.a, 8 & 9
Correctional Custodial Facility		S [1]				4.9.3.B.1.c, 2.a, 3.a, 4.b, 8 & 9
Correctional Supervision & Custodial		S [1]				4.9.3.B.1.d, 2.c, 3.b, 4.b, 7, 8, & 9
Cultural	P	G	G	G	G	RH: Limited to Nature Reserve
Cultural (excludes Nature Reserve & Wildlife Refuge)	S [1]					RH: 4.9.3.C
Educational Elementary & Secondary School		P	P	P	P	SR, SH, RX-1, RX-2: 4.9.3.D
Educational Elementary & Secondary School	S [2]					
Educational Elementary & Secondary School with accessory Salvaging and Recycling		P	P	P	P	SR, SH, RX-1, RX-2: 4.9.3.D. & 4.9.5.G.1 & 3
Protective Service	G	G	G	G	G	RH, SR, SH, RX-1, RX-2: 4.9.13.F

<b>TABLE 4.8-1: PERMITTED USES- RURAL AND SUBURBAN RESIDENTIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
LAND USE	RH	SR	SH	RX-1	RX-2	USE SPECIFIC STANDARDS
Religious	P	P	P	P	P	RH: Use shall be 80' from any property line.
Religious with accessory Columbarium	P	P	P		P	RH: Use shall be 80' from any property line.
Religious with accessory Salvaging and Recycling	P	P	P		P	RH: Use shall be 80' from any property line and 4.9.5.G.1 & 3 SR, SH, RX-2: 4.9.5.G.1 & 3
<b>Commercial Services Land Use Group With Land Use Class/Type:</b>						
Administrative and Professional Office	S [1]					RH: Maximum floor area of 2,000 square feet.
Alcoholic Beverage Service	S [1]					RH: Maximum floor area of 2,000 square feet.
Animal Service		P	P			SR, SH: Use shall be setback 100' from any residentially zoned property.
Animal Service Commercial Kennel Only	S [1]					RH: Use shall be setback 100' from any property line.
Animal Service Veterinary Hospital Only	P					RH: No outdoor activity and use shall be setback 100' from any residentially zoned property.
Automotive Service Repair Excludes bodywork & paint-booths	S [1]					RH: 4.9.4.F.1, 6 and must have access from a paved public street on MS&R
Child Care With Extended Hours (before 6:00 am or after 7:00 pm)	S [2]	S[2]	S[2]	S[2]	S[2]	RH, SR, SH: 4.9.4.H.1-2 & H.9 RX-1, RX-2: 4.9.4.H. 1-2, H.8-9
Communications						Being Updated by Staff
Day Care Adult Maximum 10 Persons	P	P	P	P	P	Maximum includes permitted Adult Care Residents.
Day Care Child Maximum of 30 Children	P	P				RH & SR: 4.9.4.H. 1-5 Minimum Site 6.6 Acres
Day Care Child Maximum of 30 Children			P	P	P	SH & RX1: 4.9.4.H. 1-5 & Minimum site 72,000 sf RX-2: 4.9.4.H. 1-5 & Minimum site of 32,000 sf
Day Care Child Unlimited Number of Children	S [2]	S[2]	S[2]	S[2]	S[2]	RH, SR, SH, RX-1, RX-2: 4.9.4.H. 1-5, 7.f. & 8
Entertainment: Fairground, Carnival, Racetrack for Animals	S [2]					RH: 4.9.4.K
Financial Service	S [1]					RH: Excludes non-chartered financial institutions
Funeral Service Crematorium Only	S [1]		S [1]			RH, SH: 500' setback from any residentially zoned property.
Medical Service - Outpatient	P					RH: 4.9.4.O.2; 4.9.4.P.2.b, .3, &.4 and must have access from a paved public street on MS&R
Personal Service	S [1]					RH: Maximum floor area

<b>TABLE 4.8-1: PERMITTED USES— RURAL AND SUBURBAN RESIDENTIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i>						
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>						
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>						
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
<b>LAND USE</b>	<b>RH</b>	<b>SR</b>	<b>SH</b>	<b>RX-1</b>	<b>RX-2</b>	<b>USE SPECIFIC STANDARDS</b>
Lodging for Maximum 4 Guests DRB review required						4.9.7.G.1, & G.5-11
Family Dwelling with accessory Traveler's Accommodation Lodging for Maximum 8 guests DRB review required		S [2]	S[2]	S[2]	S[2]	SR, SH, RX-1, RX-2: 4.9.7.B.6 and 4.9.7.G.2, G.5-12, & G.14
Mobile Home Dwelling	P		P			
Mobile Home Dwelling with accessory Home Occupations	P		P			RH, SH: 4.9.7.E
Mobile Home Dwelling with accessory Group Dwelling	P		P			RH, SH: 4.9.7.F
<b>Retail Trade Land Use Group With Land Use Class/Type:</b>						
Artists/Artisans Workshop/Studio	S [2]					RH: Maximum floor area is 2,000 square feet.
Feed store	S [1]					RH: Must have access from a paved public street on MS&R
Food and Beverage Sales	S [1]					RH: Maximum floor area is 4,000 square feet.
Fuel dispensing	S [1]					RH: Must have access from a paved public street on MS&R
General Merchandise Sales	S [1]					
<b>Storage Land Use Group With Land Use Class/Type:</b>						
Any Permitted Land Use with accessory Hazardous Material Storage	P	P	P	P	P	RH: 4.9.10.B.1, and 2.a.
<b>Utilities Land Use Group With Land Use Class/Type:</b>						
Distribution System		S [2]	S [2]	S [2]	S [2]	SR, SH, RX-1, RX-2: 4.9.11.A. 1, .2, .5, .8, .9, .11
Distribution System Limited to: Power Substation with Input Voltage of 115 Kilovolts or Greater	S [2]					RH: 4.9.11.A.3, .6, .7, .10
Distribution System Limited to: Telephone, Telegraph, or Power Substations with Input Voltage Less than 115 Kilovolts	S [2]					RH: 4.9.11.A.2, 8
Distribution System Limited to: Water Pumping and Storage Facilities Serving Two or More Properties as Public, Private, or Community Utility	S [2]					RH: 4.9.11.A.4
Renewable Energy Generation	S [2]	S [2]	S[2]	S[2]	S [2]	RH, SR, SH, RX-1, RX-2: 4.9.11.B.2, .3, .4, .5

<b>TABLE 4.8-1: PERMITTED USES– RURAL AND SUBURBAN RESIDENTIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use If Governmentally Owned and Operated</i>						
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>						
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>						
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
<b>LAND USE</b>	<b>RH</b>	<b>SR</b>	<b>SH</b>	<b>RX-1</b>	<b>RX-2</b>	<b>USE SPECIFIC STANDARDS</b>
						2,000 square feet.
Trade Service and Repair Minor	S [1]					
Transportation Service Airport Facilities	S [1]					RH: 4.9.4.Y.1 & 2.
Transportation Service General Aviation Airstrip	S [1]					RH: 4.9.4.Y.1 - 4
Traveler's Accommodation Lodging		P	P	P		SR, SH, RX-1: Minimum 50' side and rear yard setbacks Minimum lot size 10 Acres
Traveler's Accommodation Lodging	S [1]					
<b>Industrial Land Use Group With Land Use Class/Type:</b>						
Extraction	S [1]					RH: 4.9.5.B
Motion Picture Industry			S [1]			SH: 4.9.13.C
Perishable Goods Manufacturing	S [1]					RH: 4.9.5.E.2, .3
Primary Manufacturing Asphalt and Cement Plants Only	S [1]					RH: 4.9.5.B
<b>Recreation Land Use Group With Land Use Class/Type:</b>						
Commercial Recreation	S [1]					RH: Minimum setback shall be 100' from property line. Must have access from a paved public street on MS&R
Golf Course		P	P	P	P	Minimum lot size 30 acres SR, SH, RX-1, RX-2: 4.9.6.A.
Parks and Recreation		P	P	P	P	SR, SH, RX-1, RX-2: 4.9.13.C and must have access from a paved public street on MS&R
<b>Residential Land Use Group With Land Use Class/Type:</b>						
Adult Care or Physical Behavioral Health Services For Maximum 10 Residents	P	P	P	P	P	RH, SR, SH, RX-1, RX-2: 4.9.7.1.2.a, 3.a, & 4
Adult Care or Physical Behavioral Health Services For Maximum 15 Residents	S [2]	S [2]	S [2]	S [2]	S [2]	RH, SR, SH, RX-1, RX-2: 4.9.7.1.2.a, 3.b, & 4
Adult Care or Physical Behavioral Health Services For Unlimited Residents	S [2]	S [2]	S [2]	S [2]	S [2]	RH, SR, SH, RX-1, RX-2: 4.9.7.1.2.a, 3.d, 4, & 7 and Minimum 3 acre lot
Family Dwelling	P	P	P	P	P	SR, RX-1, RX-2: 4.9.7.B.6
Family Dwelling with accessory Home Occupations	P	P	P	P	P	RH, SH: 4.9.7.E SR, RX-1, RX-2: 4.9.7.B.6 and 4.9.7.E
Family Dwelling with accessory Group Dwelling	P	P	P	P	P	RH, SR, SH, RX-1, RX-2: 4.9.7.B.6 and 4.9.7.F
Family Dwelling with accessory Traveler's Accommodation		P	P	P	P	SR, SH, RX-1, RX-2: 4.9.7.B.6 and

4.8.2. PERMITTED USES: URBAN RESIDENTIAL ZONES

<b>TABLE 4.8-2: PERMITTED USES-- URBAN RESIDENTIAL ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
LAND USE	R-1	R-2	R-3	MH-1	MH-2	USE SPECIFIC STANDARDS
<b>Agricultural Land Use Group With Land Use Class/Type:</b>						
Crop Production	P	P	P	P	P	All zones: Any greenhouse heating plant or cooling fan shall be setback a minimum of 200' from any property line.
<b>Civic Land Use Group With Land Use Class/Type:</b>						
Cemetery		P	P			R-2, R-3: Use shall be adjacent to or an extension of an existing cemetery.
Civic Assembly			G			
Cultural Use	G	G	G	G	G	R-1 R-2, MH-1, MH-2: 20,000 sf minimum lot size.
Cultural Use	S [1]	S [1]	S [1]			R-1, R-2, R-3: 4.9.3.C.2 -.8
Cultural Use with Food Service	G	G	G			R-1, R-2, R-3: 4.9.4.M.1, .3 & 20,000 sf minimum lot size
Cultural Use with Alcoholic Beverage Service	G	G	G			R-1, R-2, R-3: 4.9.4.C.3 & 4.9.4.V.4, .9 and 20,000 sf minimum lot size
Cultural Use with Entertainment	G	G	G			R-1, R-2, R-3: 4.9.4.K.6 and 20,000 sf minimum lot size
Cultural Use with General Merchandise Sales	G	G	G			R-1, R-2, R-3: 4.9.9.B.1, .2 and 20,000 sf minimum lot size
Educational Use Elementary and Secondary School	P	P	P	P	P	R-1, R-2, R-3, MH-1, MH-2: 4.9.3.D.1-7
Educational Use Elementary and Secondary School	S [2]					
Educational Use with Salvaging and Recycling	P	P	P	P	P	R-1, R-2, R-3, MH-1, MH-2: 4.9.3.D.1-7 & 4.9.5.G.1 & 3
Postal Service		G	G			R-2, R-3: 20,000 sf minimum lot size
Protective Service	G	G	G	G	G	R-1, R-2, R-3, MH-1, MH-2: 4.9.13.F
Religious Use	P	P	P	P	P	R-1, R-2, MH-1, MH-2: 20,000 sf minimum lot size
Religious Use with accessory Columbarium	P	P	P	P	P	R-1, R-2, MH-1, MH-2: 20,000 sf minimum lot size
Religious Use with accessory Salvaging and Recycling	P	P	P	P	P	R-1, R-2, MH-1, MH-2: 20,000 sf minimum lot size and 4.9.5.G.1 & 3
<b>Commercial Services Land Use Group</b>						
Administrative and Professional Office		G	G		G	R-2, MH-2: One acre minimum lot size R-3: 72,000 sf minimum lot size
Communications						Being Updated by Staff
Day Care, Adult	P	P	P	P		R-1, R-2, MH-1: 4.9.4.B.1 R-3: 4.9.4.B.2

<b>TABLE 4.8-2: PERMITTED USES— URBAN RESIDENTIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
LAND USE	R-1	R-2	R-3	MH-1	MH-2	USE SPECIFIC STANDARDS
Day Care, Child Maximum 30 Children	P	P				<b>R-1, R-2:</b> 4.9.4.H.1-5, 6.a and 7.d. 14,000 sf minimum lot size
Day Care, Child Unlimited number of children			P			<b>R-3:</b> 4.9.4.H.1-5, 6.C and 7.e 10,000 sf minimum lot size
Medical Services		S [2]	S [2]			<b>R-2&amp; R-3:</b> 4.9.4.O.2,4 and 4.9.4.P.1,2,a,3, &.4
<b>Recreation Land Use Group With Land Use Class/Type:</b>						
Parks and Recreation	P	P	P	P	P	<b>R-1, R-2, R-3, MH-1, MH-2:</b> 4.9.13.B & C
<b>Residential Land Use Group With Land Use Class/Type:</b>						
Adult Care or Physical and Behavioral Health Services for Maximum 10 Residents	P	P	P	P	P	<b>R-1, R-2:</b> 4.9.7.I.2.a, .3.a, .4 <b>R-3, MH-1, MH-2:</b> 4.9.7.I.3.a, .4
Adult Care or Physical and Behavioral Health Services for <b>Unlimited</b> Number Residents		P	P			<b>R-2:</b> 4.9.7.I.2.a, .3.d, .4, .7 <b>R-3:</b> 4.9.7.I.3.d, .4, .8 (no minimum lot size)
Adult Care or Physical and Behavioral Health Services for Maximum 15 Residents	S [2]	S [2]		S[2]		<b>R-1, R-2:</b> 4.9.7.I.2.a, .3.b, .4 <b>MH-1:</b> 4.9.7.I.3.b, .4
Adult Care or Physical and Behavioral Health Services for <b>Unlimited</b> Number Residents	S [2]			S[2]		<b>R-1:</b> 4.9.7.I.2.a, 3.d, .4, .8 <b>MH-1:</b> 4.9.7.I.3.d, .4, .8
Adult Rehabilitation Service or Shelter Care for Maximum 10 Residents		S [2]				<b>R-2:</b> 4.9.7.I.1, .2.b, .3.a, .4, 9
Adult Rehabilitation Service or Shelter Care for Maximum 20 Residents			S [2]			<b>R-3:</b> 4.9.7.I.1, .2.b, .3.c, .4, 9
Adult Rehabilitation Service or Shelter Care for <b>Unlimited</b> Number Residents		S[2]	S [2]			<b>R-2:</b> 4.9.7.I.1, 2.a, .3.d, .4, 8 ?
Child Rehabilitation Service for Maximum 10 Residents		P	P			<b>R-2, R-3:</b> 4.9.7.I.1, .2.a, .3.a, .4
Family Dwelling	P	P	P	P	P	<b>R-1:</b> 4.9.7.B.5, .6, .7, .8 (single family) or 4.9.7.B (two dwellings) <b>R-2, R-3:</b> 4.9.7.B.6
Family Dwelling with accessoryTravelers' Accommodation Lodging with Maximum of 4 guests	P			P		<b>R-1, MH-1:</b> 4.9.7.G.1 and G.5-11
Family Dwelling with accessoryTravelers' Accommodation Lodging with Maximum of 8 guests		P			P	<b>R-2, MH-2:</b> 4.9.7.G.2 and G.5-11
Family Dwelling with accessoryTravelers' Accommodation Lodging with Maximum of 20 guests			P			<b>R-3:</b> 4.9.7.G.4 and G.5-11

<b>TABLE 4.8-2: PERMITTED USES— URBAN RESIDENTIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i>						
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>						
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>						
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
<b>LAND USE</b>	<b>R-1</b>	<b>R-2</b>	<b>R-3</b>	<b>MH-1</b>	<b>MH-2</b>	<b>USE SPECIFIC STANDARDS</b>
Family or Mobile Home Dwelling with accessory General Home Occupation	P	P	P	P	P	R-1, R-2, R-3, MH-1, MH-2: 4.9.7.E.
Group Dwelling			P			R-3: 4.9.7.B.6
Mobile Home Dwelling				P	P	
Mobile Home Park (100 spaces or more) with Accessory Use					P	MH-2: 4.9.7.H
Mobile Home Park with Travelers Accommodation, Campsite				P	P	MH-1, MH-2: 4.9.4.Z
Shelter Care for Victims of Domestic Violence for Maximum 10 Residents		P	P			R-2: 4.9.7.I.1, .2.a, .3.a, .4, 9 R-3: 4.9.7.I.1, .2.b, .3.a, .4, 9
<b>Storage Land Use Group With Land Use Class/Type:</b>						
Hazardous Material Storage as Accessory use to a Permitted Land Use	P	P	P	P	P	R-1, R-2, R-3, MH-1, MH-2: 4.9.10.B.1, .2.a
<b>Utilities Land Use Group With Land Use Class/Type:</b>						
Distribution System	S [2]	S [2]	S [2]	S [2]	S [2]	R-1, R-2, R-3, MH-1, MH-2: 4.9.11.A.1, .2, .5, .8, .10, .11
Renewable Energy Generation	S [2]	S [2]	S [2]	S [2]	S [2]	R-1, R-2, R-3 MH-1, MH-2: 4.9.11.B.2, .3, .4, .5

4.8.3. PERMITTED USES: SPECIAL PURPOSE ZONES

<b>TABLE 4.8-3: Permitted Uses – SPECIAL PURPOSE ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Government Owned &amp; Operated</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx					
LAND USE	IR	OS	P	RV	USE SPECIFIC STANDARDS
<b>Agricultural Land Use Group With Land Use Class/Type:</b>					
Animal Production (Excludes Stockyard)	P				IR: 4.9.2.A.1.a, 2.b, 3.b, 3.c
Animal Production Hog Ranch Only	S [1]				IR: 4.9.2.A.3.d
Animal Production Stable or Riding School Only	P				IR: 4.9.2.A.2.b, 4
Crop Production	P				IR: 4.9.2.B
Crop Production with accessory Food and Beverage Sales	P				IR: 4.9.9.A.2.a, 3-9.
General Farming	P				IR: 4.9.2.A.1.a, 2.b, 3.b, 3.c; 4.9.2.B
Stockyard Operation Feedlot for Stockyard Only	S [1]				IR: 4.9.2..C.1
Stockyard Operation Livestock Auction Yard	S [1]				IR: 4.9.2..C.2
<b>Civic Land Use Group With Land Use Class/Type:</b>					
Cultural Use: Limited to Nature Reserve	P				
Cultural Use: Other than Nature Reserve or Wildlife Refuge	S [2]				IR: 4.9.3.C.1
Educational Use: Elementary and Secondary Schools	S [2]				
Educational Use with Salvaging and Recycling	S [2]				IR: 4.9.5.G.1, .3
Protective Services	G				IR: 4.9.13.F
Religious Uses	P				
Religious Use with Columbarium	P				
Religious Use with Salvaging and Recycling	P				IR: 4.9.5.G.1, .3
<b>Commercial Services Land Use Group With Land Use Class/Type:</b>					
Administrative and Professional Office	S [2]				IR: 4.9.4.A.1
Animal Services: Limited to Veterinary Hospital	P				IR: 4.9.4.D.5
Communications, General					Being Updated by Staff
Construction Service	S [1]				IR: 4.9.4.J; 4.9.13.A.2
Entertainment Carnival	S [1]				IR: 4.9.4.K.5
Entertainment Racetrack (Animals)	S [1]				IR: 4.9.4.K.5
Medical Services: Outpatient	P				IR: 4.9.4.O.3; 4.9.4.P.2.b, .3, .4; 4.9.13.A.2
Parking			P		P: 4.9.4.S

<b>TABLE 4.8-3: Permitted Uses – SPECIAL PURPOSE ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G= Government Owned &amp; Operated</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx					
LAND USE	IR	OS	P	RV	USE SPECIFIC STANDARDS
Transportation Service Air Carrier, Airport Facilities	S [1]				IR: 4.9.4.Y.1 & 2
Transportation Service Air Carrier, General Aviation Strip	S [1]				IR: 4.9.4.Y.1 - 4
Transportation Service Air Carrier, Ultra-light Airstrip	S [1]				
Transportation Service Air Carrier, Ultra-light Flight Park	S [1]				IR: 4.9.4.Y.2 & 3
Travelers Accommodation: Campsite				P	
Travelers Accommodation: Campsite (200 spaces or more) with accessory Day Care, Personal Service, Food and Beverage Sales, General Merchandise Sales, Recreation, Family Dwelling, Mobile Home Dwelling, or Adult Care Services				P	RV: 4.9.7.H.1, .2
Travelers Accommodation: Lodging	S [1]				
<b>Industrial Land Use Group With Land Use Class/Type:</b>					
Extraction	S [1]				IR: 4.9.5.B.1, .2
Perishable Goods Manufacturing	S [1]				IR: 4.9.5.E.2, .3
<b>Recreational Land Use Group With Land Use Class/Type:</b>					
Open Space		P			OS: 4.7.28.C, .D
<b>Residential Land Use Group With Land Use Class/Type:</b>					
Family Dwelling	P				
Family or Mobile Home Dwelling with accessory Home Occupation	P				IR: 4.9.7.E
Family or Mobile Home Dwelling with accessory Home Occupation Group Dwelling	P				IR: 4.9.7.F.1-3.
Mobile Home Dwelling	P				
<b>Retail Trade Use Group With Land Use Class/Type:</b>					
General Merchandise Sales: Artists or Artisan Workshop or Studio	S [2]				IR: 4.9.9.B.2
General Merchandise Sales: Feed Store	S [2]				IR: 4.9.13.A.2
<b>Storage Use Group With Land Use Class/Type:</b>					
Hazardous Material Storage as Use to any Permitted Land Use	P			P	IR, RV: 4.9.10.B.1, .2.a
<b>Utilities Land Use Group With Land Use Class/Type:</b>					
Distribution System limited to: Power Substations with an Input 115 Kilovolts or Greater	S [2]				IR: 4.9.11.A.3, .6, .7, .10
Distribution System limited to: Telephone, Telegraph, or Power Substations with an Input of 115	S [2]				IR: 4.9.11.A.2, .8

<b>TABLE 4.8-3: Permitted Uses – SPECIAL PURPOSE ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Government Owned &amp; Operated</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx					
LAND USE	IR	OS	P	RV	USE SPECIFIC STANDARDS
Kilovolts					
Distribution System limited to: Water pumping and storage facilities operated as part of a system serving 2 or more properties as a private, public, or community utility	S [2]				IR: 4.9.11.A.4
Renewable Energy Generation	S [2]				IR : 4.9.11.B.2, .3, .4, .5

DRAFT

4.8.4. PERMITTED USES: COMMERCIAL ZONES

<b>TABLE 4.8-4: PERMITTED USES – COMMERCIAL ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx						
LAND USE	NC	RVC	C-1	C-2	C-3	USE SPECIFIC STANDARDS
<b>Civic Land Use Group With Land Use Class/Type:</b>						
Cemetery			P			C-1: 4.9.3.A.1, .5, .6 Minimum 10 acre lot size
Civic Assembly			P	P	P	
Correctional Use Custodial Facility				S [1]	S[1]	C-2 & C-3: 4.9.3.B.1.a, 2.b, 3.b, 6, 7 & 8
Correctional Use Supervision Facility				P	P	C-2 & C-3: 4.9.3.B.1.a, 2.b,3.a, 4.d, 6 & 8
Cultural Use	G	G	G	P	P	
Educational Use Elementary and Secondary Schools	S [2]		S [2]	S [2]	S [2]	
Educational Use Elementary and Secondary Schools	P		P	P	P	NC, C-1, C-2, C-3: 4.9.3.D.1 – 7
Educational Use Instructional School			P	P	P	
Educational Use Postsecondary Institution			P	P	P	C-1, C-2, C-3: 4.9.3.E
Educational Use with accessory Salvaging and Recycling	P		P	P	P	NC, C-1, C-2, C-3: 4.9.3.D.1-7 & 4.9.5.G.1, .3
Membership Organization			P	P	P	
Postal Service	G	G	G	P	P	
Protective Service	G	G	G	P	P	
Religious Use		P	P	P	P	
Religious Use with accessory Columbarium		P	P	P	P	
Religious Use with accessory Salvaging and Recycling		P	P	P	P	RVC, C-1, C-2, C-3: 4.9.5.G.1, .3
<b>Commercial Services Land Use Group With Land Use Class/Type:*</b>						
Administrative and Professional Office	P	P	P	P	P	
Alcoholic Beverage Service, Excludes Large Bars				P	P	
Alcoholic Beverage Service, Large Bar				S [1]	S [1]	C-2, C-3: 4.9.4.C.2
Alcoholic Beverage Service Excludes Large Bars, with accessory Perishable Goods Manufacturing				P	P	C-2, C-3: 4.9.5.E.6, 7, 8
Animal Service			P	P	P	C-1, C-2: 4.9.4.D.1, .2, .3, .4 C-3: 4.9.4.D.1, .2, .3, .4 or 4.9.4.D.7
Artisan Residence	P		P	P	P	NC, C-1, C-2, C-3: 4.9.4.E.1, .2, .3, .4, .5

<b>TABLE 4.8-4: PERMITTED USES – COMMERCIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
LAND USE	NC	RVC	C-1	C-2	C-3	USE SPECIFIC STANDARDS
Automotive Service and Repair (Excludes bodywork and paint-booths)				P	P	
Automotive Service and Repair: Minor Service and Repair		S [1]	S [2]			RVC: 4.9.4.F.5 C-1: 4.9.4.F.2, .3, .4, .5
Billboard				P	P	C-2, C-3: 4.9.4.G. & Standards of Ch. 3 of the Tucson Code
Buildings and Ground Maintenance				P	P	
Communications						Being Updated by Staff
Construction Service				P	P	
Day Care	P	P	P	P	P	
Entertainment, General			P	P	P	C-1: 4.9.4.C.3 C-2 & C-3: 4.9.4.K.1, .2, .3, .4 & 4.9.4.C.3
Entertainment: Dance Hall				S[1]	S [1]	C-2, C-3: 4.9.4.C.2
Financial Service	P	P	P	P	P	NC, RVC, C-3: 4.9.4.L.3 C-1: 4.9.4.L.1, .3 C-2: 4.9.4.L.3
Financial Service: Non-chartered Financial Institution				S[2]	S[2]	C-2, C-3: 4.9.4.L.4
Food Service Excludes Soup Kitchens	P	P	P	P	P	RVC: 4.9.4.M.2 & 4.9.4.V.3 C-1, NC: 4.9.4.M.1 & 5 C-2: 4.9.4.M.1
Food Service Soup Kitchens				S [1]	S [1]	C-2, C-3: 4.9.4.M.4
Food Service with accessory Alcoholic Beverage Service		S [1]	P			RVC: 4.9.4.V.2, .3, .4 & 4.9.4.C.3 C-1: 4.9.4.V.1, 5-9 & 4.9.4.C.3
Food Service with accessory Microbrewery			S [2]			C-1: 4.9.4.M.1 & 4.9.5.E.6, .7, .8
Funeral Service				P	P	
General Merchandise Sales, (automotive fuel) with accessory Auto Minor Service and Repair			P			C-1: 4.9.4.F.7
Medical Service: Extended Healthcare			P	P	P	
Medical Service: Major			P	P	P	
Medical Service: Outpatient		P	P	P	P	RVC, C-1, C-2, C-3: 4.9.4.O.2
Medical Service: Outpatient, Limited to a Blood Donor Center			S [1]	S [1]	S [1]	C-1, C-2, C-3: 4.9.4.O.3
Parking			P	P	P	
Personal Service	P	P	P	P	P	RVC: 4.9.4.T.2, .3 C-1, NC: 4.9.4.T.1
Research and Product Development			P	P	P	
Technical Service			P	P	P	C-1: 4.9.4.W.1 C-2, C-3: 4.9.4.W.2

<b>TABLE 4.8-4: PERMITTED USES – COMMERCIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use If Governmentally Owned and Operated</i>						
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>						
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>						
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
<b>LAND USE</b>	<b>NC</b>	<b>RVC</b>	<b>C-1</b>	<b>C-2</b>	<b>C-3</b>	<b>USE SPECIFIC STANDARDS</b>
Trade Service and Repair: Major (includes automotive bodywork and paint-booths)					P	<b>C-3:</b> No openings within 30 feet of adjacent residentially zoned property.
Trade Service and Repair: Minor	P		P	P	P	<b>NC:</b> Excludes upholstery shops <b>C-1:</b> Excludes upholstery, burglar alarm repair, and motor vehicle stereo repair.
Transportation Services: Land Carrier				P	P	
Travelers Accommodation: Lodging			P	P	P	
Travelers Accommodation: Lodging with accessory Alcoholic Beverage Service			S [2]			<b>C-1:</b> 4.9.4.BB. 2, 4, 7, 8, 9, 11 Excludes large bars and dance halls.
All Permitted Commercial Services Uses with accessory: General Manufacturing; Heavy Equipment Manufacturing; Perishable Goods Manufacturing*; Precision Manufacturing; Primary Manufacturing				P	P	<b>C-2, C-3:</b> * Perishable Goods Manufacturing is limited to baked goods and confectionary products
All Permitted Commercial Services with accessory Perishable Goods Manufacturing			P			<b>C-1:</b> 4.9.5.E.4, .5, .8
All Permitted Commercial Services with accessory Salvaging and Recycling	P	P	P	P	P	<b>NC, RVC, C-1, C-2, C-3:</b> 4.9.5.G.1, .3
<b>Industrial Land Use Group With Land Use Class/Type:</b>						
Craftwork				P	P	
Processing and Cleaning				P	P	
Salvaging and Recycling				P	P	<b>C-2, C-3:</b> 4.9.5.G.2, .3, .5
Salvaging and Recycling: Limited to Household Goods Donation Center			S [2]	S [3]	P	<b>C-1, C-2:</b> 4.9.5.G.2, .6 -12; 4.9.13.A.2, .B-D <b>C-3:</b> 4.9.5.G.2, .3, .6 -11; 4.9.13.C & .D
<b>Recreation Land Use Group With Land Use Class/Type:</b>						
Commercial Recreation			P	P	P	
Golf Course			P	P	P	<b>C-1, C-3:</b> 4.9.6.A.1.a - f <b>C-2:</b> 4.9.6.A.1.a - f, h
Parks and Recreation	P		P	P	P	

<b>TABLE 4.8-4: PERMITTED USES – COMMERCIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i>						
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>						
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>						
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
<b>LAND USE</b>	<b>NC</b>	<b>RVC</b>	<b>C-1</b>	<b>C-2</b>	<b>C-3</b>	<b>USE SPECIFIC STANDARDS</b>
<b>Residential Land Use Group With Land Use Class/Type:</b>						
Adult Care or Physical and Behavioral Health Services Maximum 10 Residents	P					NC: 4.9.7.l.3.a, .4
Adult Care or Physical and Behavioral Health Services Unlimited Number Residents			P	P	P	C-1, C-2: 4.9.7.l.3.d, .4, .8 C-3: 4.9.7.l.3.d, .4
Adult Rehabilitation or Shelter Care Maximum 10 Residents			P	P	P	C-1, C-2, C-3: 4.9.7.l.1, 3.a, .4, .6, .8
Adult Rehabilitation or Shelter Care Unlimited Number Residents			S [2]	S [2]	S [2]	C-1, C-2, C-3: 4.9.7.l.1, 3.d, .4, .6, .8
Child Rehabilitation Service Maximum 10 Residents	P		P	P	P	NC, C-1, C-2, C-3: 4.9.7.l.1, 3.a, .4
Family Dwelling	P		P	P	P	
Family Dwelling with Home Occupations	P		P	P	P	Being updated by staff.
Family Dwelling with General Farming				P	P	C-2, C-3: 4.9.2.A.1.a, 3.a & 4.9.2.B.1
Family Dwelling with Traveler's Accommodation Lodging	P					NC: 4.9.7.G. 1, 5, 6, 7, 8, 9, 10, 11, 12
Family Dwelling within the Rio Nuevo and Downtown Zone	P					
Group Dwelling			P	P	P	
Shelter Care for Victims of Domestic Violence for Maximum 15 Residents			P			C-1: 4.9.7.l.1, 3.b, .4
Shelter Care for Victims of Domestic Violence for Maximum 20 Residents				P	P	C-2, C-3: 4.9.7.l.1, 3.c, .4
<b>Restricted Adult Activities Use Group With Land Use Class/Type:</b>						
Adult Commercial Services, Recreation, or Retail Trade				P	P	C-2, C-3: 4.9.8
<b>Retail Trade Use Group With Land Use Class/Type:</b>						
Construction Material Sales				P	P	
Food and Beverage Sales, General	P	P	P	P	P	NC: Excludes alcoholic beverage sales

<b>TABLE 4.8-4: PERMITTED USES – COMMERCIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i>						
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>						
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>						
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
<b>LAND USE</b>	<b>NC</b>	<b>RVC</b>	<b>C-1</b>	<b>C-2</b>	<b>C-3</b>	<b>USE SPECIFIC STANDARDS</b>
Food and Beverage Sales: Large Retail Establishment		S [1]	S [1]	S [1]	S [1]	RVC, C-1, C-2, C-3: 4.9.9.D
Medical Marijuana Designated Caregiver Cultivation Location					P	C-3: 4.9.9.E.2 & 3
Medical Marijuana Dispensary				P	P	C-2, C-3: 4.9.9.E.1
Medical Marijuana Dispensary Off-site Cultivation Location				P	P	C-2, C-3: 4.9.9.E.2
Medical Marijuana Qualifying Patient Cultivation Location				P	P	C-2, C-3: 4.9.9.E.4
Merchandise Sales, General	P	P	P	P	P	C-1: Maximum of 12 fuel dispensing locations. C-2, C-3: Outdoor display of odorous material shall be minimum 30 feet from interior lot line.
Merchandise Sales: Large Retail Establishment		S [1]	S [1]	S [1]	S [1]	RVC, C-1, C-2, C-3: 4.9.9.D
Swap Meets and Auctions				P	P	C-2, C-3: 4.9.9.F
Vehicle Rental and Sales				P	P	C-2, C-3: 4.9.9.G.1-2
All Permitted Retail Trade Uses with accessory Craftwork			P			C-1: 4.9.5.A
All Permitted Retail Trade Uses with accessory: General Manufacturing; Heavy Equipment Manufacturing; Precision Manufacturing; Perishable Good Manufacturing*; Primary Manufacturing				P	P	C-2, C-3: *Perishable Good Manufacturing is limited to baked goods and confectionary products.
All Permitted Retail Trade Uses with accessory Perishable Goods Manufacturing			P			C-1: 4.9.5.E.4, .5, .8
All Permitted Retail Trade Uses with accessory Salvaging and Recycling	P	P	P	P	P	NC, RVC, C-1, C-2, C-3: 4.9.5.G.1, .3
<b>Storage Use Group With Land Use Class/Type:</b>						
Commercial Storage				P	P	C-2, C-3: 4.9.10.A
Hazardous Material Storage with a Permitted Land Use			P	P	P	C-1, C-2: 4.9.10.B.1, 2.a C-3: 4.9.10.B.1, 2.c
Personal Storage			P	P	P	C-1: 4.9.10.C C-2, C-3: 4.9.10.C.3, .6

<b>TABLE 4.8-4: PERMITTED USES – COMMERCIAL ZONES</b>						
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted Use if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>						
LAND USE	NC	RVC	C-1	C-2	C-3	USE SPECIFIC STANDARDS
<b>Utilities Use Group With Land Use Class/Type:</b>						
Distribution System	S [2]	S [2]	S [2]	P	P	NC, RVC, C-1 C-2,C-3: 4.9.11.A.1, .5, .9
Renewable Energy Generation			S [3]	S [3]	S [3]	C-1: 4.9.11.B.1-5 C-2, C-3: 4.9.11.B.1-3 & .5
Renewable Energy Generation			S [2]	S [2]	S [2]	
<b>Wholesaling Use Group With Land Use Class/Type:</b>						
Business Supply and Equipment Wholesaling				P	P	
Construction/Heavy Equipment Wholesaling				P	P	
Food and Beverage Wholesaling				P	P	
All Permitted Wholesaling Uses with accessory; General Manufacturing; Heavy Equipment Manufacturing; Precision Manufacturing; Primary Manufacturing.				P	P	
All Permitted Wholesaling Uses with accessory Perishable Goods Manufacturing, limited to baked goods and confectionary products				P	P	

\* All Commercial Services in the C-1 Zone may provide one drive-through service lane unless otherwise provided.

4.8.5. PERMITTED USES: OFFICE AND MIXED USE ZONES

<b>TABLE 4.8-5: PERMITTED USES – OFFICE AND MIXED USE ZONES</b>							
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted if Governmentally Owned and Operated</i>							
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>							
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>							
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>							
<b>LAND USE</b>	<b>O-1</b>	<b>O-2</b>	<b>O-3</b>	<b>MU</b>	<b>OCR-1</b>	<b>OCR-2</b>	<b>USE SPECIFIC STANDARDS</b>
<b>Agricultural Land Use Group With Land Use Class/Type:</b>							
Animal Production, General				P			<b>MU: 4.9.2.A.1.a, 1.c, 2.a, 2.b, &amp; 3.a</b>
Animal Production Commercial Stables Only				S [2]			<b>MU: 4.9.2.A.1.b, 2.b, &amp; 4.c</b>
<b>Civic Land Use Group With Land Use Class/Type:</b>							
Cemetery			P	S [2]			<b>O-3: Use must be adjacent to or extension of existing cemetery.</b>
Civic Assembly		P	P	P	P	P	
Correctional Use Custodial Facility				S [1]	S [1]	S [1]	<b>MU, OCR-1, OCR-2: 4.9.3.B.1.a, 2.b, 3.b, 6, 7 &amp; 8</b>
Correctional Use Supervision Facility				P	P	P	<b>MU, OCR-1, OCR-2: 4.9.3.B.1.a, 2.b, 3.a, 6 &amp; 8</b>
Cultural Use		G	G	P	P	P	
Cultural Use	S [1]	S [1]	S [1]				<b>O-1, O-2, O-3: 4.9.3.C.2 - 8</b>
Cultural Use with accessory Food Service	S [1]	S [1]	S [1]				<b>O-1, O-2, O-3: 4.9.3.C.2- 8 &amp; 4.9.4.M.1, .3</b>
Cultural Use with accessory Alcoholic Beverage Service	S [1]	S [1]	S [1]				<b>O-1, O-2, O-3: 4.9.3.C.2- 8 &amp; 4.9.4.C.3 &amp; 4.9.4.V.4, .10</b>
Cultural Use with accessory Entertainment	S [1]	S [1]	S [1]				<b>O-1, O-2, O-3: 4.9.3.C. 2- 8 &amp; 4.9.4.K.6</b>
Cultural Use with accessory General Merchandise Sales	P	P	P				<b>O-1, O-2, O-3: 4.9.3.C. 2- 8 &amp; 4.9.9.B1, .2</b>
Educational Use: Elementary and Secondary Schools		P	P		P	P	<b>O-2, O-3, OCR-1, OCR-2: 4.9.3.D</b>
Educational Use: Elementary and Secondary Schools		S [2]	S [2]		S [2]	S [2]	
Educational Use: Postsecondary Institution		P	P				<b>O-2, O-3: 4.9.3.E</b>
Educational Use: Postsecondary Institution and Instructional School				P	P	P	
Educational Use with accessory Salvaging and Recycling		P	P				<b>O-2, O-3: 4.9.3.E &amp; 4.9.5.G.1&amp;3</b>
Membership Organization					P	P	
Postal Service		G	G	P	P	P	
Protective Service		G	G		P	P	
Religious Use		P	P	P	P	P	
Religious Use with accessory Columbarium		P	P	P	P	P	
Religious Use with accessory Salvaging and Recycling		P	P	P	P	P	<b>O-2, O-3, MU, OCR-1, OCR-2: 4.9.5.G.1, .3</b>

<b>TABLE 4.8-5: PERMITTED USES – OFFICE AND MIXED USE ZONES</b>							
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted if Governmentally Owned and Operated</i>							
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>							
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>							
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>							
<b>LAND USE</b>	<b>O-1</b>	<b>O-2</b>	<b>O-3</b>	<b>MU</b>	<b>OCR-1</b>	<b>OCR-2</b>	<b>USE SPECIFIC STANDARDS</b>
<b>Commercial Services Land Use Group With Land Use Class/Type:</b>							
Administrative and Professional Office	P	P	P	S [2]	P	P	O-1: 4.9.4.R
Alcoholic Beverage Service, General				S [2]	P	P	OCR-1, OCR-2: Prohibits bars and dance halls over 18,000 square feet.
Alcoholic Beverage Service: Bar over 18,000 sq feet					S [1]	S [1]	OCR-1, OCR-2: 4.9.4.C.2
Alcoholic Beverage Service with accessory Microbrewery				P	P	P	MU, OCR-1, OCR-2: Products manufactured shall be sold at retail on site.
Animal Services				S [2]			
Automotive Service and Repair, excludes bodywork and paint-booths				S [2]			
Billboard				S [2]			MU: 4.9.4.G & Tucson Code, Ch. 3 Standards
Buildings and Ground Maintenance				S [2]			
Commercial Recreation				P	P	P	
Communications							Being Updated by Staff
Construction Service				S [2]			
Day Care, General				S [2]	P	P	
Day Care, Adult		P					
Day Care, Child		P	P				O-2: 4.9.4.H.1-5, 6.a and 7.d O-3: 4.9.4.H.1-5, 6.a and 7.e OR 4.9.4.H. 1-5, 6.b and 7.f
Day Care, Child		S [2]	S [2]				O-2: 4.9.4.H.1-5, 6.a, 7.d & 8 OR 4.9.4.H.1, 2, and 9 O-3: 4.9.4.H.1-5, 6.c, and 7.g OR 4.9.4.H. 1, 2, and 0
Entertainment General				S [2]	P	P	MU, OCR-1, OCR-2: 4.9.4.K.1, .2, .3, .4; 4.9.4.C.3
Entertainment Dance Hall					S [1]	S [1]	OCR-1, OCR-2: 4.9.4.C.2
Financial Service Excludes Non-chartered Financial Institutions				S [2]	P	P	
Financial Service limited to Non-chartered Financial Institutions				S [2]	S [2]	S [2]	MU, OCR-1, OCR-2: 4.9.4.L.4
Food Service Excludes Soup Kitchens				S [2]	P	P	OCR-1, OCR-2: 4.9.4.M.1
Food Service Soup Kitchen					S [1]	S [1]	OCR-1, OCR-2: 4.9.4.M.4
Funeral Service				S [2]			
Medical Service Extended Healthcare		P	P	P	P	P	MU: 4.9.4.O.5
Medical Service Major		P	P	P	P	P	O-2, O-3: 4.9.4.P.1 MU: 4.9.4.O.5

<b>TABLE 4.8-5: PERMITTED USES – OFFICE AND MIXED USE ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted if Governmentally Owned and Operated</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx							
LAND USE	O-1	O-2	O-3	MU	OCR-1	OCR-2	USE SPECIFIC STANDARDS
Medical Service, Major with accessory: Food Service; General Merchandise Sales; or Personal Service		P	P				O-2, O-3: 4.9.4.P.1 & 4.9.4.Q
Medical Service: Outpatient (excludes Blood Donor Center)	P	P	P	P	P	P	O-1: 4.9.4.O.1 & 4.9.4.P.1; 4.9.4.R O-2: 4.9.4.O.1 & 4.9.4.P.1 MU: 4.9.4.O.6 & 4.9.4.P.2.b, .3, .4; 4.9.13.A.2
Medical Service: Blood Donor Center					S [1]	S [1]	OCR-1, OCR-2: 4.9.4.O.3
Parking				S [2]	P	P	MU: 4.9.4.S.2
Personal Service				S [2]	P	P	
Research and Product Development			P	S [2]			O-3: 4.9.4.U
Technical Service				S [2]	P	P	MU: 4.9.4.W.2
Trade Service and Repair Major or Minor				S [2]			
Transportation Service: Land Carrier				S [2]	P	P	
Travelers Accommodation: Lodging				S [2]	P	P	
All Permitted Commercial Uses with accessory Salvaging/Recycling				P	P	P	MU, OCR-1, OCR-2: 4.9.5.G.1, .3
<b>Industrial Land Use Group With Land Use Class/Type:</b>							
Craftwork				S [2]			
General Manufacturing				S [2]			
Perishable Goods Manufacturing				S [2]			
Precision Manufacturing				S [2]			
Processing and Cleaning				S [2]			
Salvaging and Recycling: Limited to Household Goods Donation Center					P	P	OCR-1, OCR-2: 4.9.5.G.2, .6 - 11; 4.9.13.C; 4.9.13.D
<b>Recreation Land Use Group With Land Use Class/Type:</b>							
Parks and Recreation		P	P	P			
<b>Residential Land Use Group With Land Use Class/Type:</b>							
Family Dwelling	P	P	P	P	P	P	
Family Dwelling within the Rio Nuevo and Downtown Zone			P				
Family Dwelling with Home							Being updated by staff

<b>TABLE 4.8-5: PERMITTED USES – OFFICE AND MIXED USE ZONES</b>							
<i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted if Governmentally Owned and Operated</i>							
<i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i>							
<i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i>							
<i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>							
<b>LAND USE</b>	<b>O-1</b>	<b>O-2</b>	<b>O-3</b>	<b>MU</b>	<b>OCR-1</b>	<b>OCR-2</b>	<b>USE SPECIFIC STANDARDS</b>
Occupations							
Family Dwelling with Travelers' Accommodation, Lodging Home	P	P	P				<b>O-1, O-2:</b> 4.9.7.G.1, 5 –12 <b>O-3:</b> 4.9.7.G. 4 –12
Group Dwelling				P	P	P	
Mobile Home Dwelling				P			
Adult Care or Physical and Behavioral Health Services Maximum 10 Residents	P	P	P				<b>O-1, O-2, O-3:</b> 4.9.7.l.3.a, .4
Adult Care or Physical and Behavioral Health Services Maximum 15 Residents	S [2]						<b>O-1:</b> 4.9.7.l.3.b, .4
Adult Care or Physical and Behavioral Health Services Unlimited Number Residents	S [2]		P		P	P	<b>(S) O-1:</b> 4.9.7.l.3.d, .4, .8 <b>O-3:</b> 4.9.7.l.3.d, .4, .8 <b>OCR-1, OCR-2:</b> 4.9.7.l.3.d, .4
Child Rehabilitation Services Maximum 10 Residents		P	P		P	P	<b>O-2:</b> 4.9.7.l.1, 2.b, 3.a, .4 <b>O-3, OCR-1, OCR-2:</b> 4.9.7.l.1, 3.a, .4
Adult Rehabilitation Service or Shelter Care for Maximum 15 Residents		S [2]	P				<b>(S) O-2:</b> 4.9.7.l.1, .2.b, 3.b, .4, .9 <b>O-3:</b> 4.9.7.l.1, .3.b, .4, .6, .9
Adult Rehabilitation Service or Shelter Care for Unlimited Number Residents		S [2]	S [2]		P S[2]	S [2]	<b>O-3:</b> 4.9.7.l.1, 3.d, .4, 8 <b>OCR-1:</b> 4.9.7.l.1, 3.d, 4, 6, 8, <b>(S)OCR-1, OCR-2:</b> 4.9.7.l.1, 3.d, .4, 8
Shelter Care for Victims of Domestic Violence		P	P		P	P	<b>O-2:</b> 4.9.7.l.1, 2.b, 3.b, .4, .7 <b>O-3, OCR-1, OCR-2:</b> 4.9.7.l.1, 3.c, .4
<b>Restricted Adult Activities Land Use Group With Land Use Class/Type:</b>							
Adult Commercial Services, Recreation, Retail Trade					P	P	<b>OCR-1, OCR-2:</b> 4.9.8
<b>Retail Trade Land Use Group With Land Use Class/Type:</b>							
Construction Material Sales				S [2]			
Food and Beverage Sales, General				S [2]	P	P	
Food and Beverage Sales: Large Retail Establishment					S [1]	S [1]	<b>OCR-1, OCR-2:</b> 4.9.9.D
General Merchandise Sales				S [2]	P	P	<b>OCR-1, OCR-2:</b> 4.9.9.B
General Merchandise Sales: Large Retail Establishment					S [1]	S [1]	<b>OCR-1, OCR-2:</b> 4.9.9.D
Heavy Equipment Sales				S [2]			<b>MU:</b> 4.9.9.C
Swap Meets and Auctions					S [1]	S [1]	<b>OCR-1, OCR-2:</b> 4.9.9.F
Vehicle Rental and Sales				S[2]	P	P	<b>MU, OCR-1, OCR-2:</b> 4.9.9.G.1, .2

<b>TABLE 4.8-5: PERMITTED USES – OFFICE AND MIXED USE ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted if Governmentally Owned and Operated</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx							
LAND USE	O-1	O-2	O-3	MU	OCR-1	OCR-2	USE SPECIFIC STANDARDS
All permitted Retail Uses with: Accessory General Manufacturing					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.
All permitted Retail Uses with: Accessory Heavy Equipment Manufacturing					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.
All permitted Retail Uses with: Accessory Perishable Goods limited to baked goods/confectionary products					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.
All permitted Retail Uses with: Accessory Precision Manufacturing					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.
All permitted Retail Uses with: Accessory Primary Manufacturing					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.
All permitted Retail Uses with accessory Salvaging and Recycling				P	P	P	<b>MU, OCR-1, OCR-2:</b> 4.9.5.G.1, .3
<b>Storage Land Use Group With Land Use Class/Type:</b>							
Commercial Storage				S [2]	P	P	<b>MU, OCR-1, OCR-2:</b> 4.9.10.A
Hazardous Material Storage with a Permitted Land Use			P	P	P	P	<b>O-3, MU:</b> 4.9.10.B.1, 2.a <b>OCR-1, OCR-2:</b> 4.9.10.B.1, 2.c
Personal Storage				S [2]	P	P	<b>MU, OCR-1, OCR-2:</b> 4.9.10.C.3, .6
<b>Utilities Land Use Group With Land Use Class/Type:</b>							
Distribution System	S [2]	S [2]	S [2]	S [2]	P	P	<b>O-1, O-2, O-3, OCR-1, OCR-2:</b> 4.9.11.A.1, 5, 9 <b>MU:</b> 4.9.11.A.1, 2, 5, 8, 9, 11
Renewable Energy Generation	S [2]	S [2]	S [2]	S [2] S [3]	S [2] S [3]	S [2] S [3]	<b>O-1, O-2, O-3:</b> 4.9.11.B. 2-5 <b>S[2] OCR-1, OCR-2:</b> 4.9.11.B <b>S[2] MU:</b> 4.9.11.B.1,2,3,&5
<b>Wholesaling Land Use Group With Land Use Class/Type:</b>							
Business Supply and Equipment Wholesaling				S [2]			
Construction/ Heavy Equipment Wholesaling				S [2]			
Food and Beverage Wholesaling				S [2]			
All permitted Wholesaling uses with accessory: General Manufacturing; Heavy Equipment Manufacturing; Precision Manufacturing;					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.

<b>TABLE 4.8-5: PERMITTED USES – OFFICE AND MIXED USE ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use      G = Permitted if Governmentally Owned and Operated</i> <i>[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx</i> <i>[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx</i> <i>[3] Administrative Special Exception Procedure, Sec. 3.xxx</i>							
LAND USE	O-1	O-2	O-3	MU	OCR-1	OCR-2	USE SPECIFIC STANDARDS
Primary Manufacturing							
All permitted Wholesaling uses with accessory Perishable Goods Manufacturing limited to baked goods/confectionary products					P	P	<b>OCR-1, OCR-2:</b> Accessory use limited to 50% of the gross floor area.

DRAFT

4.8.6. PERMITTED USES: INDUSTRIAL ZONES

<b>TABLE 4.8-6: Permitted Uses – INDUSTRIAL ZONES</b> <i>P = Permitted Use      S = Permitted as Special Exception Use</i> [1] Mayor and Council Special Exception Procedure, Sec. 3.xxx [2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx [3] Administrative Special Exception Procedure, Sec. 3.xxx				
LAND USE*	P-1	I-1	I-2	USE SPECIFIC STANDARDS
<b>Agricultural Land Use Group With Land Use Class/Type:</b>				
Stockyard Operation			S [1]	
<b>Civic Land Use Group With Land Use Class/Type:</b>				
Civic Assembly		P		
Correctional Use: Custodial Facility		S [1]	S [1]	<b>I-1, I-2:</b> 4.9.3.B.1.a, 2.b, 3.b, 6, 7 & 8 Minimum 1 acre site
Correctional Use: Jail or Prison		S [1]	S [1]	<b>I-1 &amp; I-2:</b> 4.9.3.B.1.e, 2.d, 3.c, 4.c, 5, 6, 7 & 8 Minimum 30 acre site
Correctional Use: Jail or Prison			S [1]	<b>I-2:</b> 4.9.3 B.4.b, 5, 6, 7, 8 & 10 Minimum 150 acre site
Cultural Use		P		
Educational Use: Elementary and Secondary Schools, Limited to Grades 9 -12	S [2]	S [2]		<b>P-I:</b> 4.9.3.D.9
Educational Use: Instructional School or Postsecondary Institution		P		
Educational Use with accessory Salvaging and Recycling	S [2]	S[2]		<b>P-I, I-1:</b> 4.9.5.G.1, .3
Membership Organization		P		
Postal Service		P		
Religious Use		P		
Religious Use with accessory Salvaging and Recycling		P		<b>I-1:</b> 4.9.5.G.1, .3
<b>Commercial Services Land Use Group With Land Use Class/Type:</b>				
Administrative and Professional Office	P	P	P	
Alcoholic Beverage Service General		P		<b>I-1:</b> 4.9.4.C.3
Alcoholic Beverage Service Large Bar		S [1]	S [1]	<b>I-1, I-2:</b> 4.9.4.C.2, .4
Alcoholic Beverage Service with accessory Perishable Goods Manufacturing		P		<b>I-1:</b> 4.9.5.E.6, .7, .8
Animal Service		P		
Automotive – Service and Repair Excludes bodywork & paint-booths		P	P	

**TABLE 4.8-6: Permitted Uses – INDUSTRIAL ZONES**

P = Permitted Use S = Permitted as Special Exception Use

[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx

[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx

[3] Administrative Special Exception Procedure, Sec. 3.xxx

LAND USE*	P-1	I-1	I-2	USE SPECIFIC STANDARDS
Billboard		P	P	I-1, I-2: 4.9.4.G & Tucson Code, Ch. 3 Standards
Buildings and Ground Maintenance		P	P	
Commercial Recreation		P		
Communications				Being Updated by Staff
Construction Service		P		
Day Care	P	P	P	
Entertainment General		P		I-1: 4.9.4.K.1, .2, .3, .4 & 4.9.4.C.3
Entertainment Dance Hall		S [1]	S [1]	I-1, I-2: 4.9.4.C.2, .4
Financial Service General		P	P	I-1, I-2: 4.9.4.L.3
Financial Service Drive-through Permitted	P		P	P-I, I-2: 4.9.4.L.3
Food Service Excludes Soup Kitchen	P	P	P	P-I: 4.9.4.M.1
Food Service Soup Kitchen		S [1]		I-1: 4.9.4.M.4
Food Service with accessory: Alcoholic Beverage Service	P			P-I: 4.9.4.M.1 & 4.9.4.V.1-2 & 4.9.4.C.3
Funeral Service		P		
Medical Service: Extended Healthcare		P		
Medical Service: Major		P		
Medical Service: Outpatient Excludes Blood Donor Center	P	P		
Medical Service Blood Donor Center		S [1]	S [1]	I-1 & I-2: 4.9.4.O.3
Parking	P	P	P	
Personal Service	P	P		
Research and Product Development	P	P	P	P-I: 4.9.5.C.5, .6, .8
Technical Service	P	P	P	
Trade Service and Repair Major (includes auto body shops/paint-booths) or Minor		P	P	I-1, I-2: 4.9.4.X.1
Transportation Service Air Carrier			S [1]	
Transportation Service Land Carrier		P	P	
Travelers Accommodation: Lodging	P	P	P	P-1, I-1, I-2: 4.9.4.BB & 4.9.4.V
All Commercial Services Permitted Uses with accessory Salvaging and Recycling	P	P	P	P-1, I-1, I-2: 4.9.5.G.1, .3
<b>Industrial Land Use Group With Land Use Class/Type:</b>				
Craftwork	P	P	P	P-I, I-1, I-2: 4.9.5.C
Extraction			S [1]	I-2: 4.9.5.B
General Manufacturing	P	P	P	P-I, I-1, I-2: 4.9.5.C
Manufacturing, Hazardous Material			S [1]	I-2: 4.9.5.C
Manufacturing, Heavy Equipment			P	I-2: 4.9.5.C.
Motion Picture Industry	P	P	P	Minimum lot size 36 acres and: P-I, I-1, I-2: 4.9.5.C.
Perishable Goods Manufacturing	P	P	P	P-I, I-1, I-2: 4.9.5.E.1, .2 & 4.9.5.C.

<b>TABLE 4.8-6: Permitted Uses – INDUSTRIAL ZONES</b>				
<i>P = Permitted Use                      S = Permitted as Special Exception Use</i>				
[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx				
[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx				
[3] Administrative Special Exception Procedure, Sec. 3.xxx				
LAND USE*	P-1	I-1	I-2	USE SPECIFIC STANDARDS
Perishable Goods Manufacturing		S [2]	S [1]	I-1, I-2: 4.9.5.C
Precision Manufacturing	P	P	P	P-1, I-1, I-2: 4.9.5.C
Precision Manufacturing with accessory: Construction Material Sales; Food and Beverage Sales; General Merchandise Sales; Heavy Equipment Sales.	P			P-1: 4.9.5.C.8
Precision Manufacturing with accessory: Salvaging and Recycling	P	P	P	P-1, I-1, I-2: 4.9.5.G.1, .3
Primary Manufacturing			S [1]	I-2: 4.9.5.C
Processing and Cleaning	P	P	P	P-1, I-1, I-2: 4.9.5.C
Processing and Cleaning with accessory: Construction Material Sales; Food and Beverage Sales; General Merchandise Sales; Heavy Equipment Sales.	P			P-1: 4.9.5.C.8
Processing and Cleaning with accessory: Salvaging and Recycling	P	P	P	P-1, I-1, I-2: 4.9.5.G.1, .3
Refining			S [1]	I-2: 4.9.5.C
Salvaging and Recycling	P	P	P S [1]	(P) P-1: 4.9.5.C.2 & 4.9.5.G.2, .4, .5 (P) I-1: 4.9.5.G.2, .4 (P) I-2: 4.9.5.G.2, .4, .13 (S) I-2: 4.9.5.C.1 - 8
Salvaging and Recycling with accessory: Construction Material Sales; Food and Beverage Sales; General Merchandise Sales; Heavy Equipment Sales.	P			P-1: 4.9.5.C.8
Salvaging and Recycling: Limited to Household Goods Donation Center			P	I-2: 4.9.5.G.2, .6, & 4.9.13.C; 4.9.13.D
<b>Recreation Land Use Group With Land Use Class/Type:</b>				
Golf Course		P		I-1: 4.9.6.A.1.f, .g, .i
<b>Residential Land Use Group With Land Use Class/Type:</b>				
Family Dwelling		S [3]		I-1: 4.9.7.A
Family Dwelling with Permitted Land Use	P	P	P	P-1, I-1, I-2: 4.9.7.C
Residential Care Services: Rehabilitation Service or Shelter Care (permitted and special exception)	P S [2]	P	S [2]	(P) P-1: 4.9.7.I.1, 3.d, .4, .5 (P) I-1: 4.9.7.I.1, 3.d, .4, .5, .6, .11 (S) P-1, I-2: 4.9.7.I.1, 3.d, .4, .5
Residential Care Services: Shelter Care, Victims of Domestic Violence	P	P		P-1: 4.9.7.I.1, 3.c, .4, I-1: 4.9.7.I.1, 3.c, .4, .11
<b>Restricted Adult Activities Land Use Class With Land Use Type:</b>				
Adult: Commercial Services, Industrial, Recreation, or Retail Trade		P		I-1: 4.9.8.A
<b>Retail Trade Land Use Group With Land Use Class/Type:</b>				
Auctions		P		I-1: 4.9.9.F
Construction Material Sales		P	P	
Food and Beverage Sales, General		P		

<b>TABLE 4.8-6: Permitted Uses – INDUSTRIAL ZONES</b>				
<i>P = Permitted Use      S = Permitted as Special Exception Use</i>				
[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx				
[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx				
[3] Administrative Special Exception Procedure, Sec. 3.xxx				
LAND USE*	P-1	I-1	I-2	USE SPECIFIC STANDARDS
Food and Beverage Sales: Large Retail Establishment		S [1]		I-1: 4.9.9.D
Permitted Retail uses with accessory Food and Beverage Sales			P	I-2: 4.9.9.A
General Merchandise Sales, General		P	P	
General Merchandise Sales Large Retail Establishment		S [1]	S [1]	I-1: 4.9.9.D
Heavy Equipment Sales		P	P	I-1, I-2: 4.9.9.C
Medical Marijuana (Designated Caregiver or Off-Site) Cultivation Location		P	P	I-1, I-2: 4.9.9.E.2
Medical Marijuana Qualifying Patient Cultivation Location		P	P	I-1, I-2: 4.9.9.E.4
Permitted Retail uses with accessory Salvaging and Recycling		P		I-1: 4.9.5.G.1, .3
Swap Meets and Auctions	S [3]	S [3]	P	P-1, I-1, I-2: 4.9.9.F
Vehicle Rental and Sales	P	P	P	P-1: 4.9.9.G.2, .3 I-1, I-2: 4.9.9.G.1
<b>Storage Land Use Group With Land Use Class/Type:</b>				
Commercial Storage	P	P	P	P-1: 4.9.10.A & 4.9.5.C.8 I-1, I-2: 4.9.10.A
Commercial Storage with accessory: Construction Material Sales; Food and Beverage Sales; Heavy Equipment Sales; General Merchandise Sales	P			P-1: 4.9.10.A & 4.9.5.C.8
Commercial Storage with accessory: Hazardous Material Storage	P	P	P	P-1: 4.9.10.B.1, 2.a I-1, I-2: 4.9.10.B.1, 2.d
Hazardous Material Storage			S [1]	
Personal Storage		P	P	I-1, I-2: 4.9.10.C.3, .6
Personal Storage Uses with accessory: Construction Material Sales; Food and Beverage Sales; Heavy Equipment Sales; General Merchandise Sales	P			P-1: 4.9.10.A & 4.9.5.C.8
Personal Storage with accessory: Hazardous Material Storage	P	P	P	P-1: 4.9.10.B.1, 2.a I-1, I-2: 4.9.10.B.1, 2.d
<b>Utilities Land Use Group With Land Use Class/Type:</b>				
Distribution System	P	P	P	P-1, I-1, I-2: 4.9.11.A.1, .2, .4
Renewable Energy Generation	P	P	P	P-1, I-1, I-2: 4.9.11.B.2, .3, .5
Sanitation System			S [1]	I-2: 4.9.11.C
<b>Wholesaling Land Use Group With Land Use Class/Type:</b>				
Business Supply & Equipment Wholesaling	P	P	P	P-1: 4.9.5.C.8
Business Supply & Equipment with accessory: Construction Material Sales; Food and Beverage Sales; Heavy Equipment Sales; General Merchandise Sales	P			P-1: 4.9.5.C.8
Construction/Heavy Equipment Wholesaling	P	P	P	P-1: 4.9.5.C.8

**TABLE 4.8-6: Permitted Uses – INDUSTRIAL ZONES**

*P = Permitted Use                      S = Permitted as Special Exception Use*

*[1] Mayor and Council Special Exception Procedure, Sec. 3.xxx  
[2] Zoning Examiner Special Exception Procedure, Sec. 3.xxx  
[3] Administrative Special Exception Procedure, Sec. 3.xxx*

LAND USE*	P-1	I-1	I-2	USE SPECIFIC STANDARDS
Construction/Heavy Equipment w/ accessory; Construction Material Sales; Food and Beverage Sales; Heavy Equipment Sales; General Merchandise Sales	P			P-1: 4.9.5.C.8
Food and Beverage Wholesaling	P	P	P	P-1: 4.9.5.C.8
Food and Beverage with accessory; Construction Material Sales; Food and Beverage Sales; Heavy Equipment Sales; General Merchandise Sales	P			P-1: 4.9.5.C.8
Hazardous Material Wholesaling			S [1]	

\*Any Land Use Class not permitted or a Special Exception Use in any other zone, or permitted in the I-2 zone, may be permitted in the I-2 zone and shall comply with the dimensional standards determined to be most similar to the proposed use.

DRAFT

## 4.9. USE-SPECIFIC STANDARDS<sup>41</sup>

### 4.9.1. GENERAL

#### A. Purpose

The use-specific standards in this section are intended to provide additional standards for certain permitted and special exception land uses in order to mitigate any adverse impacts on adjacent land uses, on the immediate neighborhood, and on the community.

#### B. Applicability

These requirements are in addition to those required of principal buildings in Article 6: Dimensional Standards of the UDC and are applied only when required in a zone for a particular land use. Use specific standards shall apply where the standards in Article 6 and use-specific standards differ (e.g., lot coverage).

### 4.9.2. AGRICULTURAL USE GROUP

#### A. Animal Production

##### 1. Provisions Relating to Animals in General

- a. All buildings for animals shall be setback at least 50 feet from all property lines, except corrals that shall be setback ten feet from all property lines.
- b. All stables, barns, and animal sheds or shelters shall be setback at least 100 feet from any property line.
- c. Minimum lot size shall be 36,000 square feet.

##### 2. Provisions Relating to Livestock

- a. No more than two horses or two head of cattle are permitted per each 36,000 square feet of lot area.
- b. A stock-tight fence and necessary cattle guards shall be erected and maintained along the boundaries of any area where livestock is kept or grazed. This provision shall not apply to interior lot lines where the adjacent property is zoned IR or to open range as determined under Arizona Revised Statutes (ARS).
- c. All horses, cattle, sheep, goats, or similar animals shall be confined within a stock-tight fence in an area of no less than 400 square feet per animal. Such fenced-in area shall be setback ten feet from the rear property line where it abuts an IR, RH, SR, SH, RX-1, or RX-2 zone; 40 feet from the rear where it abuts any other zone; and 40 feet from a side property line. A setback of ten feet shall be permitted on the side yard where the adjacent property owners have a written recorded agreement to this effect, but in no event shall a corral be closer than 50 feet to any residence or living quarters on an abutting property.

##### 3. Provisions Relating Specifically to Hogs

- a. No hogs shall be permitted.

<sup>41</sup> Text from LUC Section 3.5.



4.9.3. CIVIC USE GROUP

A. Cemetery

1. The use shall be adjacent to, or an extension of, an existing cemetery.
2. The minimum site area shall be one acre for a pet cemetery and five acres for a human cemetery.
3. All buildings shall be setback at least 100 feet from any property line.
4. The use shall be limited to the storage of cremated remains in a columbarium.
5. Minimum lot size shall be 10 acres.
6. The side setback shall be 25 feet and the rear setback shall be 50 feet.

B. Correctional Use

1. Minimum Required Site Size

- a. One acre.
- b. Five acres.
- c. Ten acres.
- d. 15 acres.
- e. 30 acres.

2. Maximum Number of Beds

- a. The maximum number of beds permitted shall be 40.
- b. The number of beds permitted shall be calculated by dividing the area of the site by 2,200 square feet, with a maximum permitted capacity of 40.
- c. The maximum number of beds permitted shall be 60, with no more than 40 offenders in the Custodial Facility and no more than 20 offenders in the Supervision Facility.
- d. The maximum number of beds permitted shall be 1,250.

3. Separation: A Correctional Use shall be separated from other public or private Correctional Uses, Rehabilitation Service Uses, and Shelter Care Uses, as determined by the zone in which the Correctional Use is located. The applicant for a Correctional Use shall provide documentation of compliance with the required separation distances.

- a. 1,200 feet.
- b. 1,200 feet from a Supervision Facility, Rehabilitation Service, or Shelter Care and four miles from a Custodial Facility or a Jail or Prison.
- c. 1,200 feet from a Supervision Facility, Rehabilitation Service, or Shelter Care; four miles from a Custodial Facility; and five miles from a Jail or Prison.

4. Minimum Interior Yard Setbacks: Minimum interior yard setbacks shall be required for any structure, including a fenced enclosure, and shall be measured to the property line.

- a. 50 feet.
- b. 100 feet.
- c. 500 feet.
- d. Zero setback if adjacent to nonresidential zone or development and 80 foot setback if adjacent to residential zone or development.

**5. Building Height**

- a. The maximum building height permitted shall be 50 feet, except for guard towers that may be up to 60 feet in height.
- b. The maximum height permitted shall be 25 feet.

**6. Site Location:** The site shall be located at least 300 feet from the property line to a zone boundary line of R-3 or more restrictive zoning, or for sites where Sec. 4.9.3.C.10 is applicable, the 300 foot setback does not apply to residentially zoned property used for a prison or jail or to residentially zoned property used as a public right-of-way or railroad right-of-way.

**7. Management Plan:** The applicant shall submit to the Zoning Administrator and the Police Department a management plan. See Administrative Manual for management plan submittal requirements.

**8. Licensure:** If licensing is required for the use, proof of such licensure shall be provided prior to the issuance of a certificate of occupancy for the use. If licensure is not required, the applicant shall provide documentation to that effect.

**9. Loudspeakers:** The use of outdoor speakers shall be prohibited.

**10. Prison Clustering Provisions**

- a. The site area shall be a minimum of 150 acres.
- b. The site shall be located within one-half mile of at least one jail or prison facility owned and operated by the federal or state government, and the jail or prison has a minimum design capacity of 500 beds.
- c. The project shall not adversely affect adjacent land uses or surrounding neighborhoods. Adverse effects can be substantially mitigated through the application of additional conditions.

**C. Cultural Use**

Cultural Uses shall be subject to the following use specific standards that are not subject to variance, however, if one or more of the standards cannot be met, the Mayor and Council can modify the standards for a specific site where there is substantial conformance with the intent of the use specific standards.

1. The use shall be setback at least 100 feet from any property line.
2. The use shall provide a visual buffer where the site is adjacent to a residential use or zone. This can be accomplished by providing, for example, a landscape buffer, setbacks of buildings or uses, or masonry screen walls.
3. Storage of fertilizer, manure, or other odorous material located in an enclosed building shall be setback a minimum of 20 feet or if located outdoors shall be

---

setback a minimum of 40 feet from any property line that is adjacent to a residential use or zone.

4. Public access to the site shall be from a Major Streets and Routes (MS&R) street or from a local street that is not an internal residential neighborhood street.
5. The impacts of noise on adjacent residential uses shall be mitigated to comply with the noise standards in the Tucson Code, Chapter 16, Sec. 16-31.
6. Hours of operation for the cultural use, as well as any accessory use, should be detailed in the application and should be limited, in order to assure compatibility with adjacent residential uses.
7. Outdoor lighting shall be limited in height and shielded from adjacent residential uses.
8. Trip generation and traffic impacts on the surrounding streets shall be analyzed, and mitigation measures shall be provided.

**D. Educational Uses**

Educational Uses shall be subject to the following use specific standards. No variances shall be permitted; however, if the standards cannot be met, the applicant can request approval through a special exception procedure if permitted within the zone.

**1. Licensing**

- a. If licensing, certification, or similar type of approval is required by the State of Arizona for the use, proof of such licensure, certification, or approval shall be provided. Such information shall include the number of students for which the school is approved.
- b. If the number of students approved by the State exceeds the number approved on the site in accordance with zoning requirements, the number of students shall be limited to the number that meet zoning requirements.

**2. Site Area**

- a. Except as provided below for charter schools, the minimum required site area for educational uses in residential zones is five acres, unless a greater site area is required in Art. 6: Dimensional Standards, or the ratio of 1,452 square feet of site area for each student proposed for the school, whichever is greater, up to a maximum of ten acres for elementary schools (Grades K-6), 20 acres for middle schools (Grades 7 and 8), and 40 acres for high schools (Grades 9-12). For the purposes of this requirement, the number of students applied in this calculation is the number for which the school has been approved by the authorizing agency. If a maximum number of students is not stipulated as part of the approval from the authorizing agency, then the number used in the calculation shall be the amount proposed by the applicant.
- b. A single family residence on less than one acre shall not be occupied as or converted into a charter school.
- c. In nonresidential zones, the minimum site area shall be in accordance with the requirements in Art. 6: Dimensional Standards for the use.

3. **Hours and Days of Operation**  
Educational Uses within Neighborhood Commercial (NC) or more restrictive zoning shall be limited in hours of operation to 6:00 a.m. to 7:00 p.m., Monday through Friday only.
  4. **Outdoor Activity**  
All outdoor activity shall be held more than 50 feet away from the property line where adjacent to R-3 or more restrictive zoning. The use of loudspeakers, amplifiers, or similar type equipment outdoors shall not be permitted on the school site within 100 feet of the property line where adjacent to R-3 or more restrictive zoning.
  5. **Vehicular and Pedestrian Access**  
Vehicular and pedestrian access to the Educational Use site shall be from a street designated as a major street by the Major Streets and Routes (MS&R) Plan or from a local street other than an internal residential neighborhood street for sites zoned C-1 or more restrictive zoning.
  6. **Building Setback**  
Building setbacks may be reduced on the side of the building adjacent to R-3 or more restrictive zoning if windows are non-operable and doors are limited to alarmed emergency exit doors. (Figure 4.9-A IS BEING UPDATED)
  7. **Passenger Drop-Off Areas**  
Passenger drop-off parking areas shall be provided at a ratio of one motor vehicle parking space (parallel) for every 20 students for which the school is authorized, up to a total of eight spaces. These spaces shall be in addition to the required off-street parking spaces.
  8. **Lot Coverage**  
The maximum lot coverage shall be 20 percent.
  9. **Height**  
The maximum height shall be 75 feet.
- E. **Postsecondary Institutions**  
Teaching of only those operations or occupations that are permitted in the zoning classification of the property as permitted uses is permitted.
- F. **Religious Use**
1. The use shall be setback at least 80 feet from any property line.
  2. Minimum lot size shall be 20,000 square feet.

**4.9.4. COMMERCIAL SERVICES USE GROUP**

**A. Administrative and Professional Office**

1. Maximum floor area shall be 2,000 square feet.
2. Minimum site area shall be 43,460 square feet.
3. Maximum lot coverage shall be 20 percent.

**B. Adult Day Care**

1. The use shall be for a maximum of ten persons, or if operated in conjunction with an Adult Care Service, the number of clients together with the number of residents shall be exceed the total permitted for the Adult Care Service.
2. The use shall comply with one of the following.
  - a. For a maximum of 15 persons;
  - b. For an unlimited number of persons with a minimum lot size of 20,000 square feet; or
  - c. If operated in conjunction with an Adult Care Service, the total number of clients and residents shall not exceed the total permitted for the Adult Care Service.

**C. Alcoholic Beverage Service and Entertainment**

1. Maximum floor area shall be 2,000 square feet.
2. Large bar or dance hall.
  - a. **Minimum Setbacks**

Setbacks for the following use areas shall be measured from the use area to a zone boundary line of R-3 or more restrictive zoning.

    - (1) Outdoor Use Area: 500 feet.
    - (2) Parking Area: 200 feet.
    - (3) Loudspeakers: 500 feet.
    - (4) The Zoning Examiner may authorize a reduction to the required setbacks if special physical circumstances exist that will still mitigate any negative impacts.
  - b. **Security Management Plan**

The applicant shall submit to the Zoning Administrator and the Police Chief a security management plan describing the method and operation of security within and outside the building, including the parking area. Any changes or amendments to the plan shall be filed with, and approved by, the Zoning Administrator and the Police Chief.
  - c. **Access**

Access shall be either from a street shown on the Major Streets and Routes (MS&R) Map with no vehicular access to the site from a local street or from a local street within a nonresidential development.

3. Large bars and dance halls shall be prohibited.
4. Height shall be limited to 300'

**D. Animal Service**

1. Overnight confinement for clinic treatment shall be permitted for a maximum of five animals.
2. No boarding of animals shall be permitted.
3. The activity shall be within a completely enclosed building.
4. An outpatient clinic shall be permitted for small animals only.
5. Buildings, shelters, animal runs, and fenced areas shall be setback at least 100 feet from any property line abutting residentially zoned property.
6. Buildings, shelters, animal runs, and fenced areas shall be setback at least 100 feet from any property line.
7. The use shall be setback at least 200 feet from any residential zone.
8. Minimum lot size shall be 144,000 square feet.

**E. Artisan Residence**

**1. Purpose**

To provide an artisan residence use in the NC, C-1, C-2, and C-3 commercial zones designed to be used as both a dwelling and work space by an artist, artisan, or craftsman, including persons engaged in the application, teaching, or performance of fine arts such as, but not limited to drawing, vocal or instrumental music, painting, sculpture, and writing; and the accessory sale of art objects produced on the premises. Buildings or spaces within buildings shall be used jointly for commercial and residential purposes. Nothing in this subsection shall limit principal uses as otherwise permitted by the applicable zoning.

**2. Combined Uses**

A building or a tenant space in a commercial zone may be used as an artisan workshop with a residential dwelling. The workshop and workshop activities shall be located indoors unless outdoor activity is permitted by the applicable zoning.

**3. On-site Sales**

The on-site sale of the artist's products, including occasional shows of the artist's works, shall be permitted accessory uses.

**4. Separation and Access**

Access to the residential use shall be only through the same access that is provided for the artisan use.

**5. Operational Requirements**

The operation of the artisan residence shall not create noise, vibrations, smoke, fumes, dust, odors, vapors, other noxious emissions, or any other similar nuisances that are discernible beyond the boundaries of the building enclosing the artisan residence.

**6. Parking**

Each artisan residence unit shall provide two on-site motor vehicle parking spaces for each residential component and one on-site parking space for each 500 square feet of gross floor area (GFA) of the work space area. The GFA of the residential component shall not be included in the parking calculation.

**F. Automotive - Service and Repair**

1. No auto washing shall be permitted.
2. The service building shall be limited in design to accommodate no more than two vehicles at any time. Vehicle space size shall be a maximum of ten by 25 feet.
3. The use shall occur within an enclosed building with one access per bay, not on the side toward any residential zone.
4. The building walls shall have no openings, other than non-opening windows, within 30 feet of the adjacent residential zone boundary line.
5. Auto washing, limited to a self-service, coin-operated car wash, shall be permitted on the premises. No more than six bays using hand-operated, wand-type equipment or more than one bay using non-conveyor, automatic equipment are permitted, and vacuum equipment shall be located at least 100 feet from any residential zone.
6. The maximum floor area shall be 2,000 square feet.
7. Limited to one automatic in-bay car wash that shall not include conveyors or motorized air-drying. It shall be enclosed within a building except at points of ingress and egress, have a maximum floor area of 600 square feet, and not exceed 12 feet in height.
8. Height shall be limited to 75 feet.

**G. Billboards**

**1. Pedestrian Access**

Pedestrian access shall not be located under, or within five feet of, a vertical line intersecting the ground and any structural element extending from a billboard, including, but not limited to, overhangs, cantilevered beams, and elevated walkways. Refer to Sec. XXX for requirements.

**2. Parking**

Parking area access lanes shall not be located under, or within five feet of, a vertical line intersecting the ground and any structural element extending from a billboard, including, but not limited to, overhangs, cantilevered beams, and elevated walkways. Refer to Sec. 7.4.6.B for location requirements of parking spaces.

**3. Loading**

Refer to Sec. 7.5 for loading (servicing) space requirements and Sec. 7.5.4 for location requirements for such loading spaces.

4. **Landscaping and Screening**  
Refer to Table 7.6.4-1 for landscaping and screening requirements for billboards.
5. **Height**  
Maximum height shall be 30 feet.

#### H. **Child Care in Residential and Office Zones**

1. **Dispersal**  
A 600 foot separation between child care centers in residential zones shall be required. Child care centers that provide only before- and after-school programs at elementary and secondary school sites are not considered for the purposes of this separation. The separation distance shall be measured from property lines, except in the case of a child care center on a mixed use development site where the separation is measured from that portion of the site devoted to the child care use.
2. **Licensing**  
If licensing is required by the State of Arizona for the use, proof of such licensure shall be provided prior to issuance of a certificate of occupancy.
3. **Hours and Days of Operation**  
Child care centers adjacent to R-3 or more restrictive zoning shall be limited in hours of operation to 6:00 a.m. to 7:00 p.m. and to operation Monday through Friday only, except as provided in Sec. 4.9.4.H.9.
4. **Building Setbacks**  
Building setbacks may be reduced on the side of the building adjacent to R-3 or more restrictive zoning if windows are non-operable and doors are limited to alarmed emergency exit doors. (Figure 4.9-B. IS BEING UPDATED)
5. **Recreational Areas**  
Minimum distance of outdoor recreational areas, including, but not limited to, swimming and wading pools, ball fields, and playground equipment, to any adjacent property in R-3 or more restrictive zoning shall be 25 feet. Where abutting a street or alley, the setback shall be measured to the centerline of a right-of-way. A wall shall be required between a recreation area provided on site and adjacent to R-3 or more restrictive zoning.
6. **Number of Children**  
The maximum number of children cared for shall be as follows.
  - a. 30 children.
  - b. 100 children.
  - c. Unlimited number of children.

**7. Site Size**

The minimum required site size shall be as follows. In no case will a site larger than ten acres be required.

- a. Six and six-tenths (6.6) acres in RH and SR.
- b. 72,000 square feet in SH and RX-1.
- c. 32,000 square feet in RX-2.
- d. 14,000 square feet in R-1, R-2, and O-2.
- e. 10,000 square feet in R-3 and O-3.
- f. The minimum required site size shall be equal to the minimum site size required for the zone in Sec. 4.9.4.H.7.a, .b, .c, or .d for the zoning district, divided by 30 and multiplied by the maximum enrollment for which the center is licensed.
- g. The minimum required site size shall be equal to 200 square feet per child, multiplied by the maximum enrollment for which the center is licensed, plus 4,000 square feet.

**8. Street Frontage**

The center shall front on a Major Streets and Routes (MS&R) street with no vehicular access to the site from a local street or on a local street within a nonresidential development. The street frontage requirements shall be apply to a child care center located on an elementary school site if the child care center is in conformance with the dispersal, licensing, recreational area and building setbacks, hours and days of operation limitations, and site coverage standards.

**9. Extended Hours for Any Number of Children**

In addition to the requirements of Sec. 4.9.4.H.1, .2, .3, and 8, a child care use that operates before 6:00 a.m. or after 7:00 p.m. or on Saturday or Sunday where the site is adjacent to R-3 or more restrictive zoning shall comply with the following.

**a. Site Size**

The minimum site size for a child care center with extended hours of operation or weekend operation shall be two and one half acres, except in RH and SR where the minimum site shall be ten acres.

**b. Building Setback**

The minimum building setback shall be 75 feet from a property line adjacent to R-3 or more restrictive zoning.

**c. Recreational Areas**

Outdoor recreational areas, including, but not limited to, swimming and wading pools, ball fields, and playground equipment, shall be screened and setback from any property line adjacent to R-3 or more restrictive zoning as follows.

- (1) A wall, as defined in screening materials, shall be required between a recreational area and the adjacent property line.
- (2) The minimum setback from the adjacent property in R-3 or more restrictive zoning shall be 100 feet. Where abutting a street, alley, drainage-way, or other right-of-way, the setback shall be measured to the centerline of a right-of-way.
- (3) A reduction to the required recreational area setback may be requested in accordance with Sec. 3.xxx Variances, if the reduction meets the requirements set forth for special exception land uses.

**d. Vehicular Use Areas**

Vehicular use areas shall be designed so that no more than 50 percent of the parking spaces provided are within 50 feet of an interior property line adjacent to R-3 or more restrictive zoning.

**I. Communications (This section being updated by Staff)**

**J. Construction Service**

1. The use shall be setback at least 100 feet from any property line.
2. The yard shall be completely enclosed by screening a minimum of six feet in height.

**K. Entertainment**

1. A circus, carnival, or tent show shall be permitted for no longer than 15 days.
2. Circuses, carnivals, and tent shows shall be subject to zoning compliance review and approval through Zoning Compliance Review, Sec. 3.xxx.
3. A circus, carnival, or tent show shall be setback 100 feet from the activity to the lot line of any residential use or zone.
4. Motor vehicle parking areas and bicycle facilities for a circus, carnival, or tent show shall be dust-proofed, and access to the vehicular use areas shall be identified and controlled to minimize vehicular and pedestrian conflicts.
5. The use shall be setback at least 200 feet from any property line.
6. Concerts, dances, and other similar high-noise activities shall be conducted entirely within an enclosed building or setback a minimum of 600 feet from adjacent residentially zoned property. Modification of this criterion may be permitted by the Mayor and Council through the special exception process provided:
  - a. All speakers and similar sound projecting devices are oriented away from adjacent residentially zoned properties;
  - b. The applicant will develop a noise mitigation plan for the use based on the specific activities proposed and the proximity of such activities to the residential property line;

- c. Noise levels are continuously monitored during the performance, and noise emission standards are enforced by a cultural use employee (or designee); and
- d. The performance ends no later than 10:00 p.m.

**L. Financial Service**

- 1. Limited to a maximum of three drive-through service lanes, with one restricted to drive-through automated teller machine (ATM) service only.
- 2. The use shall be setback at least 100 feet from any property line.
- 3. No non-chartered financial institution facilities, such as payday loan facilities, except where permitted as a special exception under Sec.4.9.4.L.4.
- 4. Non-Chartered financial institutions shall require approval as a special exception by the Zoning Examiner in accordance with procedures set forth in Sec. 3.xxx and provided that:
  - a. A non-chartered financial institution site shall be separated from other non-chartered financial institution sites by a distance of 320 feet.
  - b. A non-chartered financial institution site shall be located at least 500 feet, measured in a straight line, from the property line to a zone boundary line of R-3 or more restrictive zoning.

**M. Food Service**

- 1. Activities may be conducted outdoors. Loudspeakers or music, live or recorded, shall not be permitted within 600 feet of a residentially zoned property.
- 2. Dancing shall not be permitted. Drive-in or drive-through restaurants shall not be permitted.
- 3. Soup kitchens shall not be permitted.
- 4. Soup kitchens shall comply with the following standards.
  - a. The use shall be conducted within a completely enclosed building.
  - b. Seating shall be provided at 100 percent of the meal service capacity.
  - c. A waiting area shall be provided within the building for a minimum of one-half of the total number of persons to be served.
  - d. Public rest rooms shall be provided.
  - e. No other soup kitchen use shall be located within one mile.
- 5. To differentiate between a restaurant that serves alcoholic beverages and a bar that serves food, a restaurant meets the following standards.
  - a. The full kitchen remains open and meals are available to patrons during all hours of operation, except as follows. Restaurants open later than 10:00 PM must keep the full kitchen open until at least 10:00 PM to maintain their classification as a Restaurant
  - b. Management cannot ask for age verification (carding) for admittance to the establishment.

- c. Management cannot restrict patronage by age or sex (i.e., Ladies Night, Over 21, etc.) except for limited special services or events within certain limited areas of the establishment.
- d. A cover charge cannot be required for general admittance, except for special services or events offered within certain areas of the establishment.
- e. Management shall maintain a minimum amount of table seating at all times and not have tables removed to create a dance floor or set aside major sections of the establishment for special events.
- f. The gross revenue sale of food complies with A.R.S. § 4-205.02(G)(2)

**N. Funeral Service**

- 1. A crematorium shall be setback a minimum of 200 feet from any property line.
- 2. A crematorium shall be setback a minimum of 500 feet from any boundary of the site that adjoins property in a residential zone.

**O. Medical Service**

- 1. The use shall provide a minimum of one off-street loading space or the number of spaces required per Sec. 7.4, whichever is greater.
- 2. Blood donor centers shall not be permitted.
- 3. Blood donor centers shall comply with the following standards.
  - a. The site is not located in the same block as a residential zone or any elementary or secondary school or Day Care use.
  - b. The site is located at least 300 feet, measured in a straight line, from the property line to a residential zone boundary line or the property line of an elementary or secondary school.
  - c. A waiting area equal to ten percent of the gross floor area is provided.
  - d. No other blood donor center is located within 1,200 feet.
- 4. Minimum site area shall be 1.5 acres.
- 5. Minimum site area shall be 144,000 square feet.
- 6. Minimum site area shall be 180,000 square feet.
- 7. Height shall be limited to 75 feet.

**P. Medical Service in Residential and Office Zones Standards**

- 1. The facility shall front on a street on the Major Streets and Routes (MS&R) Plan or on a residential street, provided:
  - a. The residential street shall intersect a street on the MS&R Plan, and
  - b. The property shall be within 150 feet of a street on the MS&R Plan, measured along the residential street.
- 2. Minimum Setbacks.

- a. A minimum building setback of 20 feet from any interior lot line adjoining residential zoning shall be required.
  - b. A minimum building setback of 100 feet from any property line shall be required.
  3. Requests to vary the provisions of this section, including setbacks for existing or new buildings, are processed in accordance with Sec. 3.xxx Variances.
  4. If licensing is required by the State of Arizona for the use, proof of such licensure shall be provided.
- Q. Major Medical Service and Outpatient Medical Service, Accessory Uses**
1. The use shall be located within a principal building.
  2. Access to the use shall be from within the principal building or from the interior of the development.
  3. No outside display or storage of merchandise or supplies.
  4. No sign associated with accessory uses shall be visible from any public street.
  5. Sale of items shall be restricted to those associated with medical services.
- R. Office Zone Compatibility Standards**
1. Chain link fencing shall not be used to meet screening requirements.
  2. Refuse areas shall be setback at least 20 feet from street property lines and interior property lines abutting a residential use or zone, except when alley pickup is approved by the Environmental Services Department.
  3. Refuse areas shall be screened from the street with materials similar to those of the principal building.
  4. Noise-generating equipment shall be located in an area away from adjacent residential uses or vacant residentially zoned property.
  5. Vehicular access shall be from other than internal residential neighborhood streets.
  6. Consolidation of parking areas and access points shall be required for sites with multiple buildings. Consolidation of parking areas and access points is encouraged for adjoining sites.
  7. New construction shall be reviewed by the Design Review Board (DRB) for architectural and site design compatibility with the surrounding residential area. See the Administrative Manual for DRB submittal requirements.
- S. "P" Parking Zone Standards**
1. Parking shall be restricted to at or below grade. Buildings to cover at-grade parking shall be permitted.
  2. Height shall be limited to 16 feet.
- T. Personal Service**
1. Laundry facilities shall not exceed 3,000 square feet of floor area.
  2. An attendant shall be on the premises during all open hours.
  3. No more than 24 dry cleaning units shall be permitted.

4. The maximum floor area shall be 2,000 square feet.

**U. Research and Product Development**

1. All land use operations, including storage, shall be housed within a completely enclosed building. Vehicular use areas do not have to be located within enclosed buildings.
2. The minimum lot size requirement shall be 10,000 square feet.
3. Every building shall be setback from property lines adjacent to residential uses or zones a distance equal to three times the height of the building.

**V. Sale of Spirituous Liquor in Conjunction with Food Service Use**

1. The Food Service establishment shall provide regular meal service at regularly available tables during all hours of operation or until 10:00 PM to guests for compensation. The establishment shall have kitchen facilities for keeping, cooking, and preparing foods for meals.
2. The Food Service establishment shall have 75 seats or more for the serving of meals at regularly available tables for all hours of operation. Seating at counters, in private banquet rooms, and outdoor seating shall not count toward the minimum 75 seat requirement.
3. The Food Service establishment may serve alcoholic beverages with meals; however, an area separate from the Food Service use shall not be provided with tables, counter areas, and/or booths for persons to sit at primarily for service of alcoholic beverages operating as an Alcoholic Beverage Service establishment, unless:
  - a. The Food Service establishment has 75 seats or more for the serving of meals at tables (seating at counters, in banquet rooms, and outdoor seating shall not count toward the 75 seat requirement) that are available at all hours of operation; and
  - b. The Alcoholic Beverage Service area does not exceed, in size, 25 percent of the Food Service floor area, including any Food Service outdoor area; and
  - c. The Alcoholic Beverage Service area does not have an outside public entrance separate from the main entrance to the Food Service use.
4. The Food Service establishment may serve, in addition to beer and wine, other alcoholic beverages.
5. A Food Service use with more than 75 seats for the serving of meals at tables that are available at all hours of operation may have a dance floor, provided such dance floor shall not be larger than 200 square feet. Seating at counters, in banquet rooms, and outdoor seating shall not count toward the 75 seat requirement.
6. Signs shall not be permitted in or on a window or on the exterior of any building or structure within the project that is visible from a public street or adjacent residentially zoned property identifying or advertising the Alcoholic Beverage Service use or the sale of spirituous liquors.

7. Alcoholic beverages shall not be provided with drive-in or drive-through services.
  8. Alcoholic Beverage Service may be provided outdoors if the outdoor area is a minimum of 100 feet from residentially zoned property excluding public right-of-way, or is separated by a building from adjacent residentially zoned property. If the use is within 600 feet of a residential zone, no loudspeakers or music, live or recorded, shall be permitted.
  9. A Food Service establishment that is located within 300 feet of a residential zone, excluding public right-of-way, measured in a straight line from the licensed premises to the zone boundary line of R-3 or more restrictive zoning may serve alcoholic beverages upon conformance with the following conditions:
    - a. The applicant is required to submit a mitigation plan to the PDS Director that will be reviewed in accordance with Zoning Compliance 300' Notice Sec. 3.xxx. The mitigation plan shall specifically address noise from the use, including parking lot noise, screening of lighting from vehicle headlights and light standards on site, parking, and access to adjacent neighborhoods, but shall not address issues that are the purview of the Arizona Department of Liquor Licenses and Control, such as the number of liquor licenses in the area or the hours of liquor sales.
    - b. If the use is operated in a manner that violates the mitigation plan or conditions for permitting the use or causes adverse land use impacts, the use may be suspended or terminated in accordance with Sec. 10.5.
- W. Technical Service**
1. Gross floor area shall be limited to a maximum of 1,500 square feet.
  2. Gross floor area shall be limited to a maximum of 3,500 square feet.
- X. Trade Service and Repair**
1. **Major**  
If located within 30 feet of a residential use or zone, the building walls shall have no openings, other than non-opening windows, within 30 feet of the adjacent residential use or zone boundary line.
  2. **Minor**  
Use shall exclude the repair and replacement of upholstery and the repair of burglar alarms and motor vehicle stereos.
- Y. Transportation Service, Air Carrier**
1. The minimum site area shall be as required by the Federal Aviation Agency (FAA) for the airport facility. The site area shall not be less than permitted by the underlying zoning.
  2. The Mayor and Council may restrict the number of flights and hours of operation due to the proximity and intensity of noise-sensitive land uses.

3. The runway length required for safe operation shall be as shown in the flight manual of the largest aircraft to use the site and an additional 240 feet at each end of the runway.
  4. The runway width shall be 240 feet centered on the runway.
- Z. Travelers' Accommodation, Campsite**
1. The use shall be in conjunction with, and within, a mobile home park.
  2. The overall number of mobile home spaces and campsites shall not exceed the overall density permitted for the mobile home park.
  3. The campsite area shall not be located adjacent to a non-mobile home residential zone.
  4. Access to the area shall be through the mobile home park.
  5. The area shall comply with the mobile home park development standards.
  6. No more than 25 percent of the total spaces in the mobile home park can be used for the campsite use.
- AA. Travelers' Accommodations, Lodging**
1. Minimum lot size shall be ten acres.
  2. The side and rear setbacks shall be 50 feet.
- BB. Travelers' Accommodation, Lodging and Accessory Uses**
1. The minimum distance to any public street shall be one 100 feet.
  2. Outside entrances shall not face any public street.
  3. The use shall be operated for the convenience of the guests.
  4. When the Alcoholic Beverage Service use is provided in an area set aside from the Food Service area, such as a bar or cocktail lounge, that area of the Alcoholic Beverage Service use shall not have an outside public entrance separate from the entrance to the principal use.
  5. The total area of retail and service establishments shall not exceed five percent of the total floor area.
  6. Animal-Related Uses.
    - a. No more than one animal for each 10,000 square feet of site area.
    - b. No stable or corral shall be located within 100 feet of any property line or within 300 feet of any existing buildings on an adjacent property at the time of the improvement.
    - c. No stable or corral shall be located or maintained closer than 50 feet to any property line or closer than 100 feet to any school, park, public street (excepting an alley), or dwelling on adjoining properties.
  7. Travelers' Accommodation, Lodging, shall have at least 50 rooms for transient lodging.
  8. Alcoholic Beverage Service may be provided outdoors if the outdoor area is a minimum of 100 feet from residentially zoned property or is separated by a building from adjacent residentially zoned property. If the use is within 600

- feet of a residential zone, no loudspeakers or music, live or recorded, shall be permitted.
9. Alcoholic beverages shall not be provided with drive-in or drive-through services.
  10. No alcoholic beverages, except beer and wine, shall be served.
  11. Signs shall not be permitted in or on a window or on the exterior of any building or structure visible from a public street or from adjacent residentially zoned property identifying or advertising the Alcoholic Beverage Service use or the sale of spirituous liquors.
  12. No Large Bars.
  13. No Soup Kitchens

#### 4.9.5. INDUSTRIAL USE GROUP

##### A. Craftwork Manufacturing

1. The area devoted to the use shall not exceed 25 percent of the gross floor area or 1,000 square feet, whichever is less.
2. The products manufactured on site shall be sold at retail on the premises.
3. The products manufactured on site shall be limited to leather-craft, jewelry, and clothing.

##### B. Extraction

1. The use shall be setback at least 300 feet from any property line, except that the use may be closer than 300 feet to an abutting I-2 zoned parcel with the written consent of the owner of the abutting property.
2. The generation of dust shall be minimized.

##### C. Manufacturing and Industrial (Includes General, Heavy Equipment, Precision, and Primary Manufacturing Land Uses)

1. The manufacturing activity shall be located on the same lot or site with the permitted use.
2. Access shall be from a street. Access from an alley shall also be permitted, provided the alley is at least 20 feet wide; it is paved for its entire block length; and zoning on both sides of the alley for its entire length within the block is not residential or office.
3. Reserved.
4. Manufacturing uses shall be conducted wholly within completely enclosed buildings.
5. All work and activity in connection with, and accessory to, a manufacturing use, such as loading and unloading areas, docks, and platforms, shall be located entirely within a building or an area on the lot that shall be enclosed on all sides by a solid wall or fence six feet in height. Such loading and unloading areas, docks, and platforms shall be located as far from any surrounding residential uses or zones as is reasonably possible.
6. The manufacturing and allied uses and activities shall be conducted in conformance with the following use specific standards:
  - a. Noise: The sound level of any individual operation shall not exceed the levels permitted in Chapter 16, Section 16-31, Noise Ordinance, of the Tucson Code.
  - b. Smoke: Smoke emission from any source shall not exceed a density greater than that described as No. 1 on the Ringleman Chart. However, smoke may be emitted that is equal to, but not darker than, No. 2 on the Ringleman Chart for not more than four minutes in any 30 minute period. For the purpose of grading the density of smoke, the Ringleman Chart, as published by the U.S. Bureau of Mines, shall be the standard.

- 
- c. **Glare or Heat:** Any activity producing intense glare or heat shall not be performed in such a manner as to create a nuisance or hazard beyond the property lines.
  - d. **Odors:** Emission of odorous gases or other odorous matter shall not be permitted in such quantities as to be offensive to owners or occupants of adjoining property or in such a manner as to create a nuisance or hazard beyond the property lines.
  - e. **Vibration:** No vibration shall be permitted that is discernible beyond the property lines to the human sense of feeling for a duration of three minutes or more in any one hour of the day between the hours of 7:00 a.m. and 7:00 p.m. or of a duration of 30 seconds or more in any one hour between the hours of 7:00 p.m. and 7:00 a.m.
  - f. **Fly Ash, Dust, Fumes, Vapors, Gases, and Other Forms of Air Pollution:** No emission shall be permitted that can cause damage to health, animals, vegetation, or other forms of property or that can cause any excessive soiling of the air.
  - g. **Liquids and Solid Waste:** No waste shall be discharged into the streets, drainage-ways, or on property possibly creating a danger to the public health and safety, and no waste shall be discharged in the public sewage system that might endanger the normal operation of the public sewage system.
  - h. **Illumination:** Illumination of buildings and open areas shall be located and directed so as to eliminate glare toward streets and adjoining properties and shall comply with the requirements of the Tucson Code, Chapter 6, (Outdoor Lighting Code).
- 7. Soap manufacturing shall be limited to cold process only.
  - 8. Outdoor storage, when permitted, shall not be located in a street perimeter yard. Outdoor storage areas shall be screened in accordance with Sec. 7.6, Landscaping and Screening. No materials or products shall be stacked or stored to exceed the height of the screen within 50 feet of an adjoining residential zone or street. Outdoor display of finished products shall be permitted within a street perimeter yard in an area limited to ten percent of the site area or 10,000 square feet, whichever is less. Such display area shall not encroach into required landscape buffer areas. Outdoor storage in the P-1 zone shall be limited to 25 percent of the site area.
  - 9. Accessory Manufacturing uses to Commercial Services, Retail Trade, or Wholesaling Use Groups, are permitted in the:
    - a. C-2 Zone, limited to 25% of the gross floor area.
    - b. C-3 Zone, limited to 33% of the gross floor area.
- D. Motion Picture Industry**
- 1. Buildings and structures shall be setback at least 100 feet from the boundary of the site.
  - 2. The minimum lot size shall be 36 acres.

**E. Perishable Goods Manufacturing**

1. The manufacturing of fish or meat products, sauerkraut, sugar beets, vinegar, and yeast and the rendering or refining of fats and oils shall not be permitted.
2. Slaughterhouses, meat packing plants, fertilizer yards, and plants for the reduction of animal matter shall not be permitted.
3. The building setback shall be at least 300 feet from any property line.
4. The area devoted to the accessory land use is limited to a maximum of 33 percent of the gross floor area.
5. The accessory land use shall be limited to baked goods and confectionery products.
6. The accessory land use shall be limited to the manufacturing of beer, "microbrewery."
7. The area devoted to the accessory land use shall not exceed 25 percent of the gross floor area or 1,000 square feet, whichever is less.
8. The products manufactured on site shall be sold at retail on the premises.
9. Maximum height shall be 50 feet.
10. Accessory Manufacturing uses to Commercial Services, Retail Trade, or Wholesaling Use Groups, are permitted in the:
  - a. C-2 Zone, limited to 25% of the gross floor area.
  - b. C-3 Zone, limited to 33% of the gross floor area.

**F. Radioactive Materials Restrictions**

1. Manufacturing activities involving the use, storage, or disposal of radioactive material shall be prohibited, except as permitted below.
2. Radioactive material that does not become an integral part of the manufactured product or is exempt from the licensing requirements of, or is permitted under, a general license issued by the Arizona Atomic Energy Commission or its legally established successor, may be used, stored, or disposed of as part of a manufacturing activity.
3. Radioactive material may be used in medical diagnosis and therapy or in medical, educational, or industrial research and development.

**G. Salvaging and Recycling**

1. Salvaging and Recycling shall be limited to recycling collection bins only.
2. All salvaging and recycling activities and storage shall occur within an enclosed building.
3. Salvaging and Recycling shall be limited to empty household product containers, such as, but not limited to, aluminum cans, glass and plastic bottles, and newspaper.

4. Junkyards, salvaging of motorized vehicles, such as cars, trucks, airplanes, and similar vehicles; salvaging of hazardous materials; and landfills shall not be permitted.
5. Salvaging and Recycling shall be restricted to collection of recycling materials.
6. In addition to the requirements of Sec. 7.6, Landscaping and Screening, there shall be a screen wall at least six feet in height between this use and any residential zone.
7. The household goods donation center shall be located in a permanent building staffed by an attendant who remains on the premises during the center's hours of operation.
8. Security procedures or physical barriers shall be provided to prevent after-hours drop-off of donated items and to prohibit nighttime access to these items.
9. The applicant shall submit a security management plan that describes the operation of the center, to the Zoning Administrator for review and approval. The plan shall include: the days and hours of operation for the center; descriptions of the planned security procedures and/or physical barriers planned to prohibit both vehicular access when the center is closed and outside storage when the center is closed; the outdoor lighting schematic; and the operational procedures planned to implement the security management plan. Any changes or amendments to the security management plan shall be filed with and approved by the Zoning Administrator. If the use is operated in a manner that violates the security plan or conditions for permitting the use, the use may be suspended in accordance with Sec. 10.5.
10. Signs shall be posted on the site providing the days and hours of operation and stating that donations are not to be left after the center has closed.
11. One drive-through service lane may be provided for customer drop-off of donated items.
12. The household goods donation center shall be located on, and have access from, either a street designated as an arterial street in the Major Streets and Routes Plan (MS&R) or a local street in a commercial or industrial park that has direct access to an arterial street.

**4.9.6. RECREATION USE GROUP**

**A. Golf Course**

**1. Standards for Permitted and Special Exception Land Uses**

- a. Minimum number of holes: Nine.
- b. Minimum distance between a tee and its hole: 75 feet.
- c. Minimum distance of tees and cups to any property line: 100 feet.
- d. Driving range shall be placed so that flying balls are directed toward the interior of the site.
- e. Subject to lighting requirements, Sec. 4.9.13.C.
- f. Minimum lot size shall be 30 acres.
- g. Side yard setback shall be 25 feet and rear yard setback shall be 50 feet.
- h. There shall be no side or rear yard setback when located adjacent to nonresidential zoning district or development but there shall be 80' side and rear setback when located next to residential zoning district or development.
- i. Height shall be limited to 25 feet.

**2. Standards for Accessory Uses to Golf Courses**

**a. Alcoholic Beverage Service**

- (1) Permitted only as part of, and in conjunction with, a Food Service use. All requirements for dispensing alcoholic beverages listed for Food Service, Sec. 4.9.6.A.2.b, are apply.
- (2) The Alcoholic Beverage Service area may not have a separate outside entrance. Access shall be through the Food Service use area.

**b. Food Service**

- (1) The Food Service establishment shall have kitchen facilities for keeping, cooking, and preparing foods for meals.
- (2) Food Service establishments with at least 75 seats for dining at regularly available tables may operate a cocktail lounge or bar to sell all spirituous liquors for on-premises consumption.

**c. Personal Service and General Merchandise Sales**

- (1) Personal Service and General Merchandise Sales shall be integrated into the main building associated with the principal use, such as a clubhouse or registration office. Access shall be from within such main building.
- (2) No sign associated with the Personal Service or General Merchandise Sales shall be visible from the exterior of the building.
- (3) General Merchandise Sales shall be limited to the sale of items related to the principal use only.

**d. In Addition to Sec. 4.9.6.A.1, .2, and .3, the Following Requirements Apply**

- (1) The minimum distance to any public street shall be 100 feet.
- (2) Outside entrances shall not face any public street.
- (3) The use is operated for the convenience of the users of the Golf Course.

**B. Commercial Recreation**

1. The minimum setback shall be 100 feet.
2. The minimum lot size shall be 20,000 square feet.

**4.9.7. RESIDENTIAL USE GROUP**

**A. Artist Studio/Residence in I-1**

1. The use shall be limited to buildings in existence on February 25, 1991, within the designated artist studio/residence area as defined in Sec. 11.4.
2. The use shall not displace existing industrial uses.
3. The appearance and structural integrity of the building shall be preserved or enhanced.
4. Residential use of the property shall be incidental and accessory to the artist studio use, with no greater than 50 percent of the floor area devoted to the accessory residential use.
5. The accessory residential use shall be occupied by an artist who is also the occupant of the primary artist studio use.
6. Adequate measures shall be provided to assure the health, safety, and welfare of the occupants in relation to any industrial process, use, or storage carried out in the artist studio/residence or on adjacent properties.
7. The use shall not impair or interfere with the continued industrial use of adjacent properties or with the purposes of the industrial zone.

**B. Family Dwelling**

1. Both dwellings shall be under the same ownership and on the same parcel.
2. Both dwellings shall comply with the development standards listed in Art. 6.
3. One dwelling shall be at least 25 percent smaller than the other dwelling.
4. The dwellings may be attached or detached.
5. A manufactured housing unit shall not be considered a dwelling for the purposes of this section, unless it is located in a subdivision recorded after January 1, 1982, and not located in a re-subdivision of any subdivision recorded prior to January 1, 1982.
6. A manufactured housing unit shall not be considered a dwelling for the purposes of this section, unless the following standards are met or a subdivision plat that has been clearly identified for manufactured housing has been approved and permits for manufactured homes have been issued for 25 percent or more of the lots prior to November 27, 2000.
  - a. It is placed on an excavated and backfilled foundation (ground set). If the home is located in a floodplain, the bottom of the lowest floor joist shall be a minimum of one foot above the 100 year/base flood elevation, and the foundation of the home shall be placed on the fill.
  - b. No more than eight inches of perimeter skirting wall shall be visible from the street frontage of the property. The perimeter skirting wall shall match the exterior color of the home.
  - c. The exterior siding materials shall be either hardboard, vinyl, or stucco.

- d. Concrete or masonry steps shall be provided for the entry on the street side of the dwelling.
  - e. All entry doors on the street side of the dwelling shall be inward-swinging doors.
  - f. The roofing style and materials shall be either flat roof (Pueblo), steel rib roof, or shingle or tile roof with a 3:12 roof pitch or greater. All pitched roofs, except those that are disguised by a parapet, shall have a minimum six inch eave on all sides of the dwelling.
7. For any new single family dwelling in the R-1 zone with five bedrooms, three parking spaces are required. For every bedroom over five, one additional space is required for each bedroom.
  8. For all single family dwellings in the R-1 zone with five or more bedrooms, and for all lots containing two or more single family dwellings, with the second dwelling having more than one bedroom, all parking and maneuvering shall be located on-site, either in a side or rear yard. The vehicular use area shall be improved, which includes surfacing, striping, and provision of barriers, in conformance with the Technical Manual. Parking spaces shall not be located in a vehicular use area in any front street perimeter yard.
- C. Family Dwelling or Mobile Home Dwelling as Accessory Use in Industrial Zones**
1. The dwelling is permitted as an accessory use to an Industrial, Wholesaling, or Storage Use.
  2. Restricted to one single-family or mobile home dwelling for a caretaker of the principal use.
  3. The dwelling shall conform to the development standards for the principal use.
- D. Home Occupation, Day Care: Permitted in Office, Residential, NC and C-1 zones:**
1. A home occupation shall be clearly secondary to the residential use of the dwelling.
  2. A home occupation shall be conducted in such a manner that it is compatible with the residential character of the neighborhood in which it is located.
  3. Goods related to the home occupation shall not be visible from the street.
  4. Goods shall not be sold on the premises.
  5. Except for permitted signage, the home occupation use shall not substantially alter the exterior appearance or character of the residence in which it is conducted, either by exterior construction, lighting, graphics, or other means.
  6. No more than one sign shall be visible from the exterior of the property used as a home occupation. The sign shall not exceed one square foot in size. Signs shall also conform to Chapter 3 of the Tucson Code.
  7. A home occupation shall not create any nuisance, hazard, or other offensive condition, such as that resulting from noise, smoke, fumes, dust, odors, or other noxious emissions. Electrical or mechanical equipment that causes fluctuations

---

in line voltage, creates any interference in either audio or video reception, or causes any perceivable vibration on adjacent properties is not permitted.

8. No more than five clients per day, and only one client at a time, shall be permitted on site.
  9. No more than one full-time equivalent person not residing on the premises shall be employed in the day care use.
  10. During the hours of activity of the day care use, there is no limit on the amount of floor area devoted to this use.
  11. Outdoor activities and equipment associated with the use shall be permitted and shall be screened by a five foot fence, wall, or hedge where adjoining R-3 or more restrictive zoning.
  12. Hours of operation shall be noted on the application, and those hours of operation shall not create an adverse impact on adjoining residences.
  13. Any vehicle used in conjunction with the day care use shall be limited to a passenger car, van, or pickup truck.
  14. The day care use shall be approved and licensed by the Arizona Department of Health Services prior to final approval.
- E. Home Occupation (General) accessory to any Mobile Home or Family Dwelling:**
1. A home occupation shall be clearly secondary to the residential use of the dwelling.
  2. A home occupation shall be conducted in such a manner that it is compatible with the residential character of the neighborhood in which it is located.
  3. No more than 25 percent of all buildings on the lot may be devoted to the home occupation. A detached accessory building of not more than 200 square feet in area may be used for such home occupation.
  4. Persons other than those residing in the dwelling shall not be employed in the home occupation, except that one nonresident of the premises may be employed in the IR, RH, SR, SH, O-2, O-3, NC, C-1, C-2, C-3, OCR-1, and OCR-2 zones.
  5. Goods related to the home occupation shall not be visible from the street.
  6. Goods shall not be sold on the premises.
  7. Outdoor storage of materials or equipment related to the home occupation activity shall be not permitted on the premises.
  8. Except for permitted signage, the home occupation use shall not substantially alter the exterior appearance or character of the residence in which it is conducted, either by exterior construction, lighting, graphics, or other means.
  9. No more than one sign shall be visible from the exterior of the property used as a home occupation. The sign shall not exceed one square foot in size. Signs shall also conform to Chapter 3 of the Tucson Code.
  10. A home occupation shall not create any nuisance, hazard, or other offensive condition, such as that resulting from noise, smoke, fumes, dust, odors, or other

noxious emissions. Electrical or mechanical equipment that causes fluctuations in line voltage, creates any interference in either audio or video reception, or causes any perceivable vibration on adjacent properties is not permitted.

11. No more than five clients per day, and only one client at a time, shall be permitted on site.
12. Motor vehicle and bicycle parking shall not be required for home occupation - general application. The home occupation may involve the use of no more than one commercial vehicle for the transportation of goods or materials to and from the premises. The commercial vehicle shall be limited to a passenger car, van, or pickup truck. This vehicle shall not be more than 20 feet in overall length and not more than seven feet in overall height and shall be parked on private property in a carport or garage or shielded from view from adjoining properties by landscaping, fencing, or screening material. Motor vehicle and bicycle parking necessitated by the conduct of such home occupation shall be provided on site.
13. Automotive - Service and Repair, hair salon, and Medical Service uses shall be prohibited as home occupations.
14. Home occupations shall require approval through a Zoning Compliance Review, Sec. 3.xxx.

**F. Home Occupation, Group Dwellings:**

1. Room and board shall be provided to not more than two persons in the Family Dwelling who are not members of the family or household in the IR, RH, SR, SH, RX-1, RX-2, MH-1 Zones. Room and board shall be provided to not more than four persons in the Family Dwelling who are not members of the family or household in the R-2 or MH-2 zones.
2. Meals shall be served only to roomers or boarders residing in the Family Dwelling. Separate cooking facilities in guest rooms shall be prohibited.
3. Parking requirements shall be as required for Group Dwellings, Sec. 7.4.4.

**G. Home Occupation, Travelers' Accommodation, Lodging:**

1. Accommodations shall be permitted for up to four guests for a maximum stay of 14 days. No more than two sleeping rooms shall be used to accommodate guests.
2. Accommodations shall be permitted for up to eight guests for a maximum of 14 days. No more than four sleeping rooms shall be used to accommodate guests.
3. Accommodations shall be permitted for up to 12 guests for a maximum stay of 14 days. No more than six sleeping rooms shall be used to accommodate guests.
4. Accommodations shall be permitted for up to 20 guests for a maximum stay of 14 days. No more than 10 sleeping rooms shall be used to accommodate guests.
5. Meals shall be served only to guests staying in the facility. Separate cooking facilities in guest rooms shall be prohibited.

6. The PDSO Director shall determine that the building and site improvements are compatible with the surrounding residential area. The Design Review Board (DRB) shall review all applications, except those involving properties within the Historic Preservation Zone (HPZ), for compatibility and make recommendations to the PDSO Director. The DRB shall review architectural style, building elevations, materials on exterior facades, color schemes, new mechanical equipment locations, lighting of outdoor areas, window locations and types, screening, landscaping, vehicular use areas, and other contributing design features. If the application is within the HPZ, see Sec. 5.8.5 for the review procedure for compatibility.
  7. No more than one full-time equivalent person not residing on the premises may be employed in the home occupation use.
  8. No more than one sign shall be visible from the exterior of the property used as a home occupation. The sign shall not exceed one square foot in size. Signs shall also conform to Chapter 3 of the Tucson Code.
  9. Outdoor activities and equipment associated with the use shall be permitted and shall be screened by a five foot fence, wall, or hedge where adjoining R-3 or more restrictive zoning.
  10. A home occupation shall not create any nuisance, hazard, or other offensive condition, such as that resulting from noise, smoke, fumes, dust, odors, or other noxious emissions. Electrical or mechanical equipment that causes fluctuations in line voltage, creates any interference in either audio or video reception, or causes any perceivable vibration on adjacent properties shall not be permitted.
  11. This use may involve the use of no more than one commercial vehicle for the transportation of persons or materials to and from the premises. The commercial vehicle shall be limited to a passenger car, van, or pickup truck. This vehicle shall be parked on private property in a carport or garage or shielded from view from adjoining properties by landscaping, fencing, or screening material. Motor vehicle and bicycle parking as required for Travelers' Accommodation, Lodging, shall be in addition to that required for the residential use.
  12. If Home Occupation, Group Dwelling and Home Occupation, and/or Travelers' Accommodation, Lodging, occur on the same site, the total number of guests, roomers, and boarders shall not exceed the number of guests permitted for that zone.
  13. The minimum lot size shall be 10,000 square feet.
  14. Motor vehicle and bicycle parking shall be provided per Sec. 7.7.4, for Travelers' Accommodation, Lodging. Variances shall not be granted from the number of required parking spaces.
- H. Accessory Uses in Mobile Home Parks with 100 Spaces or More**
1. Child Day Care (subject to 4.9.7.D. 1-5), Food and Beverage Sales (limited to a delicatessen or snack bar), General Merchandise Sales, and Personal Services (limited to a coin-operated laundry or pick-up station for dry cleaning) are permitted as accessory uses subject to the following:

- a. The use is located in the social or recreation center of the park.
    - b. The social or recreation center is located 50 feet or more from any interior lot line of the mobile home park and 100 feet or more from any street lot line bounding the mobile home park.
    - c. The accessory use does not occupy more than 25 percent of the floor area of the social or recreation center.
    - d. No merchandise or supplies shall be stored or displayed outside the building.
    - e. No exterior signs or public advertising are permitted.
  2. Vehicle rental and sales of model units in the mobile home park are permitted as accessory uses subject to the following:
    - a. Each model home shall have the same setback and spacing requirements as other units.
    - b. The number of spaces allotted for model homes shall be no more than five percent of the total spaces in the mobile home park.
    - c. Exterior display or advertising is limited to one sign. The sign may not exceed six square feet at each model, be over six feet in height nor be illuminated.
  3. Recreational vehicles may occupy no more than 25% of the existing spaces designed for mobile homes provided:
    - a. The mobile home park is in an MH-2 zone, or the mobile home park was built prior to July 1, 1995.
    - b. The rental lease is for no less than one month duration.
- I. Residential Care Services**
1. A Rehabilitation Service or Shelter Care use shall not be located within 1,200 feet, in any direction, from another Rehabilitation Service or Shelter Care use. The applicant for such use shall provide an inventory of such uses within 1,200 feet of the site prior to the establishment of the use.
  2. Other Services.
    - a. Accessory treatment, including counseling or other types of meetings, shall not be permitted for nonresidents of the facility.
    - b. Accessory treatment, including counseling or other types of meetings, shall be permitted for nonresidents of the facility, if limited to 25 percent of the gross floor area of the facility.
  3. Maximum Number of Residents.
    - a. Care shall be permitted for a maximum of ten residents.
    - b. Care shall be permitted for a maximum of 15 residents.
    - c. Care shall be permitted for a maximum of 20 residents.
    - d. Care shall be permitted for an unlimited number of residents.

4. If licensing shall be required by the State of Arizona for the use, proof of such licensure shall be provided.
5. Prior to establishment of a Rehabilitation Service or Shelter Care in an industrial zone, applicants for the use shall provide to the PSDS a report and site environs analysis for the facility indicating that adequate measures are provided to assure the health, safety, and welfare of the residents of the facility in respect to any industrial process, use, or storage carried out on the site or on adjacent properties.
6. The site shall be located at least 500 feet, measured in a straight line, from the property line to a zone boundary line of R-3 or more restrictive zoning.
7. Minimum lot size shall be three acres. Lot coverage shall be limited to 50 percent. Minimum setback from all interior lot lines adjoining residential zoning shall be 25 feet.
8. Minimum lot size shall be one and one-half acres. Lot coverage shall be limited to 60 percent. Minimum setback from all interior lot lines adjoining residential zoning shall be 20 feet.
9. Minimum lot size shall be 20,000 square feet.
10. Maximum height shall be 40 feet.
11. Maximum height shall be 140 feet.

#### 4.9.8. RESTRICTED ADULT ACTIVITIES USE GROUP

##### A. Restricted Adult Activities

1. The adult establishment shall not be less than 1,000 feet from any church, school, public playground, park, or neighborhood recreation property line.
2. The adult establishment shall not be less than 1,000 feet from any residential use property line or residential zone boundary line.
3. The adult establishment shall not be less than 1,000 feet from the premises of any other adult entertainment enterprise.
4. The adult establishment requires approval through Zoning Compliance Review, Sec. 3.xxx.
5. The land use activity shall occur within an enclosed building.
6. In the I-1 zone, all activity, including the display of any retail items, shall occur within a completely enclosed building and shall not be visible from the exterior.<sup>44</sup>

#### 4.9.9. RETAIL TRADE USE GROUP

##### A. Food and Beverage Sales

1. One building shall be permitted.
2. Maximum area of stand.
  - a. 3,000 square feet.
  - b. 750 square feet.
  - c. 200 square feet.
3. Only the sale of farm products grown or produced on the premises shall be permitted.
4. The building shall not be located closer than 20 feet to any property line.
5. The minimum setback from any street intersection shall be 150 feet.
6. The parking area shall be setback a minimum of 45 feet from the property line.
7. The minimum parking area shall be 800 square feet.
8. The maximum width of the entry to the parking area shall be 30 feet.
9. The vehicular use area is to be surfaced as is required in Sec. 7.4.6.I if the stand is open more than six months per calendar year. If open a shorter time, these areas shall be maintained to minimize dust.
10. The maximum floor area shall be 4,000 square feet.
11. The following standards shall apply to retail establishment (store).

---

<sup>44</sup> From 2.7.2.2.F – first sentence.

- a. A retail establishment (store) shall be limited to a maximum of 100,000 square feet of floor area. The 100,000 square feet of floor area includes gross floor area, outdoor storage areas, and any outside area that provides associated services to the public, such as, but not limited to, outdoor merchandise display, snack bars, etc. The floor area does not include motor vehicle parking or loading areas. For the purposes of determining the applicability of the 100,000 square foot floor area maximum, the aggregate square footage of all adjacent stores, which share cashiers, management, a controlling ownership interest, and storage areas, shall be considered one establishment, e.g., a plant nursery associated with a general merchandise store, such as a home improvement store.
- b. Establishments greater than 100,000 square feet of floor area (Large Retail Establishments) shall be considered through a special exception land use process as provided in the applicable zone.

**B. General Merchandise Sales**

1. Outdoor display or storage of fertilizer, manure, or other odorous material shall be located at least 30 feet from any interior lot line.
2. The maximum floor area shall be 2,000 square feet.
3. Fuel dispensing locations shall be limited to a maximum of 12.
4. The following standards shall apply to retail establishment (store).
  - a. A retail establishment (store) shall be limited to a maximum of 100,000 square feet of floor area. The 100,000 square feet of floor area includes gross floor area, outdoor storage areas, and any outside area that provides associated services to the public, such as, but not limited to, outdoor merchandise display, snack bars, etc. The floor area shall not include motor vehicle parking or loading areas.
  - b. For the purposes of determining the applicability of the 100,000 square foot floor area maximum, the aggregate square footage of all adjacent stores that share checkstands, management, a controlling ownership interest, and storage areas shall be considered one establishment, e.g., a plant nursery associated with a general merchandise store, such as a home improvement store.
  - c. Establishments greater than 100,000 square feet of floor area (Large Retail Establishments) shall be considered through a special exception land use process as provided in the applicable zone.

**C. Heavy Equipment Sales**

1. Any area used for the display or storage of heavy equipment shall be surfaced with a hard, durable, dustproof material.
2. Any lights used to illuminate outdoor activity shall be arranged so as to reflect the light away from adjacent residential uses or zones.

**D. Large Retail Establishment Design Standards**

Large Retail Establishments shall be subject to the following use specific standards. Variances from the standards shall not be permitted; however, if one or more of the

standards cannot be met, the applicant may request approval through the special exception land use process where there is substantial compliance with this section.

**1. Site Design and Relationship to Surrounding Community**

**a. Vehicular Access**

The project shall provide safety and protection to adjacent residential uses by having motor vehicle access from a major street as designated by the adopted Major Streets and Routes (MS&R) Plan. Access can also be provided from a street that is not designated by the MS&R Plan, provided it can be shown that any negative impacts on residential uses or residentially zoned properties can be mitigated.

**b. Buffers**

The project shall provide visual and noise buffers where the site is adjacent to a residential use or residentially zoned property. This can be accomplished by providing a minimum building setback of at least 200 feet from a residential use or residentially zoned property that is adjacent to the site. An eight foot high, or higher, masonry screen wall and at least a 20 foot wide landscape buffer shall be provided adjacent to the site property line where it adjoins a residential use or residentially zoned property. The landscape buffer shall be placed on the inside of the screen wall and shall include, in addition to shrubs and groundcover, canopy trees at 20 to 30 foot intervals depending on the separation needed for the tree canopies to touch at maturity to form a noise, light, and visual screen above the screen wall. No other uses, such as, but not limited to, parking or storage, shall be permitted within the landscape buffer area.

**c. Outdoor Storage Areas**

The project shall mitigate visual and noise impacts on residential uses, residentially zoned properties, and streets that may be adjacent to the site from outdoor storage areas (when permitted by the zone district requirements). The mitigation can be accomplished by locating these areas on-site and at least 200 feet from any residential use or residentially zoned property that is adjacent to the site. The areas should be screened or enclosed so that they are not visible from public streets, public sidewalks, internal pedestrian walkways, or adjacent residential properties. The screen shall be at least 8 feet high and of masonry construction to assure the highest level of noise abatement and to confine any loose papers, cartons, and other trash. Storage materials shall not be visible above the screen wall. It is preferred that these outdoor storage areas be placed between buildings in a manner that would allow the buildings to act as screens.

**d. Trash Collection Areas**

The project shall mitigate visual and noise impacts on adjoining residential neighborhoods and streets from trash collection areas by locating these areas on-site and at least 200 feet from any residential use, residentially zoned property, and street that is adjacent to the site. The areas shall be screened or enclosed so that they are not visible from public streets,

public sidewalks, internal pedestrian walkways, or adjacent residential properties. Screening and landscaping of these areas shall conform to the predominant materials used on the site. The screen shall be at least eight feet high and of masonry construction to assure the highest level of noise abatement and to confine any loose papers, cartons, and other trash. It is preferred that these trash collection areas be placed between buildings to allow the buildings to act as screens. No trash shall be removed between 4:00 p.m. and 9:00 a.m. as part of scheduled trash collection.

**e. Pedestrian Flow**

The project shall provide pedestrian accessibility, safety, and convenience to reduce traffic impacts and enable the development to project a friendly, inviting image. Sidewalks shall be at least eight feet wide and unobstructed and shall connect the public street sidewalks, the main entrances to the stores, transit stops on- or off-site, and other buildings on the site, in addition to providing convenient access to adjacent residential neighborhoods. Sidewalks shall be provided along the full length of any building where it adjoins a parking lot. Sidewalks shall have an associated three foot wide landscape strip for their entire length, except at intersections with parking area access lanes (PAALs). The landscaping shall include canopy trees or other shading devices to shade at least 65 to 75 percent of the sidewalks during the major part of the day (shadow pattern needs to be taken into consideration).

**f. Central Features and Community Spaces**

The project shall provide attractive and inviting pedestrian scale features, spaces, and amenities. Entrances and parking lot locations shall be functional and inviting with walkways conveniently tied to logical destinations. Bus stops should be considered integral parts of the configuration whether they are located on-site or along the street. Customer drop-off/pick-up points that may be provided should also be integrated into the design (shall not conflict with traffic lanes or pedestrian paths). Pedestrian ways shall be anchored by special design features, such as towers, arcades, porticos, light fixtures, planter walls, seating areas, and other architectural features that define circulation paths and outdoor spaces. Examples are outdoor plazas, patios, courtyards, and window shopping areas. Each development shall have at least two of these features.

**g. Delivery and Loading Spaces**

(1) Delivery and loading operations shall be designed and located to mitigate visual and noise impacts to adjoining residential neighborhoods. If there is a residential use or residentially zoned property adjacent to the site, such operations shall not be permitted between 10:00 p.m. and 7:00 a.m. Delivery and loading spaces shall be setback at least 200 feet from a residential use or residentially zoned property that is adjacent to the site, unless such operations are located entirely within an enclosed building, provided it is no closer than the allowable building setback.

- (2) Delivery trucks shall not be parked in close proximity to or within a designated delivery or loading area during non-delivery hours with motors and/or refrigeration/generators running, unless the area where the trucks are parked is setback at least 300 feet from residential property to mitigate the truck noise. The setback shall not apply if the main building is located between the truck parking and the residential use or residentially zoned property to act as the screen.
- (3) The delivery and loading areas shall be screened or enclosed so that they are not visible from public streets, public sidewalks, internal pedestrian walkways, or adjacent properties. The screen shall be of masonry construction and at least ten feet high, measured from the loading dock floor elevation, to screen the noise and activity at the loading dock. The masonry screen assures the highest level of noise abatement. It is preferred that the delivery and loading spaces be enclosed within a building or placed between buildings in a manner that would allow the buildings to act as screens.

**h. Traffic Impacts**

The applicant shall have a professional entity perform a Traffic Impact Analysis (TIA) report for the development using the Institute of Transportation Engineers' Trip Generation publication as the standard for trip generation calculation, as well as a parking generation report proposing the number of motor vehicle parking spaces required for the project, if different from shopping center calculations. The scope and standards for the TIA report shall be approved by the Department of Transportation, prior to submittal of the TIA report. The parking generation report shall be accepted by the Department of Transportation and PDSD, prior to the first public hearing. The TIA report shall identify traffic flow impacts on the public streets, recommend mitigation measures to address those conditions that fall below the standards established by the adopted regional Mobility Management Plan, and show how the applicant will provide the recommended improvements. The Mayor and Council may approve a parking requirement that supersedes the number required by Sec. 7.4, Motor Vehicle and Bicycle Parking, as part of their review process. The TIA and parking generation reports are applicable to a specific application. Any change to the specific proposed use of the site and buildings requires resubmittal, review, and approval of a revised TIA report and revised parking generation report.

**i. Outdoor Lighting**

A photometric plan and outdoor lighting report shall be required that provides information on how outdoor lighting is addressed to mitigate negative impacts on adjacent residential uses or residentially zoned properties. The report shall also address the negative impacts of outdoor lighting between the hours of 10:00 p.m. and 7:00 a.m. on adjacent residential properties or zones and how they will be mitigated. Outdoor lighting between 10:00 p.m. and 7:00 a.m. shall be limited to low-pressure sodium lighting.

**j. Outdoor Sales Display/Ancillary Uses**

Measures to mitigate any negative impacts to a residential use or residentially zoned property that is adjacent to the site from the location of any outdoor activity associated with services to the public, such as, but not limited to, outdoor merchandise display and sales, outdoor storage, and outdoor snack bar and eating areas shall be required. The outside activity shall be setback at least 250 feet and oriented to face away from any residential use or residentially zoned property that is adjacent to the site, unless a building is located between the activity and the residential property.

**k. Hazardous Materials**

The project shall provide a Hazardous Materials Management Plan and Hazardous Materials Inventory Statement as provided in the Fire Code to assure that the building site and design will protect public health and safety from accidental exposure to hazardous materials as provided in the Tucson Fire Code.

**l. Noise Abatement**

The project shall provide a noise mitigation plan indicating how the noise initiated by the land use will be mitigated to comply with noise standards in Chapter 16, Section 16-31, of the Tucson Code. Trucks shall not be left idling between the hours of 6:00 p.m. and 7:00 a.m.

**m. Combination of Retail with Food and Beverage Sales**

General Merchandise Sales and retail sales shall not be combined with Food and Beverage Sales except where one of the Land Use Classes consists of less than ten percent of the gross floor area.

**2. Aesthetic Character of Buildings**

**a. Facades and Exterior Walls Including Sides and Back**

The building shall be designed in a way that will reduce the massive scale and uniform and impersonal appearance and will provide visual interest consistent with the community's identity, character, and scale. Long building walls shall be broken up with projections or recessions with depths of at least three percent of the façade length along all sides of the building. Along any public street frontage, the building design should include windows, arcades, or awnings along at least 60 percent of the building length. Architectural treatment, similar to that provided to the front façade, shall be provided to the sides and rear of the building to mitigate any negative view from adjacent properties and/or streets.

**b. Detail Features**

The project shall provide architectural features that contribute to visual interest at the pedestrian scale and reduce the massive aesthetic effect by breaking up the building wall, front, side, or rear, with color, texture change, wall offsets, reveals, or projecting ribs.

**c. Roofs**

The roof design shall provide variations in roof lines to add interest to, and reduce the massive scale of, large buildings. Roof features shall complement the architectural and visual character of adjoining neighborhoods. Roofs shall include two or more roof planes. Parapet walls shall be architecturally treated to avoid a plain, monotonous look, unless it is in keeping with the architectural style of the building, e.g., Santa Fe style with smooth walls.

**d. Materials and Color**

The buildings shall have exterior building materials and colors that are aesthetically pleasing and compatible with materials and colors that are used in adjoining neighborhoods. This includes the use of high-quality materials and colors that are low reflective, subtle, neutral, or earth tone. Certain types of colors shall be avoided, e.g., fluorescent or metallic. Construction materials, such as tilt-up concrete, smooth-faced concrete block, prefabricated steel panels, and other similar material shall be avoided, unless the exterior surface is covered with an acceptable architectural treatment.

**e. Entryways**

The building design shall provide design elements that give customers orientation on accessibility and that add aesthetically pleasing character to buildings by providing clearly-defined, highly-visible customer entrances.

**f. Screening of Mechanical Equipment**

- (1) Roof- or ground-mounted mechanical equipment shall be screened to mitigate noise and views in all directions. If roof mounted, the screen shall be designed to conform architecturally with the design of the building, whether it is with varying roof planes or with parapet walls. A wood fence or similar treatment is not acceptable.
- (2) Ground-mounted mechanical equipment shall be screened. The screen shall be of masonry construction and be of sufficient height to block the view and noise of the equipment.

**3. Design Review Board (DRB)**

All proposed Large Retail Establishments shall be reviewed by the Design Review Board (DRB) for recommendation to the PDSD Director, who will make a recommendation on whether the project complies with the use specific standards. The DRB will base its recommendation on whether or not the project complies with the use specific standards related to compatibility, architecture, and site design, as provided in Sec. 4.9.9.D where specific requirements are not provided. The applicant shall be responsible for providing all documentation and information necessary to show compliance, such as, but not limited to, site plans, building elevations, landscaping plans, floor plans, and outdoor lighting photometry plan.

**E. Medical Marijuana**

**1. Medical Marijuana Dispensary**

- a. The total maximum floor area of a medical marijuana dispensary shall not exceed 2,500 square feet.
- b. The secure storage area for the medical marijuana stored at the medical marijuana dispensary shall not exceed 500 square feet of the total 2,500 square foot maximum floor area of a medical marijuana dispensary.
- c. A medical marijuana dispensary shall be located in a permanent building and shall not be located in a trailer, cargo container, mobile or modular unit, mobile home, recreational vehicle, or other motor vehicle. "Building" shall have the same meaning provided in Section 11.4.
- d. The permitted hours of operation of a medical marijuana dispensary shall be from 9:00 a.m. to 7:00 p.m.
- e. A medical marijuana dispensary shall have an interior customer waiting area equal to a minimum of 25 percent of the gross floor area.
- f. A medical marijuana dispensary shall not have a drive-through service.
- g. A medical marijuana dispensary shall not have outdoor seating areas.
- h. A medical marijuana dispensary shall not offer a service that provides off-site delivery of the medical marijuana.
- i. A medical marijuana dispensary shall be setback a minimum of 2,000 feet from any other medical marijuana dispensaries, measured in a straight and direct horizontal line between the two closest exterior walls of medical marijuana dispensaries.
- j. A medical marijuana dispensary shall be setback a minimum of 1,000 feet from a public, private or charter school or a licensed childcare center, measured in a straight and direct horizontal line from the closest exterior wall of the medical marijuana dispensary to the closest property line of a school or childcare center.
- k. A medical marijuana dispensary shall be setback a minimum of 1,000 feet from a church, library, or public park and a minimum of 2,000 feet from a licensed residential substance abuse diagnostic and treatment facility or other licensed drug or alcohol rehabilitation facility, measured in a straight and direct horizontal line from the closest wall of the medical marijuana dispensary to the closest property line of a church, library, public park, licensed residential substance abuse diagnostic and treatment facility, or other licensed drug or alcohol rehabilitation facility. A "church" means a building that is erected or converted for use as a church, where services are regularly convened that is used primarily for religious worship and schooling and that a reasonable person would conclude is a church by reason of design, signs, or other architectural features.
- l. A medical marijuana dispensary shall comply with all lawful, applicable health regulations, including those promulgated by the Arizona

Department of Health Services and any other authorized regulatory agency.

**2. Medical Marijuana Dispensary Off-site Cultivation Location**

- a. The total maximum floor area of a medical marijuana dispensary off-site cultivation location shall not exceed 3,000 square feet.
- b. The secure storage area for the medical marijuana stored at the medical marijuana dispensary off-site cultivation location shall not exceed 1,000 square feet of the 3,000 square foot total maximum floor area of a medical marijuana dispensary off-site cultivation location.
- c. A medical marijuana dispensary off-site cultivation location shall be located in a permanent building and shall not be located in a trailer, cargo container, mobile or modular unit, mobile home, recreational vehicle, or other motor vehicle. "Building" shall have the meaning provided in Section 11.4.
- d. A medical marijuana dispensary off-site cultivation location shall be setback a minimum of 2,000 feet from any other medical marijuana dispensaries or medical marijuana dispensary off-site cultivation locations measured in a straight and direct horizontal line between the two closest exterior walls of medical marijuana dispensaries' cultivation locations.
- e. A medical marijuana dispensary off-site cultivation location shall be setback a minimum of 1,000 feet from a public, private or charter school or a licensed childcare center measured in a straight and direct horizontal line from the closest exterior wall of the medical marijuana off-site cultivation location to the nearest property line of a school or childcare center.
- f. A medical marijuana dispensary off-site cultivation location shall be setback a minimum of 1,000 feet from a church, library, or public park and a minimum of 2,000 feet from a licensed residential substance abuse diagnostic and treatment facility or other licensed drug or alcohol rehabilitation facility measured in a straight and direct horizontal line from the closest wall of the medical marijuana dispensary off-site cultivation location to the closes property line of a church, library, public park, licensed residential substance abuse diagnostic and treatment facility, or other licensed drug or alcohol rehabilitation facility. A "church" means a building that is erected or converted for use as a church, where services are regularly convened that is used primarily for religious worship and schooling and that a reasonable person would conclude is a church by reason of design, signs, or other architectural features.
- g. A medical marijuana off-site cultivation location shall comply with all lawful, applicable health regulations, including those promulgated by the Arizona Department of Health Services and any other authorized regulatory agency.

**3. Medical Marijuana Designated Caregiver Cultivation Location**

- a. All conditions and restrictions for medical marijuana dispensary off-site cultivation locations apply except that the designated caregiver

cultivation location cultivation area is limited to a total 250 square feet maximum, including any storage areas.

- b. A designated caregiver may cultivate at their residence for a single qualifying patient subject to compliance with § A.R.S. 36-2806.01.
  - c. More than one designated caregiver may co-locate cultivation locations as long as the total cultivation area does not exceed 250 square feet maximum, including storage areas.
  - d. A designated caregiver shall comply with all lawful, applicable health regulations, including those promulgated by the Arizona Department of Health Services and any other authorized regulatory agency.
4. **Medical Marijuana Qualifying Patient Cultivation Location**
- a. A qualifying patient may cultivate at their place of residence subject to compliance with A.R.S. § 36-2806.01.
  - b. A qualifying patient, cultivating marijuana, shall comply with all lawful, applicable health regulations, including those promulgated by the Arizona Department of Health Services and any other authorized regulatory agency.

**F. Swap Meets and Auctions**

- 1. No large animals shall be sold.
- 2. Area lighting shall be low-pressure sodium and shielded on top.
- 3. The retail area shall be dust-proofed.
- 4. The following additional requirements apply if the use is located within 400 feet of a residential use or zone.
  - a. The use shall not operate later than 11:00 p.m.
  - b. Any high noise activity, such as amplified auctioneering, entertainment, or woodworking, shall occur within an enclosed building.

**G. Vehicle Rental and Sales**

- 1. Outdoor lights shall not operate later than 10:00 p.m., except for security lighting provided it does not exceed ten percent of all outdoor lighting.
- 2. Any lights used to illuminate outdoor activity shall be arranged so as to reflect the light away from adjacent property and comply with the Tucson Code, Chapter 6, Outdoor Lighting Code.
- 3. Limited to rental only; no retail sales.

**4.9.10. STORAGE USE GROUP**

**A. Commercial Storage**

1. Adjacent to a residential use or zone, outdoor storage shall comply with the following.
  - a. Storage material shall not be visible from outside the screen.
  - b. Outdoor lighting shall be directed away from adjacent residential uses and zones.
2. Outdoor storage, when permitted, shall not be located in the street perimeter yard.

**B. Hazardous Material Storage**

1. Aboveground storage tanks for the storage of hazardous materials, such as, but not limited to, hydrogen, gasoline, diesel fuel, automotive fluids, oil, or waste-oil, shall be permitted as accessory uses in conjunction with and for the purpose of a principal Permitted Land Use.
  - a. Exceptions
    - (1) A tank used for storing propane, water, or heating oil for consumptive use on the premises shall not be regulated by this section.
    - (2) Aboveground storage tanks that are not located within an enclosed building shall not be permitted within the Scenic Corridor Zone (SCZ).
  - b. No person shall install an accessory aboveground storage tank unless the tank meets the following requirements.
    - (1) The tank shall be used only for the purpose of servicing the vehicles used or serviced in connection with a permitted principal use. The tanks shall not be open for use by the public.
    - (2) Except as specified in this section, the setback standards of the zoning district in which the tanks shall be located apply to all accessory storage tanks.
      - (a) If the Fire Chief approves the location of a tank within an enclosed building, the minimum setbacks shall be determined by the Fire Chief, provided that the setbacks shall not be less than those required by the zoning.
      - (b) A tank that is not located within an enclosed building shall be setback as follows.
        - (i) A minimum of 50 feet from any property line adjacent to any area where, in the opinion of the Fire Chief, the tank could present a hazard or danger to person or property.
        - (ii) A minimum of 200 feet from any property line adjacent to R-3 or more restrictive zoning, or the tank location shall be approved as a special exception through a Zoning Examiner Special Exception Procedure, Sec. 3.xxx.
    - (3) The tank shall be screened by a wall equal to the height of the tank.

- (4) The maximum permitted diameter of a tank is 95 inches, except that, on 10,000 gallon storage tanks, the maximum diameter may be increased to ten feet.
  - (5) The maximum permitted height of a tank, excepting venting, manways, and filler caps, is ten feet above grade, except that, on 10,000 gallon storage tanks, the maximum height may be increased to 12 feet above grade.
  - (6) An aboveground storage tank shall have a secondary containment tank.
  - (7) A concrete pad shall be provided under all tanks.
  - (8) The construction, installation, and location of the aboveground storage tanks and the types of materials to be stored in the tanks shall be approved by the Fire Chief.
- c. These standards shall not supersede or replace any other applicable city, county, state, or federal standards and requirements for aboveground storage tanks.
2. The maximum capacity of each aboveground storage tank shall be as follows.
    - a. Capacity of 1,000 gallons shall be permitted.
    - b. Capacity of 2,000 gallons shall be permitted.
    - c. Capacity of 4,000 gallons shall be permitted.
    - d. Capacity of 10,000 gallons shall be permitted.
- C. Personal Storage**
1. All storage shall be within enclosed buildings.
  2. Access shall be from a collector or arterial street.
  3. All walls or doors visible from adjacent streets and residential properties shall be surfaced with a non-reflective material.
  4. Maximum individual unit size: 200 square feet of floor area.
  5. Razor or barbed wire shall not be used.
  6. The facility's exterior façade visible from adjoining residential properties or street frontage shall be earth tone in color and of masonry, stucco, or similar materials.
  7. Maximum site area: Three acres.

#### 4.9.11. UTILITIES USE GROUP

##### A. Distribution System

1. The setback of the facility, including walls or equipment, shall be 20 feet from any adjacent residential zone.
2. Where a facility is not enclosed within a building, the surrounding screen shall be used as the building wall for the purposes of setbacks.
3. The setback of the facility, including walls or equipment, shall be 200 feet from any existing adjacent residential zone. This setback may be varied as provided in Sec. 3.xxx Variances.
4. Where a water tower more than 20 feet in height is used in conjunction with such facilities, its center shall be located a distance from any lot line equal to not less than one-half its height.
5. The use shall not have any service or storage yards.
6. Noise emission at the property line shall be equivalent to the residential requirements of the noise ordinance.
7. No TVI (television interference) or RIV (radio interference) on a continuous basis shall be permitted.
8. Any building housing such facility shall be in keeping with the character of the zone in which it is located. The Design Review Board (DRB) shall review all applications and make recommendations to the Zoning Examiner. The DRB shall review architectural style, building elevations, materials on exterior facades, color schemes, new mechanical equipment locations, lighting of outdoor areas, window locations and types, screening, landscaping, vehicular use areas, and other contributing design features.
9. The use shall be located wholly within an enclosed building or within an area enclosed on all sides with a masonry wall or compact evergreen hedge, not less than six feet, nor more than ten feet, in height.
10. The use shall include a ten foot high wall in an earth tone and vegetative landscaping where contiguous to a residential zone.
11. The use shall be limited to water pumping and storage facilities, telephone exchanges, and power substations with an input voltage of no greater than 138 kilovolts.

##### B. Renewable Energy Generation

1. Requires approval through an Administrative Special Exception procedure, Sec. 3.xxx.
2. The setback of the facility, including walls or equipment, shall be 20 feet from any adjacent residential zone.
3. All activities shall be conducted in conformance with the following use specific standards:

- a. **Noise**  
The sound level of any individual operation shall not exceed the levels permitted in the Tucson Code, Chapter 16, Section 16-31, Noise Ordinance.
- b. **Smoke**  
Smoke emission from any source is not permitted to exceed a density greater than that described as No. 1 on the Ringleman Chart. However, smoke may be emitted which is equal to, but not darker than, No. 2 on the Ringleman Chart for not more than four minutes in any 30 minute period. For the purpose of grading the density of smoke, the Ringleman Chart, as published by the U.S. Bureau of Mines, is the standard.
- c. **Glare or Heat**  
Any activity producing intense glare or heat shall not be performed in such a manner as to create a nuisance or hazard beyond the property lines of the project site.
- d. **Odors**  
Emission of odorous gases or other odorous matter is not permitted in such quantities as to be offensive to owners or occupants of adjoining property or in such a manner as to create a nuisance or hazard beyond the property lines of the project site.
- e. **Vibration**  
No vibration is permitted that is discernible beyond the property lines of the project site.
- f. **Fly Ash, Dust, Fumes, Vapors, Gases, and Other Forms of Air Pollution**  
No emission is permitted that can cause damage to health, animals, vegetation or other forms of property or that can cause any excessive soiling of the air per State or County guidelines.
- g. **Liquids and Solid Waste**  
No waste shall be discharged into the streets, drainage ways, or on property possibly creating a danger to the public health and safety, and no waste shall be discharged in the public sewage system that might endanger the normal operation of the public sewage system.
- h. **Illumination**  
Illumination of buildings and open areas shall be located and directed so as to eliminate glare toward streets and adjoining properties and shall comply with the requirements of the Outdoor Lighting Code in Chapter 6 of the Tucson Code.
- i. **Interference**  
No TVI (television interference) or RIV (radio interference) is permitted to emanate from the project site.

4. The use shall not include a service or storage yard.
5. In addition to the requirements of Sec. 7.6, Landscaping and Screening, there shall be a decorative masonry wall at least six feet in height between the project site and any residential zone.

**C. Sanitation System**

Uses shall be at least 300 feet from any nonindustrial zone, except where the use of the non-industrially zoned property is railroad or freeway right-of-way.

**4.9.12. WHOLESALING USE GROUP**

Reserved.

**4.9.13. GENERALLY APPLIED STANDARDS**

**A. Access**

1. The use shall have primary vehicular access from an arterial street.
2. The use shall have access from a paved public street on the Major Streets and Routes (MS&R) Plan.

**B. Hours**

The principal use shall be restricted to hours of operation of 7:00 a.m. to 10:00 p.m.

**C. Lighting**

In addition to the requirements of Chapter 6, Section 6-101, Outdoor Lighting Code, of the Tucson Code, any outdoor lighting utilized in conjunction with the use shall be located and directed so as to eliminate glare toward streets and adjoining R-3 or more restrictive zoning.

**D. Noise**

In addition to the requirements of Chapter 16, Section-31, Noise, of the Tucson Code, the use shall be located within an enclosed building. There shall be no openings on the side of the building adjacent to R-3 or more restrictive zoning.

**E. Outdoor Activity**

Activity may occur outdoors.

**F. Screening**

In addition to the requirements of Sec. 7.6, there shall be a screen wall at least five feet in height between this use and any residential zone.

## **4.10. ACCESSORY USES AND BUILDINGS<sup>46</sup>**

Accessory uses and buildings shall be permitted in all zoning districts.<sup>47</sup> Those land uses and buildings associated with and incidental to a principal building shall be accessory and subject to the provisions described below.

### **4.10.1. ACCESSORY USES**

An accessory use shall comply with the following.

- A. The use shall be incidental to the principal use and is located on the same parcel as the principal use;
- B. The use shall be intended for the occupants, residents, customers, employees, or guests of the principal use; and
- C. The use shall not substantially alter the exterior appearance or character of the principal use or building to which it is incidental.
- D. Animals may be kept for personal use in all zones subject to Tucson Code, Chapter 4, and any applicable health regulations.

### **4.10.2. ACCESSORY BUILDINGS**

In all zones, the buildings used for accessory uses shall comply with the following.

- A. An accessory building shall be built only on a lot occupied by a principal building or use.
- B. An accessory building, except for a stable or enclosure for animals, may be attached to a principal building, provided that its construction complies with the development requirements of the principal building.
- C. The use of solar energy collectors for the purpose of providing energy for heating or cooling shall be permitted in all zones, whether as part of a principal building or as an accessory building. Such solar collection devices shall not be included in computing lot coverage.
- D. This section is not intended to apply to buildings of five feet or less in height and ten square feet or less in area, such as doghouses or refuse container enclosures, or to play equipment.

### **4.10.3. SPECIFICALLY WITHIN RESIDENTIAL ZONES**

The buildings used for an accessory use within a residential zone shall comply with the following.

- A. An accessory building shall not be a dwelling unit but may be a building that is used as sleeping quarters by the residents of the dwelling unit in accordance with Sec. 4.10.1.A and .B. The sleeping quarters may include bedrooms, bathrooms, and a

<sup>46</sup> Text from LUC Section 3.2.5. The sections shown as deleted have been relocated to Art. VI Dimensional Standards.

<sup>47</sup> We added this language to replace the language repeated in nearly every district in Art. II, Div. 2 that states: "Land uses accessory to the Permitted Land Use and Secondary Land Use are allowed, subject to compliance with Sec. 3.2.5." We assume that accessory uses are, in fact, allowed in all zoning districts. Since this section includes all of current Sec. 3.2.5, the need to comply with this section needs to be mentioned only once.

sitting room, provided the building complies with Sec. 4.10.1.C and is not the dominant use of the property.

- B. Detached accessory buildings are not permitted in the buildable area extending the full width of the lot between the principal building and the front street lot line, except for terraces and steps not over three feet high above the natural grade, paved areas, and fences or walls.

#### **4.10.4. SPECIFICALLY WITHIN NONRESIDENTIAL ZONES**

The building used for an accessory use within a nonresidential zone shall comply with the following.

- A. An accessory building shall not be occupied as a dwelling, except as a caretaker's facility.
- B. The area of a site occupied by an accessory use or building shall be included as part of the lot coverage calculation.

## 4.11. TEMPORARY USE OR BUILDING

Certain land uses or buildings not permitted within specific zones may be permitted on a temporary basis if authorized through Zoning Compliance Review, Sec. 3.xxx, provided such request for a temporary use complies with the following.

### 4.11.1. QUALIFICATION FOR PERMIT

For certain land uses or buildings to be permitted on a temporary basis, the land use or building shall comply with one or more of the following special circumstances.

- A. The circumstances constitute a substantial hardship, such as, but not limited to, a natural disaster, e.g., fire or flood, or a government action that has resulted in damage to an existing building on the subject property.
- B. A temporary building, such as a mobile or modular unit, occupied as a caretaker's facility or a home for the eventual resident may be permitted during the construction of a permanent building. The temporary building shall be on the same site as the construction.
- C. The temporary location of off-street parking facilities during the structural expansion or remodeling of an existing building. Such temporary facilities do not have to comply with requirements of a permanent parking facility but shall, at a minimum, provide the following.
  - 1. Screening from adjacent residential development. Since this is a temporary facility, screening cannot be achieved by the use of landscaping unless mature vegetation that can act as the screen exists on the site.
  - 2. Dust-proofing.
- D. A temporary real estate office may be permitted during construction of a project, provided:
  - 1. The temporary use shall be terminated at the end of one year from the date the approval was granted; however, additional 12 month extensions may be granted, provided sales activity for the project continues and ten percent or more of the lots or units remain unsold.
  - 2. The temporary office building is located on a lot and complies with Unified Development Code (UDC) zoning requirements applicable to that lot.
  - 3. The temporary office building is located in the same subdivision within which sales occur.
  - 4. The temporary use or building complies with any additional conditions required by the approval authority.
- E. A temporary construction equipment yard for public improvement projects involving street improvements or the placement of utilities within public rights-of-way, provided solutions are implemented to mitigate potential negative impacts to adjacent residential development. Such solutions include, but are not limited to, screening of equipment, setbacks, hours of operation, and limited or restricted use of residential streets.

- F. The temporary placement of a mobile telecommunications tower facility on nonresidential property may be permitted upon the demonstration by a telecommunications provider that the facility is necessary for its operations; the facility is setback from any residentially zoned property by a distance equal to the height of the proposed tower and base; and the tower and base do not exceed 65 feet from the existing grade. The temporary use authorized by this subsection shall be approved for a period not to exceed 60 days and may be approved for one extension of time not to exceed 60 days.

**4.11.2. BOND REQUIRED**

A cash or assurance bond in the amount of 1,000 dollars for a residential use and 5,000 dollars for a nonresidential use shall be required, unless stipulated otherwise in the qualification standards in Sec. 4.11.1, to guarantee termination of the temporary use. The cash or assurance bond shall be provided to the City before any permit for the use is issued.

**4.11.3. REFUND**

The bond, as required in Sec. 4.11.2, shall be refunded when the temporary use or building is removed by the applicant in accordance with Sec. 4.11.4.

**4.11.4. REMOVAL**

The temporary use or building shall be removed on or before the date of expiration of the approval period. Should the zoning compliance certificate be revoked, a temporary use shall be removed within 15 days notice.

- A. Removal is to include all improvements installed to accommodate the temporary use or building.
- B. If, after the removal, the property is left graded and vacant, the property shall be reseeded in accordance with the requirements of the grading ordinance for graded but undeveloped properties.

**4.11.5. FORFEITURE**


If the temporary use or building is not removed or the site does not achieve compliance, the bond required by Sec. 4.11.2 shall be forfeited.

**4.11.6. TIME LIMIT**

Approval for a temporary use or building may be granted for one year, with an additional one year period granted for good cause, unless otherwise stipulated in the temporary use or building qualification standards in Sec. 4.11.1.

## **ATTACHMENT C**

### **ARTICLE 6: DIMENSIONAL STANDARDS AND MEASUREMENTS**



**CITY OF TUCSON  
UNIFIED DEVELOPMENT CODE**

**PRELIMINARY FINAL PUBLIC DRAFT – OCTOBER 2011**

**CONTENTS**

**ARTICLE 6: DIMENSIONAL STANDARDS AND MEASUREMENTS**

<b>6.1.</b>	<b>PURPOSE.....</b>	<b>1</b>
<b>6.2.</b>	<b>APPLICABILITY.....</b>	<b>1</b>
<b>6.3.</b>	<b>TABLE OF DIMENSIONAL STANDARDS.....</b>	<b>1</b>
<b>6.4.</b>	<b>RULES OF MEASUREMENT AND EXCEPTIONS TO DIMENSIONAL STANDARDS.....</b>	<b>18</b>
6.4.1.	Purpose.....	18
6.4.2.	Lot Size.....	18
A.	Standards.....	18
B.	Exceptions.....	18
6.4.3.	Lot Coverage.....	19
A.	Coverage Included.....	19
B.	Calculation.....	19
6.4.4.	Side, Rear, and Front Yards.....	19
A.	Measurement.....	19
B.	Exceptions.....	20
6.4.5.	Height.....	21
A.	Measurement of Building.....	21
B.	Measurement of All Other Structures.....	22
C.	Height Exceptions.....	24
<b>6.5.</b>	<b>DEVELOPMENT COMPATIBILITY STANDARDS.....</b>	<b>26</b>
6.5.1.	Purpose.....	26
6.5.2.	Applicability.....	26
6.5.3.	Mitigation of Multi-Story and Taller Structures.....	27
6.5.4.	Mitigation of Service Areas.....	27
A.	Applicability.....	27
B.	Requirement.....	28
6.5.5.	Mitigation of Parking Facilities and Other Areas.....	28
A.	Applicability.....	28
B.	Requirement.....	28
6.5.6.	Compliance Statement Required.....	28
<b>6.6.</b>	<b>PRINCIPAL LAND USE.....</b>	<b>28</b>
6.6.1.	One or More principal Uses, Separate Projects.....	28
6.6.2.	Two or More principal Uses, Same Project.....	29
A.	Two or More Uses, Same Dimensional Standards.....	29
B.	Two or More Uses, Different Dimensional Standards.....	29
<b>6.7.</b>	<b>ACCESSORY USES AND STRUCTURES.....</b>	<b>29</b>
6.7.1.	Standards For all Zones.....	29
6.7.2.	Standards for Residential Zones.....	30
6.7.3.	Standards for Nonresidential Zones.....	31

## ARTICLE 6: DIMENSIONAL STANDARDS AND MEASUREMENTS

### 6.1. PURPOSE

This article provides the general dimensional standards that apply to principal and accessory structures for each zoning district in the city. The standards are intended to protect open space, solar access, and the privacy of all properties and to minimize negative impacts between developments.<sup>1</sup> This article also provides the method for measuring the dimensional standards to ensure consistent application of the standards.

### 6.2. APPLICABILITY

The standards in this article shall apply to all principal and accessory structures and uses established in the City of Tucson.

### 6.3. TABLE OF DIMENSIONAL STANDARDS

- The dimensional standards for principle structures shall be in accordance with Table 6.3-1 and other sections of this article.
- These standards may be further limited or modified for certain uses by other applicable sections of this UDC, such as use-specific dimensional standards in Article 4: Zones.
- General rules for measurement and exceptions are located in Sec. 6.4.<sup>4</sup> Dimensional standards for accessory structures are in Sec. 6.6 below.

#### LEGEND FOR TABLE 6.3

Density	Lot Size or Site Area	Use
<p># of units permitted per lot size or site area.</p> <p>1/ac (one unit per acre)</p> <p>1/7,000 sf (one per 7,000 square feet)</p> <p>36/ac (36 units per acre)</p>	<p>Non residential site area in square feet (sf) or acres (ac).</p> <p>Residential lot size in square feet (sf) or acres (ac).</p>	<p><b>Nonres:</b> includes nonresidential development, (Agri, Civic, Commercial, Industrial, Retail, Storage, etcetera)</p> <p><b>Res:</b> Residential development only.</p> <p><b>MF:</b> Multi-family</p> <p><b>SF:</b> Single family Dwelling</p>

<sup>1</sup> Text based on LUC Sec. 3.2.6.1.

<sup>4</sup> Additional Use Specific Dimensions, greater setback or minimum lot size requirements, are located in Article 4.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Institutional Reserve (IR) [current]	A (FDU, MH) 21(25 uses)	A: 1/36	A: 36 acres 21: 36 ac.	21: 10%	A: CC 21: FF	A: CC 21: FF	Sec. 3.2.6.5	A: 30 21: 30
Institutional Reserve (IR) [proposed]	None	1/36 acre	36 acre	Res: None <sup>8</sup> Nonres: 5% <sup>9</sup>	Res: 25 Nonres: 100 <sup>10</sup>	Res: 25 Nonres: 100	20 <sup>11</sup>	30
Rural Homestead (RH) [current]	B (FDU, MH, res. care) 2 (Anim. Prod.)	B: 1	B: 180,000 2: 10 ac. 25: 180,000	2: 10% 25: 20%	B: CC 2: FF 25: FF	B: CC 2: FF 25: FF	Sec. 3.2.6.5	B: 30 2: 30 25: 30

<sup>5</sup>Building Residential Adjacency Setback. Where the building height is greater than 20 feet for a proposed building or an extension or addition to an existing building and the subject property is adjoining a property with an existing residential building the setback shall be increased by one foot for every foot of building height greater than 20 feet. Subdivisions with an approved Tentative Plat are exempt from this requirement. (Insert on every page with Table. Asterisk after "Side (ft)" and "Rear (ft)").

<sup>6</sup> The "Development Designator" column will be deleted in the final version of the table because all designators will be replaced with the district-based standards in this table. In addition, for the purposes of this draft, the designators are in parentheses next to dimensional standard to which they apply. In the final version of this table these designators will be deleted and only the dimensional standards will remain. The text will notify readers that Article 4: Zoning Districts may contain additional special dimensional standards for certain uses.

<sup>7</sup> The intent for residential density is to maintain and clarify the current standards in LUC Sec. 3.2.3. Density is expressed both as units/ft and units/acre, consistent with the current LUC. Where appropriate, different densities for single family and multi-family development were provided.

<sup>8</sup> The current distinction between a "lot" and "site-area" is from LUC Sec. 3.2.3. Definitions have been added, however, to clarify and distinguish both terms.

<sup>9</sup> "Res" in this table, means standard applies to residential development, and the label "Nonres" means standard applies to nonresidential development. For the city's current zones based on Pima County zones (R-1 through MH-2) and for the city's residential zones (R-1 through MH-2), we have retained a lot coverage requirement for nonresidential uses to ensure that some reasonable limit on impervious surface exists on larger lots and in residential areas. Also, recommended as noted, we have reduced the max. lot coverage requirement by 5% in all districts to compensate for the fact that the proposed new lot coverage definition does not count drive areas as coverage.

<sup>10</sup> The current side and rear setbacks for nonresidential uses (designator FF) in the IR range from 0' when next to commercial and industrial zones and 120' when next to low-density residential zones. Pima County setbacks for the IR District are 50' feet for all setbacks. Staff recommends a uniform S/R setback of 100' because any nonresidential development in the IR is more likely to be adjacent to low-density residential zones than nonresidential zones and so setbacks favoring the protection of residential development is reasonable for this district. Note: In districts where nonresidential uses are more likely to be adjacent to other nonresidential uses, we would make the opposite conclusion and recommend that the S/R setback be chosen on the less restrictive end of the range.

<sup>11</sup> A uniform front yard setback of 20' has been chosen for every zoning district. This setback allows enough room to ensure that all cars parked in a driveway in front of a house or garage will not overhang into the street ROW. Also, in many cases, other standards, such as landscaping and parking, will require additional front yards for uses that require buffering greater than 20 feet.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Rural Homestead (RH) [proposed]	25 (37 uses) None	1/180,000 sf lot	180,000 sf lot (B,25) <sup>12</sup>	Res: None Nonres: 15% <sup>13</sup>	Res: 25 Nonres: 50 <sup>14</sup>	Res: 25 Nonres: 50	20	30
Suburban Ranch (SR) [current]	C (FDU, res. care) 1 (golf course) 2 (stables, lodging) 5 (11 uses) 6 (8 uses)	C: 1	C: 144,000 1: 30 ac. 2: 10 ac. 5: 144,000 6: 144,000	1: 10% 2: 10% 5: 15% 6: 50%	C: BB 1: FF 2: FF 5: FF 6: FF	C: BB 1: FF 2: FF 5: FF 6: FF	Sec. 3.2.6.5	C: 30 1: 25 2: 30 5: 30 6: 25
Suburban Ranch (SR) [proposed]	None	1/144,000 sf lot	144,000 sf lot (C,5,6) <sup>15</sup>	Res: None Nonres: 45%	Res:25 Nonres: 50 <sup>16</sup>	Res:25 Nonres: 50	20	30
Suburban Homestead	E (FDU, 2 other		E: 36,000	E: None	E: BB	E: BB	Sec.	E: 30

\*Building Residential Adjacency Setback. Where the building height is greater than 20 feet for a proposed building or an extension or addition to an existing building and the subject property is adjoining a property with an existing residential building the setback shall be increased by one foot for every foot of building height greater than 20 feet. Subdivisions with an approved Tentative Plat are exempt from this requirement. (Insert on every page with Table. Asterisk after "Side (ft)" and "Rear (ft)".)

<sup>12</sup> Remove all DD's in final

\*Building Residential Adjacency Setback. Where the building height is greater than 20 feet for a proposed building or an extension or addition to an existing building and the subject property is adjoining a property with an existing residential building the setback shall be increased by one foot for every foot of building height greater than 20 feet. Subdivisions with an approved Tentative Plat are exempt from this requirement.

<sup>13</sup> Where there is a range of lot coverages for nonresidential uses in a residential district we chose the least restrictive standard. Use specific standards may be needed for the various uses. In some cases, a special minimum lot size standard of 10 acres has been added for designator 2 (animal production - stable or riding school).

<sup>14</sup> The current side and rear setbacks for nonresidential uses (designator FF) in the RH range from 0' when next to commercial and industrial zones and 120' when next to low-density residential zones. Pima County setbacks for the RH District are S = 20 feet and R = 50 feet. A uniform S/R setback of 50 feet, which is near the middle of the range and consistent with the Pima County standards, because any nonresidential development in the RH is more likely to be adjacent to medium-density residential zones than nonresidential zones and so setbacks favoring the protection of this type of residential development is reasonable for this district is recommended.

<sup>15</sup> A special minimum site area standard of 30 acres has been added for golf course use and 10 acres for commercial stables and travelers' accommodation, lodging.

<sup>16</sup> The current side and rear setbacks for nonresidential uses (designator FF) in the SR range from 0' when next to commercial and industrial zones and 120' when next to low-density residential zones. Pima County setbacks for the SR District are S=10 feet and R = 50 feet. A uniform S/R setback of 50', which is near the middle of the range and consistent with the Pima County standards, because any nonresidential development in the SR is more likely to be adjacent to medium-density residential zones than nonresidential zones and so setbacks favoring the protection of this type of residential development is reasonable for this district is recommended.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.%)	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
(SH) [current]	<ul style="list-style-type: none"> <li>1 (Golf course) uses</li> <li>2 (Com. stable)</li> <li>5 (Animal serv.)</li> <li>8 (Cemetery)</li> <li>9 (13 uses)</li> <li>10 (5 uses)</li> <li>21 (Movie ind.)</li> </ul>	E: 2	<ul style="list-style-type: none"> <li>1: 30 ac.</li> <li>2: 10 ac.</li> <li>5: 144,000</li> <li>8: 43,560</li> <li>9: 36,000</li> <li>10: 36,000</li> <li>21: 36 ac.</li> </ul>	<ul style="list-style-type: none"> <li>1: 10%</li> <li>2: 10%</li> <li>5: 15%</li> <li>8: 20%</li> <li>9: 15%</li> <li>10: 50%</li> <li>21: 10%</li> </ul>	<ul style="list-style-type: none"> <li>1: FF</li> <li>2: FF</li> <li>5: FF</li> <li>8: FF</li> <li>9: EE</li> <li>10: EE</li> <li>21: FF</li> </ul>	<ul style="list-style-type: none"> <li>1: FF</li> <li>2: FF</li> <li>5: FF</li> <li>8: FF</li> <li>9: EE</li> <li>10: EE</li> <li>21: FF</li> </ul>	<ul style="list-style-type: none"> <li>3: 2.6.5</li> </ul>	<ul style="list-style-type: none"> <li>1: 25</li> <li>2: 30</li> <li>5: 30</li> <li>8: 25</li> <li>9: 30</li> <li>10: 25</li> <li>21: 30</li> </ul>
Suburban Homestead (SH) [proposed]	None	2/36,000 sf lot	36,000 sf lot (E,8,9,10) <sup>17</sup>	Res: None Nonres: 10%	Res: 10 Nonres: 40 <sup>18</sup>	Res: 20 Nonres: 40	20	30
Residence Zone (RX-1) [current]	<ul style="list-style-type: none"> <li>D (FDU, res. care)</li> <li>1 (golf course)</li> <li>3 (lodging)</li> <li>9 (16 uses)</li> </ul>	D: 1	<ul style="list-style-type: none"> <li>D: 36,000</li> <li>1: 30 ac.</li> <li>3: 10 ac.</li> <li>9: 36,000</li> </ul>	<ul style="list-style-type: none"> <li>1: 10%</li> <li>3: 15%</li> <li>9: 15%</li> </ul>	<ul style="list-style-type: none"> <li>D: BB</li> <li>1: FF</li> <li>3: FF</li> <li>9: EE</li> </ul>	<ul style="list-style-type: none"> <li>D: BB</li> <li>1: FF</li> <li>3: FF</li> <li>9: EE</li> </ul>	<ul style="list-style-type: none"> <li>Sec.</li> <li>3: 2.6.5</li> </ul>	<ul style="list-style-type: none"> <li>D: 30</li> <li>1: 25</li> <li>3: 25</li> <li>9: 30</li> </ul>
Residence Zone (RX-1) [proposed]	None	1/36,000 sf lot	36,000 sf lot (D,9) <sup>19</sup>	Res: None Nonres: 10%	Res: 10 Nonres: 40 <sup>20</sup>	Res: 20 Nonres: 40	20	30

<sup>17</sup> Building Residential Adjacency Setback. Where the building height is greater than 20 feet for a proposed building or an extension or addition to an existing building and the subject property is adjoining a property with an existing residential building the setback shall be increased by one foot for every foot of building height greater than 20 feet. Subdivisions with an approved Tentative Plat are exempt from this requirement. (Insert on every page with Table. Asterisk after "Side (ft)" and "Rear (ft)").

<sup>18</sup> A special minimum site area standard of 30 acres will be added for designator 1 (golf course), 10 acres for designator 2 (commercial stables), 144,000 sf for designator 5 (animal service), and 36 acres for designator 21 (motion picture industry).

<sup>19</sup> The current side and rear setbacks for nonresidential uses (designators EE and FF) in the SH range from 0' when next to commercial and industrial zones and 120' when next to low-density residential zones. Pima County setbacks for the SH District are S=10 feet and R = 40 feet. A uniform S/R setback of 40 feet, which is in the middle of the range and consistent with the Pima County standards, because any nonresidential development in the SR is more likely to be adjacent to medium-density residential zones than nonresidential zones and so setbacks favoring the protection of this type of residential development is reasonable for this district is recommended.

<sup>20</sup> A special minimum site area standard of 30 acres will be added for designator 1 (golf course) and 10 acres for designator 3 (travelers' accommodation, lodging). The current side and rear setbacks for nonresidential uses (designators CC, DD, and FF) in the RX-1 range from 0' when next to commercial and industrial zones and 120' when next to low-density residential zones. Pima County setbacks for the CR-1 District are S=10 feet and R = 40 feet. A uniform S/R setback of 40 feet, which is in the middle of the range and consistent with the Pima County standards for the CR-1 and SH (same minimum lot size), because any nonresidential development in the RX-1 is more likely to be adjacent to medium-density residential zones than nonresidential zones and so setbacks favoring the protection of this type of residential development is reasonable for this district is recommended.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Residence Zone (RX-2) [current]	F (FDU, res. care) 1 (golf course) 11 (elem./sec schools) 13 (11 uses) 14 (crop prod.)	F: 1	F: 16,000 1: 30 ac. 11: 20,000 13: 16,000 14: 16,000	1: 10% 11: 15% 13: 15% 14: 50%	F: BB 1: FF 11: CC 13: DD 14: DD	F: BB 1: FF 11: CC 13: DD 14: DD	Sec. 3.2.6.5	F: 25 1: 25 11: 25 13: 25 14: 25
Residence Zone (RX-2) [proposed]	None	1/16,000 sf lot	16,000 sf lot (F,11,13,14) <sup>21</sup>	Res: None Nonres: 10% <sup>22</sup>	Res: 10 Nonres: 30 <sup>23</sup>	Res: 20 Nonres: 30	20	25
Residence Zone (R-1) [current]	G (Fam. Du, Res. Care Svs) H (Fam. DU) 11 (Elem./sec schools) 12 (5 uses) 17 (8 uses)	G: 1	G: 7,000 H: 10,000 11: 20,000 12: 20,000 17: 7,000	G: 70% H: 70% 11: 15% 12: 60% 17: 70%	G: AA H: AA 11: CC 12: CC 17: BB	G: AA H: AA 11: CC 12: CC 17: BB	Sec. 3.2.6.5	G: 25 H: 25 11: 25 12: 25 17: 25
Residence Zone (R-1) [proposed]	None	1/ 7,000 sf 2/ 10,000 sf	7,000 sf lot (G,17) <sup>25</sup> 2 SF: 10,000 sf lot	65%	7 <sup>27</sup>	16	20	25

\*Building Residential Adjacency Setback. Where the building height is greater than 20 feet for a proposed building or an extension or addition to an existing building and the subject property is adjoining a property with an existing residential building the setback shall be increased by one foot for every foot of building height greater than 20 feet. Subdivisions with an approved Tentative Plat are exempt from this requirement. (Insert on every page with Table. Asterisk after "Side (ft)" and "Rear (ft)").

<sup>21</sup> A special minimum site area standard of 30 acres will be added for designator 1 (golf course).

<sup>22</sup> A special lot coverage standard of 50% will be added for designator 14 (crop production).

<sup>23</sup> The current side and rear setbacks for nonresidential uses (designators CC, DD, and FF) in the RX-2 range from 0' when next to commercial and industrial zones and 100' when next to low-density residential zones. Pima County setbacks for the CR-2 District are S=10 feet and R = 40 feet. A uniform S/R setback of 30 feet, which is slightly less than the setback for the RX-1 given that the RX-2 has a smaller minimum lot size and shorter height limit and so should have smaller side and rear setbacks by comparison is recommended.

<sup>25</sup> A special minimum site area of 20,000 sf will be added for designators 11 (Elem./sec. schools) and designator 12 (5 uses).

<sup>27</sup> Given the two minimum lot sizes in the R-1 are similar, all residential and nonresidential uses would be subject to same side and rear setbacks.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator	Residential Density (max.%)	Lot Size/ Site Area (min.)	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Residence Zone (R-2) [current]	I (FDU)	I: 1	I: 5,000	I: 70%	I: AA	I: AA	I: 25	
	K (FDU)	K: 15	K: 5,000	K: 75%	K: BB	K: BB	K: 25	
	8 (admin./prof. office)		8: 43,560	8: 20%	8: FF	8: FF	8: 25	
	11 (Elem./sec. sch)		11: 20,000	11: 15%	11: CC	11: CC	11: 25	
	12 (7 uses)		12: 20,000	12: 60%	12: CC	12: CC	12: 25	
	19 (med. sys)		19: 1.5 ac	19: 70%	19: CC	19: CC	19: 25	
	41 (13 uses)		41: 5,000		41: BB	41: BB	41: 25	
						Sec. 3.2.6.5		



**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Residence Zone (R-2) [proposed]	None	15/acre	Res: 5,000 sf lot (I,41,K) Nonres: 20,000 sf site area <sup>29</sup> (8,11,12)	65%	SF: 7 MF/Nonres: 10 <sup>31</sup>	SF: 16 MF/Nonres: 20	20	25
Residence Zone (R-3) [current]	I (FDU) P (FDU) 7 (admin./prof. office) 11 (Elem./sec. schools) 12 (cultural use) 18 (13 uses) 30 (8 uses)	I: 1 P: 36	I: 5,000 7: 72,000 11: 20,000 12: 20,000 18: 0 30: 0	I: 70% P: 70% 7: 15% 11: 15% 12: 60% 18: 70%	I: AA P: CC 7: FF 11: CC 12: CC 18: CC 30: DD	I: AA P: CC 7: FF 11: CC 12: CC 18: CC 30: DD	Sec. 3.2.6.5	I: 25 P: 40 7: 25 11: 25 12: 25 18: 40 30: 40
Residence Zone (R-3) [proposed]	None	36/acre	Res: 5,000 sf lot (I, 18, 30) <sup>33</sup> Nonres: 20,000 sf site area (7, 11, 12) <sup>34</sup>	65% (I,P) 12,18 <sup>35</sup>	SF: 7 MF/Nonres: 10 <sup>36</sup>	SF: 16 MF/Nonres: 20	20	FDU Res: 25 40 MF resid. / nonres.)

<sup>29</sup> A special minimum lot size standard of 1.5 acres will be added for designator 19 (medical service), but designator 8 (admin./prof. office) is merged with other similar-impact uses with 20,000 lot size.

<sup>31</sup> For purposes of side and rear setbacks, the 10'/20' setbacks have been applied not only to the 20,000 sf lots but also to the 1.5 acre lots (has same CC designator as 20,000 sf lots) and the 43,560 lots because admin./professional office do not seem to warrant a greater setback than the other uses (e.g., medical service) in this category.

<sup>33</sup> The uses in designators 18 and 30 (except communications uses that will keep their current 0 min. lot size) have been given a min. lot size of 5,000 (instead of 0) to create a more uniform standard and because it is not apparent why these mostly civic, residential, and commercial uses should have no min. lot size.

<sup>34</sup> The minimum site area standards have been merged for designator 7 (admin./prof. offices) with the 20,000 sf lots because the impacts of the affected uses are similar.

<sup>35</sup> Both residential and nonresidential uses will have 65(70)% lot coverage, except designators 7 (admin./prof. offices) and 11 (elem./sec. schools) that will each have a lot coverage standard of 15%.

<sup>36</sup> Similar to the R-2, the setback standard for admin./prof. offices have been merged with the 20,000 sf lots because the impacts of the affected uses are similar.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>38</sup>	Residential Density (max.) <sup>39</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
<b>Mobile Home Zone (MH-1) [current]</b>	G (FDU, MH) M (FDU, MH) 11 (Elem./sec. schools) 12 (4 uses) 17 (6 uses) 41 (communic.)	G: 1 M: 8	G: 7,000 M: 7,000 11: 20,000 12: 20,000 17: 7,000 41: 5,000	G: 70% M: 70% 11: 15% 12: 60% 17: 70%	G: AA M: BB 11: CC 12: CC 17: BB 41: BB	G: AA M: BB 11: CC 12: CC 17: BB 41: BB	Sec. 3.2.6.5	G: 25 M: 16 11: 25 12: 25 17: 25 41: 25
<b>Mobile Home Zone (MH-1) [proposed]</b>	None	SF/MH: 1/7,000 sf lot MF/MH Park: 8/ acre <sup>38</sup>	SF/MH Unit 7,000 sf lot area (G,17,41) MF/MH Park: 7,000 sf site area (M)	65% (G,M,12,17) <sup>39</sup>	7 10	16 20	20	25
<b>Mobile Home Zone (MH-2) [current]</b>	1 (MH, FDU, res. care svcs) K (MH) 8 (admin./prof. office) 11 (Elem./sec. schools) 12 (civic, rec.) 41 (commun./util. distribution)	I: 1 K: 15	I: 5,000 K: 5,000 8: 43,560 11: 20,000 12: 20,000 41: 5,000	I: 70% K: 75% 8: 20% 11: 15% 12: 60%	I: AA K: BB 8: FF 11: CC 12: CC 41: BB	I: AA K: BB 8: FF 11: CC 12: CC 41: BB	Sec. 3.2.6.5	I: 25 K: 25 8: 25 11: 25 12: 25 41: 25

<sup>38</sup> the DD M for "mobile home dwelling" applies to mobile home parks, while the DD G for the same use refers to individual mobile home units, and so the proposed dimensional standards reflect this distinction.

<sup>39</sup> Both residential and nonresidential uses will have 70% lot coverage, except designator 11 (elem./second. school) will have a lot coverage standard of 15%.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Mobile Home Zone (MH-2) [proposed]	None	SF/MH: 1/5,000 sf lot	SF/MH Unit 5,000 sf lot (I,41)	65% (J,K,12) <sup>40</sup>	7	16	20	25
		MF/MH Park: 15/acre	MH Park: 5,000 sf site (K)		10	20		
Office Zone (O-1) [current]	M (FDU) 7 (Commun. towers, res. care facil.) 12 (res. care facil, cultural use, utility distrib.) 26 (office, comm. svcs, res. care facil.)	M: 8	M: 7,000 7: 72,000 12: 20,000 26: 10,000	M: 70% 7: 15% 12: 60%	M:BB 7: FF 12: CC 26: BB	M:BB 7: FF 12: CC 26: BB	Sec. 3.2.6.5	M: 16 7: 25 12: 25 26: 16
		SF: 1/7000 MF: 8/acre	1/7,000 sf lot	65%	0 (nonres. adjacency) 7 (res. adjacency)	0 (nonres. adjacency) 16 (res. adjacency)	20	SF, Office: 16 (M, 26: FDU) Other: 25 (7, 12: res. care fac., cult. use, utility distrib.)

<sup>40</sup> Both residential and nonresidential uses will have 70[5%] lot coverage, except designators 8 (admin. / prof. office) and 11 (elem./second. school) that will each have lot coverage standards of 20% and 15% respectively.

<sup>49</sup> A specific setback standard (to be determined) will be added for outdoor play areas associated with a day care when located next to a residential zone.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max.) <sup>8</sup>	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Office Zone (O-2) [current]	N(FDU) 7(res. care) 11(civic) 12(res. care, cultural) 15(child care) 20(child care) 27(office, comm. sys, prison, ups,)	N: 8	N: 5,000 7: 72,000 11: 20,000 12: 20,000 15: 14,000 20: 2.5 ac 27: 0	N: 70% 7: 15% 11: 15% 12: 60% 15: 80% 20: 60%	N:BB 7: FF 11: CC 12: CC 15: BB 20:BB 27:BB	N:BB 7: FF 11: CC 12: CC 15: BB 20:BB 27:BB	N: 25 7: 25 11: 25 12: 25 15: 25 20: 25 27: 26	
Office Zone (O-2) [proposed]	None	8/acre	SF: 5,000 sf lot Non SF: 0 sf	65%	0 (nonres. adjacency) 7 (res. adjacency) <sup>43</sup>	0 (nonres. adjacency) 16 (res. adjacency)	25	
Office Zone (O-3) [current]	L (FDU) J (FDU RND) 3(cemetery) 7(communic.) 12(cult, dist. utilities) 16(child care) 18(civic, rec.) 20(child care) 27(R&D) 30(res. care, comm. sys)	L: 22 J: 17	L: 5,000 J: 2,500 3: 10 ac 7: 72,000 12: 20,000 16: 10,000 18: 0 20: 2.5 ac 27: 0 30: 0	L: 75% J: 90% 3: 15% 7: 15% 12: 60% 16: 50% 18: 70% 20: 60%	L:BB J:DD 3: FF 7: FF 12: CC 16: BB 18: CC 20:BB 27:BB 30: DD	L:BB J:DD 3: FF 7: FF 12: CC 16: BB 18: CC 20:BB 27:BB 30: DD	L: 25 J: 40 3: 25 7: 25 12: 25 16: 25 18: 40 20: 25 27: 26 30: 40	

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Office Zone (O-3) [proposed]	None	22 / acre	5,000 sf lot <sup>45</sup> Non SF: 0	70%	0 (nonres. adjacency) 7 (res. adjacency)	0 (nonres. adjacency) 16 (res. adjacency)	20	SF: 25 Other: 40
Rural Village Center Zone (RVC) [current]	8 (wireless comm.) 12 (Util. distr.) 29(17 uses)	None	8: 43,560 12: 20,000 29: 0	8: 20% 12: 60%	8: FF 12: CC 29: DD	8: FF 12: CC 29: DD	Sec. 3:2.6.5	8: 25 12: 25 29: 30
Rural Village Center Zone (RVC) [proposed]	None	None	0	None	0 (nonres. adjacency) 10 (res. adjacency)	0 (nonres. adjacency) 25 (res. adjacency)	20	30
Neighborhood Commercial Zone (NC) [current]	M (FDU) 7(1) 11(3) 26(15) 33(1)	M: 8	M: 7,000 7: 72,000 11: 20,000 26: 10,000 33: 0	M: 70% 7: 15% 11: 15%	M: BB 7: FF 11: CC 26: BB 33: DD	M: BB 7: FF 11: CC 26: BB 33: DD	Sec. 3:2.6.5	M: 16 7: 25 11: 25 26: 16 33: 50
Neighborhood Commercial Zone (NC) [proposed]	None	8/acre	SF: 7,000 sf site (M,33) 10,000 sf site <sup>47</sup> (26,11)	Res: 65%	7	16	20	16 <sup>49</sup>

<sup>45</sup> All uses would be subject to a 5,000 sf min. site area.

<sup>47</sup> A specific min. site area standard of 0' has been added for designator 7 (communications -- limited to wireless comm. towers and antennae).

<sup>49</sup> A specific height standard of 25' has been added for designator 7 (communication limited to wireless comm. towers and antennae).

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Commercial Zone (C-1) [current]	O (FDU)	O: 36	K: 5,000	O: 75%	O: CC	O: CC	O: 25	
	K (res. care svcs)	K: 15	1: 30 ac.		K: BB	K: BB	K: 25	
	1 (golf course)		3: 10 ac.		1: FF	1: FF	1: 25	
	3 (cemetery)		8: 43,560		3: FF	3: FF	3: 25	
	8 (communic.)		12: 20,000		8: FF	8: FF	8: 25	
	12 (util. distr.)		16: 10,000		12: CC	12: CC	12: 25	Sec.
	16 (R&D)		17: 7,000		16: BB	16: BB	16: 25	3.2.6.5
	17 (group DU)		28: 0		17: BB	17: BB	17: 25	
	28 (28 uses)		29: 0		28: DD	28: DD	28: 30	
	29 (9 uses)		33: 0		29: DD	29: DD	29: 30	
33 (art. resid.)		38: 0		33: DD	33: DD	33: 50		
38 (per. storage)				38: BB	38: BB	38: 16		
Commercial Zone (C-1) [proposed]	None	36 /acre	0 (0, 8, 28, 29, 33, 38)	Res: 65%	0 (nonres. adjacency)	0 (nonres. adjacency)	30	10
Commercial Zone (C-2) [current]	R (FDU) 1 (golf course) 8 (prison) 30 (27) 31 (39) 32 (billboard) 33 (art.res.)	R: 44	1: 30 ac. 8: 43,560 30: 0 31: 0 32: 1,500 33: 0	R: 70% 1: 10% 8: 20%	R: CC 1: FF 8: FF 30: DD 31: DD 32: DD 33: DD	R: CC 1: FF 8: FF 30: DD 31: DD 32: DD 33: DD	R: 40 1: 25 8: 25 30: 40 31: 40 32: 30 33: 50	Sec. 3.2.6.5

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Commercial Zone (C-2) [proposed]	None	44 /acre	0 <sup>52</sup>	Res: 65%	0 (nonres. adjacency) 20 (res. adjacency) <sup>53</sup>	0 (nonres. adjacency) 25 (res. adjacency)	10	40
Commercial Zone (C-3) [current]	S (FDU) 1 (Golf course) 8 (Correct. use) 31 (Rehab facil.) 32 (Billboard) 33 (32 uses) 34 (35 uses)	S: 87	S: N/A 1: 30 ac 8: 1 ac 31: 0 32: 1,500 33: 0 34: 0	S: 80% 1: 10% 8: 20% 31: N/A 32: N/A 33: N/A 34: N/A	S: CC 1: FF 8: FF 31: DD 32: DD 33: DD 34: DD	S: CC 1: FF 8: FF 31: DD 32: DD 33: DD 34: DD	Sec. 3.2.6.5	S: 75 1: 25 8: 25 31: 40 32: 30 33: 50 34: 75
Commercial Zone (C-3) [proposed]	None	87/acre	0 <sup>54</sup>	Res: 65%	0 (nonres. adjacency) 20 (res. adjacency)	0 (nonres. adjacency) 25 (res. adjacency)	10	75
Parking Zone (P) [current]	40(1)	None	40: 5,000		40: AA	40: AA	Sec. 3.2.6.5	40: 16
Parking Zone (P) [proposed]	None	None	5,000 sf site area	None	7	16	10	16
Recreational Vehicle Zone (RV) [current]	M (trav. accommodation/campsite)	M: 8	M: 7,000	M: 70%	M: BB	M: BB	Sec. 3.2.6.5	M: 16
Recreational Vehicle Zone (RV) [proposed]	None	8/acre	7,000 sf site area	65%	7	16	10	16

<sup>52</sup> Special min. site area standards of 30 acres for designator 1 (golf course) and 1 acre for designator 8 (custodial facility) have been added.

<sup>53</sup> Use specific side and rear setback standards of 80' and 0' will be added for designators 1 (golf course) and 8 (supervision facility) when next to residential and nonresidential development respectively.

<sup>54</sup> Special min. site area standards of 30 acres for designator 1 (golf course) and 1 acre for designator 8 (custodial facility) have been added.

<sup>55</sup> A specific min. site area standard of 1 acre has been added for designator 8 (custodial facility and supervision facility).

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max.) <sup>8</sup>	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Office/Commercial/ Residential Zone (OCR-1) [current]	W (FDU) 8 (Supervision facility) 35 (39 uses)	None	8: 43,560 35: 0	W: 80% 8: 20%	W: DD 8: FF 35: EE	W: DD 8: FF 35: EE	Sec. 3.2.6.5	W: 140 8: 25 35: 140
Office/Commercial/ Residential Zone (OCR-1) [proposed]	None	None	0 <sup>56</sup>	65% (resid.)	0 (nonres. adjacency)	0 (nonres. adjacency)	10	140 <sup>58</sup>
Office/Commercial/ Residential Zone (OCR-2) [current]	X (FDU) 8 (supervision or custodial facility) 31 (Res. care) 36(47)	None	X: 0 8: 43,560 31: 0 36: 0	X: 80% 8: 20%	X: DD 8: FF 31: DD 36: EE	X: DD 8: FF 31: DD 36: EE	Sec. 3.2.6.5	X: 300 8: 25 31: 40 36: 300
Office/Commercial/ Residential Zone (OCR-2) [proposed]	None	None	0 <sup>59</sup>	65% (resid.)	0 (nonres. adjacency)	0 (nonres. adjacency)	10	300 <sup>61</sup>

<sup>57</sup> The 39 nonresidential uses (designators 35 and EE) are the core uses for determining the setbacks in this district. The EE setbacks for development next to residential districts currently range from 20' to 280' (2(h)). Because the setbacks in the higher range seem excessive, staff recommends lesser uniform setbacks (S = 50; R = 100) but ones that still offers adequate protection to adjacent residential uses, especially when combined with the new compatibility standards.

<sup>58</sup> A specific height standard of 25' has been added for designator 8 (custodial facility and supervision facility).

<sup>59</sup> A specific min. site area standard of 1 acre has been added for designator 8 (supervision facility and custodial facility).

<sup>60</sup> The 47 nonresidential uses (designators 36 and EE) are the core uses for determining the setbacks in this district. The EE setbacks for development next to residential districts currently range from 20' to 600' (2(h)). Because the setbacks in the higher range seem excessive, lower uniform setbacks (S = 100; R = 150) but ones that still offers adequate protection to adjacent residential uses, especially when combined with the new compatibility standards are recommended.

<sup>61</sup> A specific height standard of 25' for designator 8 (custodial facility and supervision facility) and 40' for designator 31 (rehabilitation service or shelter care) have been added.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Multiple Use Zone (MU) [current]	G (FDU, MH)	G: 1	G: 7,000	G: 70% K: 75% 2: 10% 6: 50% 8: 20% 9: 15% 17: 70% 25: 20%	G: AA	G: AA	G: 25	
	K (FDU, MH)	K: 15	K: 5,000		K: BB	K: BB	K: 25	
	2 (comm. stable)		2: 10 ac.		2: FF	2: FF	2: 30	
	6 (med. svcs)		6: 144,000		6: FF	6: FF	6: 25	
	8 (cust./correct.)		8: 43,560		8: FF	8: FF	8: 25	
	9 (anim. prod.)		9: 36,000		9: EE	9: EE	9: 30	
	17 (group DU)		17: 7,000		17: BB	17: BB	17: 25	
	25 (med. svcs)		25: 180,000		25: FF	25: FF	25: 30	
	28(9)		28: 0		28: DD	28: DD	28: 30	
	29(37)		29: 0		29: DD	29: DD	29: 30	
32 (billboard)		32: 1,500	32: DD	32: DD	32: 30			
38 (parking)		38: 0	38: BB	38: BB	38: 16			
Mixed Use Zone (MU) [proposed]	None	SF/MH Unit: 1/5,000 sf lot	5,000 sf site area <sup>63</sup>	65% (resid.)	0 (nonres. adjacency)	0 (nonres. adjacency)	20	30 <sup>65</sup>
	33(29)	MF/MH Park: 15/acre	33: 0		25 (res. adjacency)	25 (res. adjacency)		
Park Industrial Zone (P-I) [current]	34 (elem./sec.)	None	34: 0		33: DD	33: DD	Sec.	33: 50
					34: DD	34: DD	3.2.6.5	34: 75

<sup>63</sup> Use specific min. site area standards of 10 acres for designator 2 (commercial stables), of 144,000 sf for designator 6 (medical service – major & extended health care), of 1 acre for designator 8 (custodial facility and supervision facility), of 36,000 sf for designator 9 (animal production), and of 180,000 sf for designator 25 (medical service – outpatient) have been added.

<sup>64</sup> The 37 nonresidential uses (designators 29 and DD) are the core uses for determining the setbacks in this district. The DD setbacks for development next to residential districts currently range from 20' to 45' (1.5h if height is 30'). Because the setbacks in the higher range seem excessive, lower uniform setbacks (S = 10; R = 25) but ones that still offers adequate protection to adjacent residential uses, especially when combined with the new compatibility standards are recommended.

<sup>65</sup> A specific height standard of 16' has been added for designator 38 (parking).

<sup>67</sup> The 29 nonresidential uses (designators 33 and DD) are the core uses for determining the setbacks in this district. The DD setbacks for development next to residential districts currently range from 20' to 75' (1.5h if height is 50'). Because the setbacks in the higher range seem excessive, lower uniform setbacks (S = 25; R = 50) but ones that still offers adequate protection to adjacent residential uses, especially when combined with the new compatibility standards are recommended.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator	Residential Density (max.) <sup>68</sup>	Lot Size/ Site Area (min.) <sup>69</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Park Industrial Zone (P-I) [proposed]	None	None	0	0	0 (nonres. adjacency)	10	50 <sup>68</sup>	
Light Industrial Zone (I-1) [current]	1 (golf course) 32 (billboard) 33 (perish. foods manuf.) 34 (65) 35 (res. care) 36 (large bar, commun., dance hall)	None	1: 30 ac. 32: 1,500 33: 0 34: 0 35: 0 36: 0	1: 10%	1: FF 32: DD 33: DD 34: DD 35: EE 36: EE	1: FF 32: DD 33: DD 34: DD 35: EE 36: EE	1: 25 32: 30 33: 50 34: 75 35: 140 36: 300	
Light Industrial Zone (I-1) [proposed]	None	None	0 <sup>69</sup>	0	0 (nonres. adjacency)	10	75 <sup>71</sup>	

<sup>68</sup> A specific height standard of 75 has been added for designator 34 (elementary/secondary school).

<sup>69</sup> A specific min. site area standard of 30 acres has been added for designator 1 (golf course).

<sup>70</sup> The 65 nonresidential uses (designators 34 and DD) are the core uses for determining the setbacks in this district. The DD setbacks for development next to residential districts currently range from 20' to 112.5' (1.5(h) if height is 75'). Because the setbacks in the higher range seem excessive, staff recommends lesser uniform setbacks (S = 50; R = 75) but ones that still offers adequate protection to adjacent residential uses, especially when combined with the new compatibility standards.

<sup>71</sup> Use specific height standards of 25' for designator 1 (golf course), of 30' for designator 32 (billboard), of 50' for designator 33 (perishable foods manufacturing), of 140' for designator 35 (residential care services - shelter care victims of domestic violence & rehabilitation service or shelter care), and of 300' for designator 36 (large bar, communications, & dance hall) have been added.

**TABLE 6.3-1: Zone-Based Dimensional Standards**

District	Development Designator <sup>5</sup>	Residential Density (max.) <sup>6</sup>	Lot Size/ Site Area (min.) <sup>7</sup>	Lot Coverage (max. %)	Yards			Height (ft)
					Side (ft)	Rear (ft)	Front (ft)	
Heavy Industrial Zone (I-2) [current]	30 (retail, adult acts, agric., comm.) 32 (billboard) 34 (med. svcs, auto repair) 35 (52 uses) 36 (large bar))	1 caretaker	30: 0 32: 1,500 34: 0 35: 0 36: 0		30: DD 32: DD 34: DD 35: EE 36: EE	30: DD 32: DD 34: DD 35: EE 36: EE	Sec. 3.2.6.5	30: 40 32: 30 34: 75 35: 140 36: 300
Heavy Industrial Zone (I-2) [proposed]	None	None	0	0	0 (nonres. adjacency)	0 (nonres. adjacency)	10	140
Open Space Zone (OS) [current]	4 (open space)	None	4: 4,000	4: 10%	4: FF	4: FF	Sec. 3.2.6.5	4: 12
Open Space Zone (OS)	None	None	4,000 sf site area	5%	25 <sup>73</sup>	25	20	12

<sup>72</sup> The 52 nonresidential uses (designators 35 and EE) are the core uses for determining the setbacks in this district. The EE setbacks for development next to residential districts currently range from 20' to 280' (2h) if height is 140'. Because the setbacks in the higher range seem excessive, staff recommends lesser uniform setbacks (S = 100; R = 150) but ones that still offers adequate protection to adjacent residential uses, especially when combined with the new compatibility standards.

<sup>73</sup> The current setback for open space uses when next to low-density residential development is 4(h) or 48 feet and 2(h) or 24 feet when next to medium-density residential. Staff recommends uniform setback of 25 feet, which is closer to the medium-density standard, because it seems more reasonable as a uniform standard for all permitted uses.

## 6.4. RULES OF MEASUREMENT AND EXCEPTIONS TO DIMENSIONAL STANDARDS<sup>74</sup>

### 6.4.1. PURPOSE

This section is intended to provide uniform and consistent methods to measure and apply the dimensional standards in Table 6.3-1 and to provide exceptions to these standards.

### 6.4.2. LOT SIZE

#### A. Standards

##### 1. MS&R Street Frontage<sup>76</sup>

A lot with frontage on a street designated on the MS&R Plan shall be designed with sufficient width and depth so that motor vehicles can enter or leave the lot without backing out onto the MS&R street.

##### 2. Lot Width at Street Frontage<sup>77</sup>

If a lot has street frontage, the lot width at the street frontage shall be of a size sufficient for the purposes of locating motor vehicle and pedestrian access improvements as required by the UDC or Technical Manual.

#### B. Exceptions<sup>78</sup>

The following are excepted from the minimum lot size standards of this Article.

##### 1. Parcels that are:

a. Exclusively and permanently restricted by plat, deed, or covenant for private use, such as, but not limited to, common areas for parking, recreation, open space, drainage, or detention or retention of stormwater; or

b. Dedicated to the public for parks, open space, or other similar public purposes, such as placement of well sites, electrical substations, or other utilities.

c. An existing lot that is less than the minimum lot area required by the applicable zoning district because of a governmental act or condemnation or voluntary transfer of property in lieu of condemnation may be developed if the proposed development on the lot conforms to all other requirements of the UDC.

d. The lot was existing and of record on September 20, 1948, or was legally created under Pima County jurisdiction and of record at the time of annexation;

**NOTE: Sec. 3.2.10: Residential Density Calculations**, is not included because the proposed elimination of the development designator system would make the residential density calculations and examples in this section essentially obsolete. Furthermore, staff indicated that it rarely relies on this section and that calculating residential density is not otherwise a serious problem in the city, further reducing the need to retain this section.

<sup>76</sup> Text from LUC Section 3.2.14.3.

<sup>77</sup> Text from LUC Section 3.2.14.4

<sup>78</sup> Text from LUC Section 3.2.14.2.

- e. The lot is zoned for residential development; and
- f. The proposed development on the lot conforms to all other standards of this Article.

**6.4.3. LOT COVERAGE<sup>79</sup>**

**A. Coverage Included**

Lot coverage includes any area of a lot covered by the roof of a principal or accessory buildings.

**B. Calculation**

The lot coverage percentage is determined by dividing the total area of a lot covered by the roofs of principle and accessory buildings by the total lot area.

**6.4.4. SIDE, REAR, AND FRONT YARDS<sup>80</sup>**

**A. Measurement<sup>81</sup>**

1. The width of the rear, side, and front yard is the distance measured horizontally from the property line to the required distance for the particular yard, except where an MS&R setback applies the street setback shall be measured from the proposed future MS&R ROW line.<sup>82</sup>
2. On cul-de-sac and eyebrow front lots, the minimum street yard depth may be measured from a straight line drawn between the front lot corners, rather than measured directly from the curved front property line. In no case, however, shall the minimum street yard be reduced in excess of 50 percent by this alternative measurement. (See Figure 6.4.4-A.)
3. Where an unbroken section of a wall or a building is not parallel with the lot line, the required yard may be applied to the average width; however, such yard shall not be narrower at any point than half the required width, nor narrower at any point than three feet. (See Figure 6.4.4-A.)

<sup>79</sup> This section significantly simplifies the method for calculating lot coverage text taken from LUC Section 3.2.9. As part of this modification, the maximum allowable lot coverage in the dimensional table has been reduced by 5% to account for the fact that drive areas are no longer counted as lot coverage.

<sup>80</sup> The term "perimeter yard" will be replaced with "side yard" and "rear yard" in the UDC.

<sup>81</sup> Text from LUC Section 3.2.6.3.

<sup>82</sup> The replacement of the designator system with fixed setback standards is proposed to make the measurement of setbacks easier, especially for street yards. The street setback is measured from the property line except where there is a proposed MS&R ROW, in which case the setback is measured from that MS&R ROW.




Figure 6.4.4-A: Eyebrow front yards and non-parallel walls

**B. Exceptions<sup>83</sup>**

Encroachment into the required side or rear yard shall be allowed as provided below.

**1. Side and Rear Property Lines**

Along interior property lines, the following may extend two feet into the required width, provided the side or rear yard is not reduced to less than three feet.

- a. Chimney.
- b. Roof overhang.
- c. Bay window.

**2. Street Property Lines**

Along street property lines, the following may extend into the required width as provided below.

- a. <sup>84</sup>The following may extend two feet into the required street yard.  
 (1) Chimney.

<sup>83</sup> Text from LUC Section 3.2.6.6.

<sup>84</sup> Proposed change.

- (2) Roof overhang.
  - (3) Stairs.
  - (4) Bay window.
  - (5) Open structures.
- b. On any corner lot, no fence, structure, object, or planting shall be erected or maintained to interfere with the sight visibility triangle provisions set forth in the Technical Manual.
3. **Structures within Front Yards**  
Architectural features that are part of a solar energy system may project up to four feet into required front yards. Such architectural features include, but are not limited to, overhangs, moveable insulating walls and roofs, detached solar collectors, reflectors, and piping.
4. **Carports and Garages in Single-Family and Duplex Development**  
For carports, garages, or similar parking structures in single-family or duplex residential development on individual lots, a minimum 20 foot setback from the property line shall be provided in front of the entrance.<sup>85</sup>

**6.4.5. HEIGHT<sup>86</sup>**

**A. Measurement of Building**

Building height is the vertical distance measured from the average finished grade<sup>87</sup> to the highest point of a flat roof; to the deck line of a mansard roof; or to the middle (between the eave and ridge) of the highest gable of a pitched or hipped roof, except as follows. (See Figure 6.4.5-A)

1. **Historic Preservation Zone (HPZ)**

Building height is the vertical distance measured between the highest part of a structure and the finished grade at the midpoint of the front facade of the principal structure, excluding chimneys, mechanical equipment, and other miscellaneous additions.

2. **Airport Environs Zone (AEZ)**

Measurement of height for buildings as provided in Sec. 6.4.5 shall apply, except where the height may exceed the maximum height standards of Sec. 5.6.7, Airport Hazard Districts, in which case Sec. 5.6.7 prevails.

3. **Scenic Corridor Zone (SCZ)**

Any wall extending above the roof, such as a parapet wall or a fire wall, shall be considered part of the roof for purposes of measuring height.

4. **Hillside Development Zone (HDZ)**

See height measurement standards in Sec. 5.2.8.

<sup>85</sup> Wall heights are already covered under "Accessory Structures" so it is removed. Setbacks for carports and garages are standardized at 20 feet

<sup>86</sup> Text from LUC Section 3.2.7.

<sup>87</sup> Replace "design grade elevation" with "average finished grade" in Article 9: Definitions.

**B. Measurement of All Other Structures**

**1. General**

The height of all structures, other than buildings, shall be the vertical distance measured from design grade at the base of the structure at all points along that structure to the top of the structure. For structures within six feet of a property line, the design grade used for measuring height shall be the lower of the two grades on each side of that property line. Perimeter walls shall be measured from the base of the wall that faces an adjacent property.,

**2. Airport Environs Zone (AEZ)**

Measurement of height for structures and trees as provided in Sec. 6.4.5 shall apply, except where the height may exceed the maximum height standards of Sec. 5.6.7, Airport Hazard Districts, in which case Sec. 5.6.7 prevails.

DRAFT




Figure 6.4.5-A: Measurement of Building

**C. Height Exceptions**

The following structural elements may extend above the maximum allowed height, subject to any limitations listed. (See Figure 6.4.5-B.)

**1. Ornamental Elements**

Ornamental elements of the buildings and structures, such as spires, cupolas, belfries, clock towers, and domes, provided that such elements:

- a. Are not for human occupancy; and
- b. Do not exceed ten feet above the allowed structure height, except as follows:

(1) Ornamental elements of buildings and structures proposed to exceed ten feet above the allowed structure height are subject to review by the Design Review Board in accordance with Sec. 2.2.6 and approval as a special exception by the Zoning Examiner in accordance with procedures set forth in Sec. 3.6.1 and Zoning Examiner Special Exception Procedure, Sec 3.6.1.B.2 and provided that:

- (a) The ornamental element is an integral part of the building's architecture, and is not for human occupancy;
- (b) Ornamental elements proposed to exceed ten feet above the allowed structure height shall not be used for signage or;
- (c) The applicant shall demonstrate how the proposal minimizes impacts to existing land uses by including a view shed analysis and an analysis of the project site grades and adjacent property grades as part of their submittal;
- (d) Setbacks required for the architectural element will be one foot for each additional foot in height that it exceeds the base allowance of ten feet.

**2. Functional Elements**

Chimneys, mechanical penthouses, and bulkheads for stairwells, elevator shafts, or skylights, provided that such elements:

- a. Are not for human occupancy;
- b. Do not exceed ten feet above the allowed structure height; and
- c. Do not exceed 25 percent of the total roof area of the building on which they are located.

**3. Mechanical and Accessory Equipment**

Mechanical equipment, except solar energy equipment, and accessories necessary to the operation or maintenance of the building, provided that such elements:

- a. Do not exceed six feet above the allowed structure height;

- b. Do not exceed 25 percent of the total roof area of the building on which they are located;
  - c. Are concealed by an opaque screen; and
  - d. Are located away from the edge of the building a distance equivalent to the height of the elements.
4. **Solar Energy Equipment**  
Solar energy equipment, provided that such elements do not exceed the allowable height limits by more than ten feet.
5. **Parapet Walls and Safety Railings**  
Parapet walls and safety railings, provided they do not exceed the allowable height by more than four feet.
6. **Communications Antennae**  
Communications antennae not in conjunction with a communications facility, excluding dish antennae greater than three feet in diameter, provided such elements do not exceed the allowable height limits by more than five feet.
7. **Dish Antennae**  
Dish antennae, greater than three feet in diameter, provided that such elements:
  - a. Do not exceed the allowable height limits by more than ten feet;
  - b. Are located as close to the center of the roof structure as possible;
  - c. Are screened from view, to the maximum extent possible without interfering with reception, from the street frontage of the property at pedestrian level by an opaque screen, such as a parapet wall at the roof's edge; and
  - d. Are located on a building with a structure height greater than 40 feet.
8. **Communications Antennae**  
Communications antennae, other than those associated with wireless communications, in conjunction with a communications facility do not have a maximum height limitation, provided the antennae are located at least one foot distance for every foot in height measured from all property lines of residentially zoned property.
9. **Change of Zoning**  
If the Mayor and Council authorize a rezoning of property and buildings exist on the property that exceed the maximum required height for the proposed land use, the existing buildings shall be considered conforming. This exception applies only to buildings existing at the time of authorization, except as provided by Sec. 6.4.5.C.10 below.
10. **Historic Preservation Zone (HPZ)**  
New construction in a Historic Preservation Zone (HPZ) may exceed the height standards of the zone if additional height is needed to be compatible with

the height of other buildings within the development zone as determined by the Planning and Development Services Department Director.




Figure 6.4.5-B: Exceptions to Height Limit

## 6.5. DEVELOPMENT COMPATIBILITY STANDARDS<sup>89</sup>

### 6.5.1. PURPOSE

The purpose of the Design Compatibility Standards is to mitigate excessive visual, noise, odor, vibration intrusion, and other similar public health and safety concerns that may be created by new development projects on adjacent, existing residential properties.

### 6.5.2. APPLICABILITY

A. The standards of this section apply as follows:

1. Except within those districts and developments as provided in Section 6.5.2.B, the Development Compatibility Standards of this section shall apply when the proposed development is adjacent to attached dwelling units (e.g. townhouses and condominiums) in a subdivision or a detached dwelling unit. For the purposes of this section, these types of dwelling units are referred to as "affected properties";

<sup>89</sup> The text of this section was taken from the recently adopted transition standards in the IID. It was modified to apply more generally throughout the city and only to redevelopment projects next to existing residential development.

2. For projects within a planned development or subdivision, the Development Compatibility Standards shall apply only when the proposed development is adjacent to affected existing residential properties outside the planned development or subdivision boundaries;
  3. Additional applicability requirements are provided in Section 6.5.3.A;
  4. The standards shall apply along the side of the property adjacent to the affected property(ies) only; and,
  5. When the standards of this section conflict with other section of the UDC, the standards of this section shall control.
- B. The standards of this section do not apply as follows:
1. Proposed development within an Urban Overlay District, the Downtown Area Infill Incentive District requesting a Modification of Development Regulations, a Flexible Lot Development, a Planned Area Development, or a Planned Community Development. Development in these districts and types of development shall be controlled by the compatibility standards required by the applicable district or enabling ordinance; and,
  2. Proposed development adjacent to non-residential uses or multi-family residences, except as provided in Section 7.9.2.A.

**6.5.3. MITIGATION OF MULTI-STORY AND TALLER STRUCTURES**

- A. The proposed development's building setback (i.e. yard) from the affected property line shall be increased by one foot for every foot of height greater than 20 feet.
- B. The following standards are required of the proposed development when the applicability standards of Section 6.5.2 apply and the proposed building(s), in part or entirely, is less than 30 feet from the affected property line:
1. Windows at or above the second story of a structure shall be located or treated to reduce views into adjacent affected residential property's buildings and yard areas;
  2. Balconies shall be oriented away from affected residential property or use a screening device to reduce views into the buildings and yard areas of the rear or side yards of the affected residential property;
  3. The proposed building(s) shall be oriented so as to reduce views onto an affected residential property; and
  4. A buffer and/or screening device may be used to reduce views into the affected building and side and rear yards areas and may include features such as landscaping, a wall, or a similar architectural feature.
- C. The above compatibility standards may be reduced or eliminated. To reduce or eliminate the above compatibility standards a letter of stating no objection is required from the affected property owner. The letter shall be sent to PDSD stating no objection to reduction or elimination of the above compatibility standards.

**6.5.4. MITIGATION OF SERVICE AREAS**

- A. **Applicability**  
The following requirement applies with a finding of compliance approved by the PDSD Director when the proposed development is not regulated by Article 7

**6.5.5 Mitigation of Parking Facilities and Other Areas**

Development Standards, Article 4 Use Specific Standards, or special conditions resulting from a legislative decision.

**B. Requirement**

Potential nuisance or noisy areas shall be oriented away from affected residential property, such as by placing service areas for loading and garbage disposal between the developing site's buildings, behind opaque barriers, or by using architectural or landscaping treatments that effectively reduce nuisance impacts from service areas. The service area shall be mitigated to reduce the noise and view of the service features, reduce the emission of offensive odors to owners or occupants of adjacent properties or create a nuisance or hazard beyond the property lines of the project site, and prevent vibrations that are discernible beyond the property lines of the project site.

**6.5.5. MITIGATION OF PARKING FACILITIES AND OTHER AREAS**

**A. Applicability**

The following requirement applies with a finding of compliance approved by the PDS Director when the proposed development is not regulated by Article 7 Development Standards, Article 4 Use Specific Standards, or special conditions resulting from a legislative decision.

**B. Requirement**

Where the site has a parking areas or an area with noise and outdoor lighting features, the areas shall be screened from affected residential property by a combination of a wall or opaque non-chain link fence with a vegetative hedge or a row of trees that shall be dense enough to screen views onto the developing site. An alternative treatment may be used, such as using architectural or landscaping treatments that effectively reduce nuisance impacts from parking facilities and other areas. Where there is a finding that the vegetative screen will be opaque a masonry wall may not be required.

**6.5.6. COMPLIANCE STATEMENT REQUIRED**

A statement of compliance with the compatibility standards shall be included in the building permit for the development project. The statement shall attest to the property owner's agreement in providing the necessary compatibility treatment.

**6.6. PRINCIPAL LAND USE<sup>90</sup>**

**6.6.1. ONE OR MORE PRINCIPAL USES, SEPARATE PROJECTS**

One or more principal uses conducted as separate projects on a parcel shall be considered individually in determining the respective Land Use Classes and dimensional standards

<sup>90</sup> Text from LUC Section 3.2.2.1 and 3.2.2.2. This section has not been completed and will likely need to be revised by staff to meet the city's purposes now that proposed dimensional standards are available so that we now know which residential and nonresidential standards will be existing on the same site as horizontal mixed use. For the purposes of this draft, we have deleted all material related to the development designator and retained or modified text that may still be applicable to the new dimensional standards. Also, the current text addresses horizontal mixed-use only and not vertical mixed use, something that staff mentioned as a deficiency in the existing LUC.

**6.6.2 Two or More principal Uses, Same Project****6.6.2. TWO OR MORE PRINCIPAL USES, SAME PROJECT**

Two or more principal uses conducted as a single project, which integrates elements of the various uses, such as, but not limited to, vehicular parking, vehicular and pedestrian access, refuse collection, and loading services, as common use among the various uses in the project, shall have dimensional standards applied as follows.

**A. Two or More Uses, Same Dimensional Standards**

On projects with two or more uses that have the same dimensional standards, the dimensional standard requirements shall be applied on the site as if there were only one use.

**B. Two or More Uses, Different Dimensional Standards**

1. Projects without a residential component shall calculate the residential density (RAC), setbacks and the minimum lot size standards separately for the residential use. All other uses shall use the dimensional standards of the principal use having the least restrictive dimensional standards.

**6.7. ACCESSORY USES AND STRUCTURES<sup>91</sup>**

The dimensional standards for accessory uses and structures shall comply with the standards of this section. See Sec. 4.10 for general standards.

**6.7.1. STANDARDS FOR ALL ZONES**

In all zones, the buildings and structures used for accessory uses shall comply with the following.

- A.** An accessory building shall be developed in conformance with the standards of the principal land use, except as provided by this section and Sec. 6.6.2 below.
- B.** An accessory structure that exceeds the allowable height of a wall within a perimeter yard and is detached from a principal structure shall comply with the perimeter yard width standards of the principal structure, except that the accessory structure may be built to a parcel line with the consent of the adjoining or, when separated by an alley, adjacent property owner(s).
- C.** Accessory structures, such as light poles, flagpoles, and other tall and narrow structures that are similar, shall be exempt from the setback requirement.<sup>92</sup> Amateur radio towers are exempt from the setback requirement and are allowed to a maximum height of 100 feet.
- D.** All structures for animals shall be set back at least 50 feet from all property lines, except corrals that shall be set back ten feet from all property lines.
- E.** The maximum height of a wall or fence within a perimeter yard shall be six feet; however, the wall or fence may be higher than six feet, but no higher than ten feet, if: (See Illustration 6.61-A.)

<sup>91</sup> Parts of text from LUC Section 3.2.5. We have relocated to this section only those parts of 3.2.5 that pertain to dimensional standards for accessory uses and structures. All other parts of 3.2.5 are currently located in Sec. 4.10 Zone Districts of the draft UDC.

<sup>92</sup> This general exception, which is currently the last sentence of the previous provision, was made a separate standard because it is important and should be more prominently located for the reader.

1. At least 75 percent of the area above six feet in height is left unobstructed and open through the use of architectural elements, such as arches, columns, or wrought iron;
2. Part of, or located on top of, a retaining wall no higher than ten feet measured from design grade and no higher than six feet measured from the top of the retaining portion of the wall;
3. A greater height is required through the rezoning process or the special exception land use process; or
4. A greater height is required by a specific UDC standard.




Figure 6.6.1-A: Height of Wall or Fence within a Side or Rear Setback

- F. In nonresidential zones, walls or fences, as permitted in E. above, may exceed the height standards, provided the wall or fence complies with side and rear yard standards applicable to buildings on the site.

**6.7.2. STANDARDS FOR RESIDENTIAL ZONES**

The structures used for an accessory use within a residential zone shall comply with the following:

- A. Accessory structures shall not exceed 12 feet in height, unless attached to a principal structure. If attached to the principal structure, maximum height permitted shall be the same as for the principal structure.
- B. Accessory structures shall have a side and rear setback of seven feet and a street setback of 20 feet or the setback of the existing primary use.<sup>93</sup>

<sup>93</sup> Text added per staff direction.

- C. The total gross floor area (gfa) of all accessory structures shall not exceed 50 percent of the gfa of the principal structure. Accessory structures less than 200 square feet gra are exempt from this requirement.

**6.7.3. STANDARDS FOR NONRESIDENTIAL ZONES**

The structure used for an accessory use within a nonresidential zone shall comply with dimensional standards of the principle structure.<sup>94</sup>

DRAFT

---

<sup>94</sup> Text added per staff comment.

## ATTACHMENT D

### COMPARISONS BETWEEN THE DEVELOPMENT DESIGNATOR AND PROPOSED ZONE-BASED DIMENSIONAL STANDARDS

#### Comparison #1: 1-story single-family residence next to mix of 1- and 2-story residences

	Zone	# of Stories/ Building Height	Location Relative to Proposal
<b>Proposed Use</b>			
Single-family residence	R-1	1 story/12'	n/a
<b>Adjacent Uses</b>			
Single-family residences	R-1	1 story/12'	Side and rear
Single-family residence	R-1	2 stories/25'	Side

	Yards (i.e. building setbacks)		
	Side	Rear	Front
<b>LUC Requirement</b>	8' [DD 'AA': 6' or 2/3(H)]	8' [DD 'AA': 6' or 2/3(H)]	20' (established area, non-MS&R)
<b>Proposed Requirement</b>	7'	16'	20'

DD = Development Designator

**Comparison #2: 2-story single-family residence next to mix of 1- and 2-story residences**

	Zone	# of Stories/ Building Height	Location Relative to Proposal
<b>Proposed Use</b>			
Single-family residence	R-1	2 stories/25'	n/a
<b>Adjacent Uses</b>			
Single-family residences	R-1	1 story/12'	Side and rear
Single-family residence	R-1	2 stories/25'	Side

	Yards (i.e. building setbacks)		
	Side	Rear	Front
<b>LUC Requirement</b>	16'-8" [DD 'AA' = 6' or 2/3(H)]	16'-8" [DD 'AA': 6' or 2/3(H)]	37'-6" [established area, non-MS&R: 1.5 (H)]
<b>Proposed Requirement</b>	<p><b>Current DCS: 12' [7' (standard setback) + 5' (DCS setback)] + DCS Mitigation of Taller Buildings</b></p> <p><b>If DCS applies only when adjacent to 1-story:</b></p> <p>From property line next to 1-story = 12' + DCS Mitigation of Taller Buildings;</p> <p>From property line next to 2-story = 7'</p>	21' [16' (standard setback) + 5' (DCS setback)]	20'

DD = Development Designator  
 DCS = Development Compatibility Standards

**Comparison #3: Multi-family next to 1- and 2-story residences**

	<b>Zone</b>	<b># of Stories/ Building Height</b>	<b>Location Relative to Proposal</b>
<b>Proposed Use</b>			
Multi-family residence (i.e. apartment)	R-2	2 stories/25'	n/a
<b>Adjacent Uses</b>			
Single-family residences	R-1	1 story/12'	Side and rear
Multi-family residence	R-2	2 stories/25'	Side

	<b>Yards (i.e. building setbacks)</b>		
	<b>Side</b>	<b>Rear</b>	<b>Front</b>
<b>LUC Requirement</b>	18'-9" [DD 'BB': 10' or ¼(H)]	18'-9" [DD 'BB': 10' or ¼(H)]	37'-6" [established area, non-MS&R: 1.5 (H)]
<b>Proposed Requirement</b>	From property line abutting the 1-story = 15' [10' (standard setback) + 5' (DCS setback)] + <b>Other Applicable DCS Requirements</b>  From property line abutting the 2-story = 10'	25' + DCS [20' (standard setback) + 5' (DCS setback)]	20'

DD = Development Designator  
DCS = Development Compatibility Standards

**Comparison #4: Multi-family next to 1- and 2-story residences**

	<b>Zone</b>	<b># of Stories/ Building Height</b>	<b>Location Relative to Proposal</b>
<b>Proposed Use</b>			
Multi-family residence (i.e. apartment)	R-3	3 stories/40'	n/a
<b>Adjacent Uses</b>			
Single-family residence	R-2	1 story/12'	Side
Multi-family residences	R-3	2 stories/25'	Side and rear

	<b>Yards (i.e. building setbacks)</b>		
	<b>Side</b>	<b>Rear</b>	<b>Front</b>
<b>LUC Requirement</b>	<b>30'</b> [DD 'CC': 10' or $\frac{3}{4}$ (H)]	<b>30'</b> [DD 'CC': 10' or $\frac{3}{4}$ (H)]	<b>40'</b> (MS&R: 21' or H)
<b>Proposed Requirement</b>	From property line abutting the 1-story = <b>30'</b> [10' (standard setback) + 20' (DCS setback) + <b>Other Applicable DCS Requirements</b>  From property lines abutting the multi-family residences = <b>10'</b>	<b>20'</b>	<b>20'</b>

DD = Development Designator  
DCS = Development Compatibility Standards

**Comparison #5: Office next to 1-story residences**

	<b>Zone</b>	<b># of Stories/ Building Height</b>	<b>Location Relative to Proposal</b>
<b>Proposed Use</b>			
Office (corner lot)	O-1	1 story/16'	n/a
<b>Adjacent Uses</b>			
Single-family residence	R-1	1 story/12'	Side and rear
Street	n/a	n/a	Side

	<b>Yards (i.e. building setbacks)</b>		
	<b>Side</b>	<b>Rear</b>	<b>Front</b>
<b>LUC Requirement</b>	From property line abutting 1-story residence = <b>12'</b> [DD 'BB': 10' or ¾(H)]  From street ROW = <b>21'</b> (Zoning Administrator interpretation: corner lots on MS&R shall have same setback on side street as setback along MS&R)	<b>12'</b> [DD 'BB': 10' or ¾(H)]	<b>21'</b> (MS&R: 21' or H)
<b>Proposed Requirement</b>	<b>7' + Applicable Service &amp; Parking Area DCS Requirements</b>	<b>16'</b>	<b>20'</b>

DD = Development Designator  
DCS = Development Compatibility Standards

**Comparison #6: Retail next to commercial and a 1-story residence**

	<b>Zone</b>	<b># of Stories/ Building Height</b>	<b>Location Relative to Proposal</b>
<b>Proposed Use</b>			
Retail	C-1	2 stories/30'	n/a
<b>Adjacent Uses</b>			
Single-family residence	R-1	1 story/12'	Rear
Commercial Uses	C-1	2 stories/30'	Both sides

	<b>Yards (i.e. building setbacks)</b>		
	<b>Side</b>	<b>Rear</b>	<b>Front</b>
<b>LUC Requirement</b>	0'	45' [DD 'DD' = 1.5(H)]	30' (MS&R: 21' or H)
<b>Proposed Requirement</b>	0'	35' [25' (standard setback) + 10' (DCS setback)] + <b>Other Applicable DCS Requirements</b>	10'

DD = Development Designator  
 DCS = Development Compatibility Standards

**Comparison #7: Restaurant next to 1-story residence and commercial uses**

	<b>Zone</b>	<b># of Stories/ Building Height</b>	<b>Location Relative to Proposal</b>
<b>Proposed Use</b>			
Restaurant	C-1	2 stories/30'	n/a
<b>Adjacent Uses</b>			
Single-family residences	R-1	1 story/12'	Rear
Commercial Uses	C-1	2 stories/25'	Both sides

	<b>Yards (i.e. building setbacks)</b>		
	<b>Side</b>	<b>Rear</b>	<b>Front</b>
<b>LUC Requirement</b>	0'	45' [DD 'DD' = 1.5(H)]	30' (formula = 21' or H)
<b>Proposed Requirement</b>	0'	35' [25' (standard setback) + 10' (DCS setback)] + <b>Other Applicable DCS Requirements</b>	10'

DD = Development Designator

DCS = Development Compatibility Standards

**Comparison #8: Bar next to 1-story residence and commercial uses**

	Zone	# of Stories/ Building Height	Location Relative to Proposal
<b>Proposed Use</b>			
Bar	C-3	1 story/15'	n/a
<b>Adjacent Uses</b>			
Single-family residence	R-2	1 story/12'	Rear
Commercial uses	C-3	1 story/15'	Both sides

	Yards (i.e. building setbacks)		
	Side	Rear	Front
<b>LUC Requirement</b>	0'	22.5' [DD 'DD': 1.5(H)]	21' (MS&R: 21' or H)
<b>Proposed Requirement</b>	0'	25' + Other Applicable DCS Requirements	10'

DD = Development Designator

DCS = Development Compatibility Standards