



22nd & Houghton Planned Area Development (PAD)

**City of Tucson
November 21, 2017**

22nd & Houghton Planned Area Development

Houghton Road and 22nd Street
Tucson, Arizona

Submitted to:

City of Tucson
Planning & Development Services Department
201 North Stone Avenue
Tucson, Arizona 85701

Prepared for:

22nd Street Baptist Church
6620 East 22nd Street
Tucson, Arizona 85710
Telephone: (520)

&

Brentwood Development
5800 Stanford Ranch Road
Suite 210
Rocklin, CA 95765

Prepared by:

The Planning Center
2 East Congress Street, Suite 600
Tucson, AZ 85701

&

Sustainability Engineering Group
8280 East Gelding Dr., Suite 101
Scottsdale, AZ 85260
Telephone: (480) 588-7226

&

Stantec Consulting Inc.
5151 East Broadway Boulevard, Suite 400
Tucson, AZ 85711
Telephone: (520) 750-7474

Lazarus Silvyn & Bangs
5983 East Grant Road
Tucson, Arizona 85712
Telephone: (520) 207-4464

Case No. C9-17-02
November 21, 2017

Part I Introduction	5
A. Project Vision & History	6
B. Rationale and Benefits for Use of a PAD.....	8
C. Benefits to the Community.....	8
D. Conformance with Adopted Plans	9
1. Plan Tucson	9
2. Houghton East Neighborhood Plan.....	11
E. Compatibility to Adjoining Land Uses	13
F. Suitability with Existing Infrastructure	13
Part II Site Analysis.....	14
A. Significant Natural and Built Constraints	15
B. Transportation and Circulation.....	15
1. Surrounding Roadways	15
2. Major Streets and Routes.....	16
3. Traffic Volumes	16
4. Alternate Modes of Transportation	16
C. Zoning.....	20
D. Adjacent Parcels and Structures	22
E. Park, Recreation and Open Space	24
F. Public, Educational, Community and Cultural Facilities.....	26
G. Existing Drainage.....	28
H. City of Tucson Ordinances	30
I. Existing Infrastructure	30
1. Electric.....	30
2. Sewer	30
3. Water.....	30
J. Topography.....	34
K. Vegetation and Wildlife	36
1. Sonoran Desert Scrub.....	36
2. Xeroriparian Class C	36
3. Arizona Game and Fish Department.....	36
L. Soils	39
M. Viewsheds and Visual Analysis	39
N. Cultural Sites	43
1. Arizona State Museum Letter.....	43
Part III PAD District Proposal.....	45
A. Plan Overview.....	46
B. Proposed Land Uses	51
1. Commercial	51
2. Open Space	51
C. Development Standards	55
1. Permitted Uses.....	55
2. Prohibited Uses.....	57



3.	Open Space Permitted Uses.....	57
D.	Development Standards	58
1.	Property Development.....	58
2.	Building Height Standards.....	58
3.	Parking Standards.....	58
4.	Scenic Route Standards.....	59
5.	Loading.....	60
6.	Solid Waste Disposal	60
7.	Hours of Operation	60
8.	Lighting & Security	60
E.	Drainage Plan	61
1.	Response to Hydrologic Characteristics	61
F.	Open Space.....	63
1.	Open Space Development Standards.....	63
2.	Riparian Standards.....	63
3.	Riparian Resources.....	64
G.	Landscape Program	67
1.	Streetscape	67
2.	Parking Area & Pedestrian Path Landscape	67
3.	Landscape/Screening borders adjacent to residential uses	67
H.	Circulation Plan.....	69
1.	Access Points.....	69
2.	Planned Improvements	69
3.	Traffic Volumes	69
4.	Level of Service.....	70
5.	Pedestrian Circulation	70
I.	Phasing Schedule.....	73
J.	Cultural Resources	73
K.	Water Conservation Standards.....	73
1.	Low Water Use Plants.....	73
2.	Irrigation	73
3.	Rainwater Harvesting.....	74
4.	Heat Island Mitigation.....	74
L.	Pima County Wastewater Reclamation	74
Part IV: Implementation & Administration		75
A.	Design Review Committee	76
B.	Design Standards	76
C.	Interpretations and Amendments.....	77
1.	Interpretation	77
2.	Amendments	77
Bibliography		78



V: Appendices 79

Appendix A: Neighborhood Shopping Center	80
Appendix B: Public Sewer Improvement Plans.....	83
Appendix C: Water Master Plan.....	87
Appendix D: Houghton Road and 22nd Street Intersection Future Modifications.....	95

List of Exhibits


Exhibit I: Location Map.....	7
Exhibit I.D.1: Plan Tucson Future Growth Scenario Map	10
Exhibit I.D.2: HENP Map.....	12
Exhibit II.B.1: Traffic.....	18
Exhibit II.B.2: Major Streets & Routes.....	19
Exhibit II.C: Zoning.....	21
Exhibit II.D: Existing Land Uses.....	23
Exhibit II.E: Recreation	25
Exhibit II.F: Community Facilities.....	27
Exhibit II.G: Existing Drainage	29
Exhibit II.I.3.a: Sewer Network.....	31
Exhibit II.I.3.b: Pima County Wastewater Reclamation Capacity Letter.....	32
Exhibit II.I.4: Tucson Water Letter.....	33
Exhibit II.J: Topography	35
Exhibit II.K: Vegetative Communities	37
Exhibit II.K.3: Arizona Game and Fish Letter	38
Exhibit II.M: Photo Key Map.....	40
Exhibit II.M.1: Site Photos.....	41
Exhibit II.N: Arizona State Museum Archaeological Survey	44
Exhibit III.A.1: Proposed Architectural Renderings	48
Exhibit III.A.2: Proposed Architectural Rendering with Vestibules	49
Exhibit III.A.3: Proposed Retail Architectural Renderings	50
Exhibit III.B.1: Conceptual Land Use Plan	53
Exhibit III.B. 2: Illustrative Site Plan	53
Exhibit III.E: Preliminary Grading & Drainage Plan.....	62
Exhibit III.F.3.a: Riparian Resources	65
Exhibit III.F.3.b: Riparian Mitigation Plan	66
Exhibit III.G: Landscape Borders	68
Exhibit III.H.1: Circulation Concept	72
Exhibit Appendix A.1: Existing Food & Drug Stores	81
Exhibit Appendix A.2: Existing Fry's Locations	82



List of Tables

Table II.B.3: Traffic Volumes..... 16
Table II.C: Surrounding Zones.....20
Table II.D: Existing Land Uses.....22
Table III.D.1: Development Area Standards58
Table III.H.3: Proposed Use-Trip Generation 70





22nd & Houghton Planned Area Development (PAD)

I. Introduction


City of Tucson

A. Project Vision & History

The 22nd and Houghton Planned Area Development (the “PAD” or “PAD District”) consists of approximately 16.2 acres located on an infill site at the northeast corner of 22nd Street and Houghton Road near the eastern city limits (the “Property”) (See *Exhibit I: Location Map*). Over the past several years, eastern Tucson has flourished with new residential and commercial development. The Houghton Road Corridor, located along the western boundary of the subject property, was recently widened to a total of six travel lanes with a regional multipath corridor. 22nd Street was also widened from two to four lanes and the intersection of 22nd and Houghton was improved to increase the traffic capacity. These improvements allow for increased visibility to this intersection ultimately making this a prime location for a neighborhood shopping center. The vision for the proposed neighborhood shopping center is to provide a unique shopping opportunity for the surrounding community that will feature upscale neighborhood retail establishments and restaurants as well as a Fry’s Food and Drug Store with an associated gas station and kiosk. The Fry’s store will offer additional amenities such as a drive-through pharmacy, click list online ordering, a Sushi Island, an enhanced meat counter and deli, a large selection of organic produce, a Pan Asian bistro, a Starbucks, outdoor seating and dining areas, and apparel.



Exhibit I: Location Map




LEGEND

- Project Boundary
- Township, Range & Section
- Jurisdictional Boundary
- Houghton Road Corridor

Notes:

Project Site is located at:
 Township 14S, Range 15E and Section 13
 Acreage: Approx. 16.2 AC, Parcel ID #'s:
 133-38-008J, 133-38-008F



FILE NAME: location_6x8.mxd
 SOURCE: Pima County GIS, 2016



B. Rationale and Benefits for Use of a PAD

The City of Tucson's Planned Area Development Zone (PAD) designation allows property owners to comprehensively develop the land with development standards that would not otherwise be possible through the traditional Unified Development Code (UDC) zoning classifications. The City's current UDC is structured for commercial development without consideration of the existing physical constraints on the property or surrounding it. The current development proposal is for a neighborhood shopping center including a grocery store, associated gas station and two retail pads. Using C-1 as the base zone, this PAD allows for site specific zoning and design regulations to ensure a quality design that can protect the integrity of existing neighborhoods. It will:

- more effectively address neighborhood concerns through customized land uses and development and design standards;
- design for outdoor sales along the front side of the building with conditions that require the vestibule doors remain open during business hours and shut when the store is closed;
- allow for modifications to landscape borders and screening plans to respond to both neighborhood concerns and consolidated open space provisions;
- ensure protection for adjacent neighbors with larger buffers and protection of undisturbed open space areas adjacent to existing single family residential properties; and
- utilize existing infrastructure near the project site.

This PAD shall serve as the primary mechanism for controlling the development of the property. In accordance with Section 3.5.5 of the Unified Development Code (UDC), the PAD standards herein supersede the standards of the UDC. Where specific references to UDC standards are provided, those reference the UDC standards in existence on the date this PAD is approved by the Mayor and Council.

C. Benefits to the Community

The 22nd and Houghton PAD will foster significant benefits to the community, among them include:

- Providing a unique shopping opportunity for the local community that will feature a Fry's Food and Drug Store with amenities including, but not limited to, a drive-through pharmacy with click list online ordering, a Sushi Island, an enhanced meat counter and deli, a large selection of organic produce, a Pan Asian bistro, a Starbucks, outdoor seating and dining areas, and apparel;
- Developing a neighborhood commercial shopping center to serve the far east-side neighborhoods, reducing vehicle miles for basic goods and services;
- Setting aside open space elements to preserve and protect privacy of adjacent residents as well as native vegetation and wildlife; and
- Advancing the economic sustainability of the area through the creation of additional tax revenue and quality employment opportunities.



D. Conformance with Adopted Plans

The PAD District is consistent with policy recommendations in the City's Plan Tucson and the Houghton East Neighborhood Plan. Both stress the compatibility between uses, the promotion of commercial development along arterials corridors, and the protection of established neighborhoods.


1. Plan Tucson

As shown on *Exhibit I.D.1: Plan Tucson Future Growth Scenario Map*, the PAD is located within an area designated as a Neighborhood of Greater Infill Potential (NGIP). NGIP are neighborhoods that have the potential for new residential and commercial development/redevelopment in the next several decades. These neighborhoods include a mix of uses such as: a variety of housing types, grocery stores, and other retail and services. The goal of the PAD is to promote the major intersection of 22nd Street and Houghton Road as an infill site for neighborhood commercial development. The PAD development regulations and design standards are envisioned to protect established residential neighborhoods adjacent to the site by orienting new development to protect the privacy of surrounding residential land uses. Other related policies include:

- LT 1: Integrate land use, transportation, and urban design to achieve an urban form that supports more effective use of resources, mobility options, more aesthetically-pleasing and active public spaces, and sensitivity to historic and natural resources and neighborhood character.
- LT 7a: Use the Future Growth Scenario Map as a general guide for determining the general location of development opportunities, development patterns, and land use and transportation concepts, while also considering area and site-specific issues.
- LT 9: Plan Tucson supports locating housing, employment, retail, and services in proximity to each other to allow easy access between uses and reduce dependence on the car.
- RR 4: The Redevelopment and Revitalization element goals of Plan Tucson support infill projects that build from existing assets of areas identified for redevelopment and revitalization.
- BC 8: The Business Climate element of Plan Tucson promotes continued economic viability of existing neighborhoods and commercial districts by supporting a safe, distinctive, well-maintained, and attractive community with neighborhoods made up of residences and businesses that contribute to Tucson's quality of life and economic success.



Exhibit I.D.1: Plan Tucson Future Growth Scenario Map



2. Houghton East Neighborhood Plan

The intent of the Houghton East Neighborhood Plan (HENP) is to guide future development to protect the natural amenities of the area and to enhance existing neighborhoods. The HENP covers a two-square-mile area bounded by Speedway Boulevard, Tanque Verde Loop/Melpomene Road, 22nd Street and Houghton Road. In accordance with the HENP Policy Concepts Map, the HENP supports non-residential development at the two major intersections located within the HENP, 22nd Street and Houghton Road, and Broadway Boulevard and Houghton Road (See *Exhibit I.D.2: HENP Policy Concepts Map*). Furthermore, the PAD at 22nd and Houghton is recommended for commercial development and is envisioned to accommodate a neighborhood shopping center with over 25% of the subject property to be set aside as open space. See *Appendix A* for additional information on the definition of neighborhood commercial. The history of the HENP includes two amendments, including one for the PAD:


- Southeast corner of Broadway and Houghton was approved in 1990 to increase building height at the to 28 feet.
- The 22nd and Houghton and PAD (The Property) was approved for plan amendment on March 8, 2016 which removed the 20-foot height restriction for this location. Per this plan amendment, the approved building height is 26 feet.

Other HENP nonresidential policies that apply to the PAD proposal:

- HENP-Policy I: Develop a variety of retail, service and office uses at appropriate locations.
 - HENP- Policy 1.A: Locate nonresidential uses only at the intersections of Houghton Road with Broadway and 22nd Street.
 - HENP Policy 1.B: Require nonresidential uses to provide access exclusively onto arterial streets.
- HENP Policy 2: Require nonresidential development to be compatible with adjacent uses.
 - HENP Policy 2A: Require security and parking lot lighting to be shielded and directed away from adjacent residential uses, in accordance with zoning regulations.
 - HENP Policy 2B: Required new nonresidential development to implement a landscape plan with a mixture of plant size, including mature trees, understory shrubs and ground cover.
 - HENP Policy 2C: Require new nonresidential development to employ design elements such as masonry walls, earth berms and sufficient landscaping to buffer adjacent uses.
 - HENP Policy 4 C: Require neighborhood commercial or office uses to retain 20 percent of the Property as consolidated open space.
 - HENP Policy 1A: Require developers to submit a hydrology/hydraulic study of drainage conditions and design of proposed improvements, considering both upstream and downstream conditions, as established in the Floodplain Regulations.



Exhibit I.D.2: HENP Map



E. Compatibility to Adjoining Land Uses

The Property is suitable for neighborhood shopping center uses as it is located at the major intersection of 22nd and Houghton. This intersection and surrounding roadways were recently improved to widen Houghton Road to 6-lanes and 22nd Street to 4-lanes. In addition, this intersection has been identified by Plan Tucson, Houghton East Area Plan and the Rincon Southeast Subregional Plan as a location intended for commercial uses. The following land uses surround the PAD District:


- North: a one-story single-family residential subdivision exists to the north. Natural open space buffers as well as a masonry wall along the property boundary will ensure future compatibility with adjoining neighbors.
- West: the northwest and southwest corners of the Houghton/22nd intersection are both zoned for commercial. The northwest corner consists of a one-story convenience store and the southwest corner is currently vacant. An approximately 35' wide landscape buffer is provided along the western boundary of the property adjacent to the Houghton Road Greenway.
- South: the site directly to the south is currently vacant but was once zoned for commercial in 2007. Due to the economic downturn, the proposed retail and office complex did not develop, and the rezoning expired.
- East: a one-story single-family residential exists to the east. Natural open space buffers as well as a masonry wall along the property boundary will ensure future compatibility with adjoining neighbors.

F. Suitability with Existing Infrastructure

The proposed PAD will be an infill development along two major arterials. Infrastructure improvements have recently been completed in conjunction with the Houghton Road Corridor and 22nd Street improvements. The following has been approved by the public agencies:

- A Public Sewer Improvement Plan and a Private Sewer Plan have been completed to enable the Property to connect to the Pima County public sewer system (See *Appendix B*).
- A Preliminary Water Master Plan was approved by City of Tucson Water Department as part of the Houghton Road improvement and security water service to the Property (See *Appendix C*).
- A Traffic Impact Study by Stantec Consultants Inc. was completed as part of the Houghton Road Corridor planning. Access point locations and traffic improvements were recommended as part of this study and approved by the City of Tucson Transportation Department. See TIS that is submitted separately.





22nd & Houghton Planned Area Development (PAD)

II. Site Analysis

City of Tucson

A. Significant Natural and Built Constraints

The Property is an infill parcel located on the northeast corner of two arterial streets: 22nd Street and Houghton Road and is surrounded by existing development to the north, west, south and east. The Property is currently undisturbed except for a Tucson Electric Power (TEP) electrical box located in the south-central portion of the property and existing grading due to the Houghton Road and 22nd roadway widening improvements. In addition, TEP electrical transmission lines are located along the south and western boundaries of the Property, within the rights-of-way of Houghton Road and 22nd Street.

A small drainageway runs through the middle of the Property from east to west with flows of slightly over 100 cfs. The existing vegetation on Property consists largely of upland desert scrub predominately including Creosote, Foothills Palo Verde, Mesquite, Brittle Bush, and Prickly Pear. Plant density across much of the Property is medium to low upland scrub vegetation, typical to the region. The small drainage area near the west end of the property (near the Houghton Road culvert), consists of more dense vegetation including Foothills Palo Verdes, Mesquites and a small number of Hackberries. There is no vegetation type or density on Property that meets the Pima County Xeroriparian “C” habitat requirements (as mapped). A very small area near the Houghton Road culvert will be evaluated at time of Development Plan for density and species make up for inclusion in protected riparian habitat per City requirements.

B. Transportation and Circulation

1. Surrounding Roadways

As shown on *Exhibit II.B.1: Traffic*, the PAD is bordered by Houghton Road on the west and 22nd Street on the south. Houghton Road and 22nd Street are currently under construction for improvements. The existing right-of-way is 200 feet. The posted speed limit on Houghton Road is currently 45 mph. Houghton Road was recently widened from Broadway Boulevard to 22nd Street to include six lanes, improved access control, bike lanes, sidewalks, landscaping that maintains the scenic corridor, greenway and improved drainage. Houghton Road Greenway is proposed along the east side of Houghton Road and will consist of a 12-foot paved path and a landscaped corridor.

22nd Street is a two-lane arterial roadway with a striped shoulder and a posted speed limit of 40 mph. 22nd Street currently has a right-of-way of 150-feet. 22nd Street was recently improved to include: four lanes, bike lanes and sidewalks east to just beyond Barbara Place as part of the Houghton Corridor improvement.

The 22nd and Houghton Road intersection was also improved to include dual left turn lanes and a separate dedicated right turn lane in all four directions. The east/west thru movement along 22nd Street will remain as a single thru lane.



2. Major Streets and Routes

The Property is located at the intersection of two major streets within the MS&R plan: 22nd Street and Houghton Road. Houghton Road is classified as a Scenic Arterial Street in the City of Tucson Major Streets and Routes Plan (2007). 22nd Street is classified as an Arterial Street in the City of Tucson Major Streets and Routes Plan (2007). Both roadways and the intersection are undergoing improvements for future roadway capacity and future development (See *Exhibit II.B.2: Major Streets and Routes*).

The existing and planned rights-of-way for all roadways listed on the City of Tucson Major Streets and Routes Plan within a one-mile radius of the Property are shown on *Exhibit II.B.1: Traffic*.

3. Traffic Volumes

Average Daily Traffic (ADT) volumes were derived from Pima Association of Governments Traffic Count Records as shown on *Table II.B.3: Traffic Volumes*. Stantec Consulting Services completed a Traffic Impact Study of the roadways surrounding the intersection of 22nd Street and Houghton Road and determined that the intersection currently operates at a Level of Service B, indicating a reasonable free-flow of traffic. The Traffic Impact Study has been submitted under a separate cover.

Table II.B.3: Traffic Volumes

Road	Segment	ADT	Date
Houghton Road	Broadway Boulevard to 22 nd Street	18,693	2011
Houghton Road	22 nd Street to Old Spanish Trail	11,972	2013
22 nd Street	Harrison Road to Houghton Road	8,563	2012
22 nd Street	Houghton Road to Melpomene Way	9,514	2011

Source: Pima Association of Governments

4. Alternate Modes of Transportation


According to SunTran's system-wide transit map, Sun Tran Bus Route #7, Route #17, and Route 201X are all located within one mile of the Property (See *Exhibit II.B.1: Traffic*). There is also a Park and Ride lot located within one mile of the Property at the intersection of Houghton Road and Broadway Boulevard. As a result of coordinating with City staff on the Houghton Road Corridor improvements, the Traffic Impact Study (submitted under a separate cover) indicates that there will be a bus stop incorporated along Houghton Road near the proposed PAD. It is unknown as to when service will be integrated along Houghton Road.



There are ± 8 bike routes within a one-mile radius of the site. (See *Exhibit II.B.1: Traffic*). As part of the Houghton Road improvements, a multi-use path (greenway) is under construction along the west boundary of the PAD. The improvements along 22nd Street also include bike lanes on the southern boundary of the PAD.



Exhibit II.B.1: Traffic



LEGEND


- Project Site
- One-Mile Radius
- Traffic Signals
- Scenic Routes
- Bike Routes
- Bus Route
- Bus Stops
- P Park & Ride Lot
- (90'/90') Existing ROW/Planned ROW



NORTH
 0' 1,000' 2,000'
 FILE NAME: traffic_6x8.mxd
 SOURCE: Pima County GIS, 2016



Exhibit II.B.2: Major Streets & Routes



C. Zoning

The subject property is currently zoned SR (Suburban Ranch). Zones for the surrounding properties within 150 feet can be found in *Table II.C: Surrounding Zones*.


Table II.C: Surrounding Zones

Direction	Zone
North	RX-1 (Residence Zone)
South	SR (Suburban Ranch) Former C-1 (Commercial Zone) now RX-1 (Residence Zone)
East	RX-1 (Residence Zone)
West	C-1 (Commercial), R-1 (Residential)

In addition, both the HENP and the Rincon Southeast Subregional Plan designates the intersection of 22nd Street and Houghton Road for commercial use. The southeast corner (Assessor's Parcel # 136-09-012B) was rezoned to commercial in 2007, (C9-07-18). However due to the recent recession, the property has since reverted to its original zoning (See *Exhibit II.C: Zoning*).



Exhibit II.C: Zoning



LEGEND		Tucson Zoning	
	Site Boundary		O-3
	Parcels		RX-1
	150-Foot Radius		SR
			R-1
			C-1



0' 250' 500'
FILE NAME: zoning_6x8.mxd
SOURCE: Pima County GIS, 2016



D. Adjacent Parcels and Structures


Existing land uses on adjacent parcels within 150 feet of the subject property can be seen in *Table II.D: Existing Land Uses* and on *Exhibit II.D: Existing Land Uses*.

Table II.D: Existing Land Uses

Property	Vacant
North	One-Story Single-Family Residential
South	Vacant, One- and Two Story Single-Family Residential
East	One-Story Single-Family Residential
West	One-Story Commercial, One- and Two-Story Single-Family Residential,



Exhibit II.D: Existing Land Uses



LEGEND

- Site Boundary
- Subdivisions
- 150-Foot Radius
- Development Plans
- Parcels



FILE NAME: ex_cond_6x8.mxd
SOURCE: Pima County GIS, 2016



E. Park, Recreation and Open Space


According to the Pima Regional Trail System Master Plan (PRTSMP), there are several trails located within one mile of the Property: Hidden Hills, Estes Wash, and Houghton Road Greenways; Old Spanish Trail Path; Hidden Hills, Estes Wash, Coronado Ridge and Reyes Wash trails; Melpomene Way Alignment; Freeman/Del Este singletrack trails; Danforth trailhead and the Old Spanish Trail trailhead (See *Exhibit II.E: Recreation*).

The Houghton Road Greenway lies adjacent to the PAD and features a 10-foot regional multipath corridor with native plants and landscaping that maintains the scenic corridor. The Houghton Road Greenway will utilize water harvesting and incorporate wildlife-sensitive design.

Case Natural Resource Park is located within one mile of the Property. The 4.1-acre park features a parking lot, playground, shaded and unshaded picnic tables, barbecue grills, walking paths, and a butterfly/hummingbird garden.



Exhibit II.E: Recreation



LEGEND

- Site Boundary
- Jurisdictional Boundaries
- One Mile Radius
- Parks

TRAILS

- Path
- Greenway
- Singletrack Trail
- Trail

Trailhead



SCALE: 1" = 2000'
 FILE NAME: recreation.mxd
 SOURCE: Pima County GIS, 2016




F. Public, Educational, Community and Cultural Facilities

The Property is located within the Tucson Unified School District. As indicated on *Exhibit II.F: Community Facilities*, two public schools are located within one-mile of the Property: Dunham Elementary School and Soleng Tom Elementary School. Additionally, one charter school, Academy of Tucson High, is located within a one-mile radius of the Property.

The Miller-Golf Links Pima County Public Library is located approximately 1.3 miles southwest of the subject property. The nearest fire station is located at 250 South Harrison Road, just over one-mile northwest of the subject property. There is one police station located within the vicinity of the PAD. The City of Tucson Rincon Substation is located at 9670 East Golf Links Road, approximately 1.3 miles southwest of the Property.



Exhibit II.F: Community Facilities



LEGEND

Site	Fire Station	Public Schools
One-Mile Radius	Library	Charter Schools
	Police	

NORTH 0' 1,000' 2,000'

 SCALE: 1" = 2000'

 FILE NAME: schools_6x8.mxd

 SOURCE: Pima County GIS, 2016

THE PLANNING CENTER

a division of IPC Group, Inc.




G. Existing Drainage

As shown on *Exhibit II.G: Existing Drainage*, off-site flows are generated from the south, east, and north due to the slope of the existing grade contours. There are six off-site concentration points entering the Property. There are four calculated flows (OS1 through OS4) coming from the north and east. These flows have been calculated at 25 cfs from OS1, 8.3 cfs from OS2, 21 cfs from OS3, and 18 cfs from OS4. Additionally, two flows (OS5 and OS6) are coming from the south (north half of 22nd Street.) The calculated flow rate of OS5 is 5.6 cfs. The flow of OS6 consists of two portions: the flow coming from the area of 22nd Street with the calculated flow rate of 8.1 cfs, and the flow coming from the south of 22nd Street (L1) via a 36" RCP (after the 22nd Street improvement) with a calculated flow rate of 44 cfs. Thus, the total flow of OS5 and OS6 is approximately 52.1 cfs (See *Exhibit II.G: Existing Drainage*).

The on-site flows from the east to the west and then into 3-48" RCP culverts located approximately 420 ft. north of the intersection of 22nd Street and Houghton Road. The culverts run from east to west under Houghton Road and into the Este Wash. The 100-year existing conditions peak discharge for this Property is 116 cfs. The on-site drainage has been broken down into 5 drainage area's labeled DA1 thru DA5 and flows generated in accordance with PC-Hydro (See *Drainage Report submitted under a separate cover*).



Exhibit II.G: Existing Drainage



SEAL

EXPIRES 12-31-15

SUSTAINABILITY ENGINEERING GROUP

SEG

8330 E GILCHRIST DR #101, SCOTTSDALE, ARIZONA 85260
WWW.SEGSG.COM TEL 480.988.7226

fray's
FOOD & DRUG STORES
Fry's Food Stores of Arizona
500 South 68th Avenue, Suite A
TUCSON, AZ 85714
Phone (520) 867-1884
Fax (520) 867-1974

Kroger
The Kroger Co.
10251 East 5th Street, Suite A
TUCSON, AZ 85748
Phone (520) 715-5917
Fax (520) 715-5905

PROJECT:
FRY'S NEW STORE #642
10325 & 10395 E. 22ND STREET
TUCSON, AZ 85748

DATE: 7/22/2015

SCALE: PERMIT

JOB NO.: 141042

EXISTING CONDITIONS DRAINAGE AREA MAP

APPENDIX VIII

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND THE PROPERTY OF SUSTAINABILITY ENGINEERING GROUP, AND SHALL REMAIN THEIR PROPERTY. THE USE OF THIS DRAWING SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH IT WAS PREPARED AND PUBLICATION THEREOF IS EXPRESSLY LIMITED TO SUCH USE.



H. City of Tucson Ordinances

The Property is subject to the Scenic Overlay Zone and the City of Tucson Major Streets and Routes Plan.

I. Existing Infrastructure

The Property is an infill Property surrounded by existing infrastructure that has sufficient capacity for the proposed PAD development.

1. Electric

Tucson Electric Power services the Houghton/22nd area. There is existing electrical infrastructure in the form of an electrical box located on the south-central portion of the Property. In addition, electrical transmission lines are located along the perimeter of the Property in the Houghton Road and 22nd Street rights-of-way.

2. Sewer

The existing sewer network can be seen on *Exhibit II.1.3.a: Sewer Network*. The Property is tributary to the Tres Rios Water Reclamation Facility via the Tanque Verde Road Interceptor. Capacity is currently available for this Property in the public sewer line (G-88-038) downstream of 9585-05. The recently constructed Public Sewer Improvement Plans are included as *Appendix B*. The existing property owner recently constructed public sewer across Houghton Road to ensure connections for the subject property prior the Houghton Road widening. See also *Exhibit II.1.3.b: Pima County Wastewater Reclamation Wastewater Capacity Letter*.


3. Water

Per the Tucson Water Service Area Map, the Property is located within the Tucson Water obligated service area. Tucson Water will provide water service to the Property and has an assured water supply (AWS) designation from the State of Arizona Department of Water Resources (ADWR) (*See Exhibit II.1.4: Tucson Water Letter*).

In addition, in conjunction with the Houghton Road widening, a Preliminary Master Water Plan was submitted to and accepted by the City of Tucson Water Department New Development Unit in 2015, for substantial conformance with standard specifications and details (*See Appendix C*.)



Exhibit II.I.3.a: Sewer Network



LEGEND

- Site Boundary
- Existing Sewer Network
- Parcels
- Existing Manholes



NORTH 0' 150' 300'
FILE NAME: sewer_6x8.mxd
SOURCE: Pima County GIS, 2016



Exhibit II.I.3.b: Pima County Wastewater Reclamation Capacity Letter



JACKSON JENKINS
DIRECTOR

PH: (520) 724-6500
FAX: (520) 724-9635

May 5, 2016

Tim Craven
The Planning Center
110 S Church Ave., Ste. 6320
Tucson, Arizona 85701

Sewerage Capacity Investigation No. 2016-107 Type I

**RE: 22nd Street and Houghton Road Planned Area Development, Parcels 13338008J, 13338008F
Estimated Flow 13,154 gpd (ADWF).
P16WC00109**

Greetings:

The above referenced project is tributary to the Tres Rios Water Reclamation Facility via the Tanque Verde Interceptor.

Capacity is currently available for this project in the public sewer G-88-038, downstream from manhole 9585-05.

This letter is not a reservation or commitment of treatment or conveyance capacity for this project. It is not an approval of point and method of connection. It is an analysis of the system as of this date and valid for one year. Allocation of capacity is made by the Type III Capacity Response.

If further information is needed, please feel free to contact us at (520) 724-6642.

Reviewed by: Kurt Stemm, CEA Sr.



Exhibit II.I.4: Tucson Water Letter



CITY OF
TUCSON
TUCSON WATER
DEPARTMENT

April 21, 2016

Sustainability Engineering Group
8280 E. Gelding Dr., Ste #101
Scottsdale, AZ 85260

Attn: Matthew Miles

SUBJECT: Water Availability for project: Houghton and 22nd Frys, APN: 13338008F, 13338008J, Case #: WA1958, T-14, R-15, SEC-13, Lots: 99999999, Location Code: TUC, Total Area: 16.1ac Zoning: SR

WATER SUPPLY

Tucson Water will provide water service to this project based on the subject zoning of the above parcels. Tucson Water has an assured water supply (AWS) designation from the State of Arizona Department of Water Resources (ADWR). An AWS designation means Tucson Water has met the criteria established by ADWR for demonstration of a 100-year water supply – it does not mean that water service is currently available to the subject project.

WATER SERVICE

The approval of water meter applications is subject to the current availability of water service at the time an application is received. The developer shall be required to submit a water master plan identifying, but not limited to: 1) Water Use; 2) Fire Flow Requirements; 3) Offsite/Onsite Water Facilities; 4) Loops and Proposed Connection Points to Existing Water System; and 5) Easements/Common Areas.

Any specific area plan fees, protected main/facility fees and/or other needed facilities' cost, are to be paid by the developer. *If the existing water system is not capable of meeting the requirements of the proposed development, the developer shall be financially responsible for modifying or enhancing the existing water system to meet those needs.*

This letter shall be null and void two years from the date of issuance.

Issuance of this letter is not to be construed as agency approval of a water plan or as containing construction review comments relative to conflicts with existing water lines and the proposed development.

If you have any questions, please call New Development at 791-4718.

Sincerely,

Richard A. Sarti, P.E.
Engineering Manager
Tucson Water Department

RS:ka
CC:File



NEW DEVELOPMENT • P.O. BOX 27210 • TUCSON, AZ 85726-7210
(520) 791-4718 • FAX (520) 791-2501 • TDD (520) 791-2639 • www.tucsonaz.gov/water



1.53



J. Topography

The topography on the Property ranges from 2,832 feet at the western boundary to 2,866 feet at the southeastern corner of the property. There are no slopes greater than 15% located on the property (See *Exhibit II.J: Topography*).

The average cross slope of the parcel is 5.8%, as calculated by performing the following calculation:

$$\text{ACS} = \frac{I \times L \times 0.0023}{A}$$

Interval (I) = 2'

Total length of contours (L) = 20,496


Area (A) = 16.2 acres

$$\text{ACS} = \frac{2 \times 20,496 \times 0.0023}{16.2 \text{ acres}}$$

ACS = 5.8




Exhibit II.J: Topography



LEGEND

-  Site Boundary
-  2' Elevation Contours
-  Parcels



FILE NAME: topo_6x8.mxd
SOURCE: Pima County GIS, 2016



K. Vegetation and Wildlife

As shown on *Exhibit II.K: Vegetative Communities*, there are two vegetative communities and/or plant associations located on the Property: Sonoran Desert Scrub and Xeroriparian Class C.

1. Sonoran Desert Scrub

The Sonoran Desert Scrub community occupies approximately 12.6 acres of the Property. The plants species predominately consist of Creosote Bush (*Larrea tridentate*), Foothills Palo Verde (*Parkinsonia microphylla*), Velvet Mesquite (*Prosopis velutina*), Brittlebush (*Encelia farinose*), and Prickly Pear Cacti (*Opuntia engelmannii*). Plant density throughout much of the Property is medium to low, typical of upland scrub vegetation in the region.

2. Xeroriparian Class C

Pima County has mapped Xeroriparian C habitat delineated on-site (*See Exhibit II.K: Vegetative Communities*). However, the mapped boundary does not correspond to actual on-site conditions or the aerial photography. Some Xeroriparian habitat does exist within the 100-Year Floodplain on-site. The limits of the Xeroriparian habitat will be adjusted, based on an actual inventory of riparian habitat.


The Xeroriparian habitat consists of a mix of Whitethorn Acacia Trees (*Acacia constricta*), Foothills Palo Verde Trees (*Cercidium microphyllum*), Desert Hackberry Shrubs (*Celtis pallida*), and Velvet Mesquite Trees (*Prosopis velutina*). A number of Fish Hook Barrel Cacti (*Ferocactus wicklizenii*) also occur in the Xeroriparian area.

3. Arizona Game and Fish Department

As shown on *Exhibit II.K.3: Arizona Game and Fish Letter*, the Arizona Game and Fish Department's Online Environmental Review Tool indicates there are eight special status species that have been documented within a three-mile radius of the Property: Mexican Gray Wolf, Mexican Long-Tongued Bat, Yellow-billed Cuckoo, Sonoran Desert Tortoise, Reticulate Gila Monster, Lesser Long-nosed Bat, Stag-horn Cholla, Lowland Leopard Frog, and Tumamoc Globeberry.



Exhibit II.K: Vegetative Communities



LEGEND

- Site Boundary
- Washes

Vegetation

- Agriculture / Developed / Water / Bare Ground
- Sonoran Desertscrub
- Pima County Class C Xeroriparian Area



FILE NAME: veg_6x8.mxd
SOURCE: Pima County GIS, 2016



Exhibit II.K.3: Arizona Game and Fish Letter

Arizona Game and Fish Department
Project ID: HGIS-03320

project_report_bdu_01_18347_18739.pdf
Review Date: 3/28/2016 08:42:34 AM

Special Status Species and Special Areas Documented within 3 Miles of Project Vicinity

Scientific Name	Common Name	FWS	USFS	BLM	NPL	SGCN
Canis lupus baileyi	10J area Zone 2 for Mexican gray wolf	LE,XN				
Choeronycteris mexicana	Mexican Long-tongued Bat	SC	S	S		1C
Coccyzus americanus	Yellow-billed Cuckoo (Western DPS)	LT	S			1A
Gopherus morafkai	Sonoran Desert Tortoise	CCA	S			1A
Heloderma suspectum suspectum	Reticulate Gila Monster					1A
Leptonycteris curasoae yerbabuenae	Lesser Long-nosed Bat	LE				1A
Lithobates yavapaiensis	Lowland Leopard Frog	SC	S	S		1A
Opuntia versicolor	Stag-horn Cholla					SR
Tumamoca macedougalii	Tumamoc Globeberry		S	S		SR

Note: Status code definitions can be found at http://www.azgfd.gov/w_c/edits/hdms_status_definitions.shtml.

Species of Greatest Conservation Need
Predicted within Project Vicinity based on Predicted Range Models

Scientific Name	Common Name	FWS	USFS	BLM	NPL	SGCN
Aix sponsa	Wood Duck					1B
Amazilia violiceps	Violet-crowned Hummingbird		S			1B
Ammodramus savannarum perpallidus	Western Grasshopper Sparrow					1B
Ammospermophilus harrisi	Harris' Antelope Squirrel					1B
Anthus spragueii	Sprague's Pipit	C*				1A
Antrostomus ridgwayi	Buff-collared Nightjar		S			1B
Aquila chrysaetos	Golden Eagle	BGA		S		1B
Aspidoscelis stictogramma	Giant Spotted Whiptail	SC	S			1B
Athene cunicularia hypugaea	Western Burrowing Owl	SC	S	S		1B
Botaurus lentiginosus	American Bittern					1B
Buteo regalis	Ferruginous Hawk	SC		S		1B
Chilomeniscus stramineus	Variable Sandsnake					1B
Coccyzus americanus	Yellow-billed Cuckoo (Western DPS)	LT	S			1A
Colaptes chrysoides	Gilded Flicker			S		1B
Coluber bilineatus	Sonoran Whipsnake					1B
Corynorhinus townsendii pallescens	Pale Townsend's Big-eared Bat	SC	S	S		1B
Crotalus tigris	Tiger Rattlesnake					1B
Cynanthus latirostris	Broad-billed Hummingbird		S			1B
Cynomys ludovicianus	Black-tailed Prairie Dog	SC		S		1A
Dipodomys spectabilis	Banner-tailed Kangaroo Rat			S		1B
Eudema maculatum	Spotted Bat	SC	S	S		1B
Eumops perotis californicus	Greater Western Bonneted Bat	SC		S		1B
Falco peregrinus anatum	American Peregrine Falcon	SC	S	S		1A



L. Soils


Per data obtained during a soil survey of eastern Pima County performed in 2003 by the National Resource Conservation Service (NRCS), the soil type across the entire Property is classified as Palos Verdes-Jaynes Complex. The NRCS indicates that soils of this type are typically used for home sites and other urban development, as well as for recreation purposes.

M. Viewsheds and Visual Analysis

The viewsheds of the Catalina, Rincon and Santa Rita mountains are all visible throughout most of the Property. See *Exhibit II.M: Photo Key Map* and *Exhibit II.M.1: Site Photos* for views of the Property and for views looking from the Property to the adjacent properties. Viewsheds onto the subject property from surrounding parcels and arterial roadways varies from low to high. The PAD boundaries along the west and south are highly visible along the major arterials. The inner portions of the property vary from medium to low visibility due to the lower topography and vegetation in this area. Photos of the Property are shown below.




Exhibit II.M: Photo Key Map



LEGEND

-  Site Boundary
-  Parcels
-  Photo Location and Direction



FILE NAME: photokey_6x8.mxd
SOURCE: Pima County GIS, 2016



Exhibit II.M.1: Site Photos



Photo 1: View from the southeast Property corner looking northeast.



Photo 2: View from the southeast corner looking west along 22nd Street.



Photo 3: View from the southeast Property corner looking south.



Photo 4: View from south Property boundary looking south toward the 22nd Street and Barbara Drive.



Photo 5: View from south Property line looking north across the Property.



Photo 6: View looking from near the center of the Property toward the wash riparian area.



Exhibit II.M.1: Site Photos (Cont.)



Photo 7: View from the southwest Property corner looking toward the 22nd & Houghton intersection.



Photo 8: View from the southwest Property corner looking west.



Photo 9: View from the southwest Property corner looking north.



Photo 10: View from northwest Property corner looking northwest.



Photo 11: View from the northwest Property corner looking southeast across the site.



Photo 12: View along the north Property boundary looking north.



N. Cultural Sites

1. Arizona State Museum Letter

As shown in *Exhibit II.N: Arizona State Museum Archaeological Survey*, the Property has not been previously surveyed for archaeological resources. However, twenty-one survey projects have been conducted in support of commercial and residential development, road construction and improvements, and the installation and maintenance of subsurface gas and water lines within a one-mile radius of the subject property. One archaeological site has been identified within the one-mile radius of the Property; however, it is not crossed by the Property. The Arizona State Museum recommends that a qualified archaeological be consulted prior to ground disturbance.



Exhibit II.N: Arizona State Museum Archaeological Survey



Arizona State Museum
THE UNIVERSITY OF ARIZONA
 1013 E. UNIVERSITY BLVD.
 TUCSON, AZ 85721

ARCHAEOLOGICAL SITE RECORDS SEARCH

**This report documents the results of an archaeological site-records check.
It does not constitute a cultural resources clearance.*

Date: 4/7/2016

Requester Name: Lexy Wellott
Company: The Planning Center
Address: 110 S. Church St., Suite 6320
City State, Zip Code: Tucson, AZ, 85701
Phone / Email: 520-623-6146 / lwellott@azplanningcenter.com

Project Name and/or Number: BDU-01 **Project Description:** 22nd and Houghton Planned Area Development

Project Area Location: 133-38-008J, 133-38-008F **Legal Description:** T14S, R15E, S13

Search Results:

According to a search of the archaeological records retained at the Arizona State Museum (ASM), 21 survey projects have been conducted within a one-mile radius of the project area between 1980 and 2013. Previous survey work was conducted in support of commercial and residential development; road construction and improvements; and the installation and maintenance of subsurface gas and water lines. No portion of the project area has been previously surveyed. One archaeological site has been identified within a 1-mile radius of the project area; however, it is not crossed by the project area.

Sites in Project Area:

None are recorded; but the project area has not been previously surveyed.

Recommendations:

1. No portion of the proposed project area has been subject to an archaeological survey and there is a possibility for unidentified historic properties in the area. ASM recommends, but it is not required by ASM, that a qualified archaeological contractor be consulted before any ground disturbance begins. A list of archaeological contractors is available on the ASM website at: <http://www.statemuseum.arizona.edu/crservices/permits/index.shtml>.
2. Pursuant to *Arizona Revised Statutes §41-865 et seq.*, if any human remains or funerary objects are discovered during your project work, all work will stop within the area of the remains and Dr. Todd Pitezal, ASM assistant curator of archaeology, will be contacted immediately at (520) 621-4795.
3. City, county, or municipal governments may have requirements, therefore ASM recommends that the relevant jurisdiction(s) be consulted.


If you have any questions about the results of this records search, please contact me.

Sincerely,

Shannon Twilling, M.A.

Shannon D. Twilling, M.A.
 Research Specialist
 Archaeological Permits Office
 Arizona State Museum
 (520) 621-2096
 twilling@email.arizona.edu





22nd & Houghton Planned Area Development (PAD)

III. Planned Area Development Proposal

City of Tucson

A. Plan Overview

The 22nd and Houghton Planned Area Development (PAD) is proposed for a neighborhood-scaled shopping center. It is located at the intersection of two major arterial roadways. In accordance with the Houghton East Neighborhood Plan (HENP), the Property is designated for commercial use at this intersection. The principal tenant includes a proposal for a modern-version of the Fry's Food & Drug Store, two retail pads and an associated Fry's gas station. Fry's primary offerings are groceries and secondary offerings are pharmacy and health and beauty items typically found in drug stores. The building may feature an outdoor display area (see photos 1-3) and a pharmacy drive-through. Any outdoor display products must be within a vestibule with doors and shall remain open only during store operational hours. This new location anticipates offering additional amenities such as drive-through pharmacy with click list online ordering, a Sushi Island, an enhanced meat counter and deli, a large selection of organic produce, a Pan Asian bistro, a Starbucks, an outdoor seating and dining area, and apparel.



Photo 1: View of Fry's optional outdoor sales garage doors





Photo 2: View of typical optional interior outdoor sales area



Photo 3: View of typical optional interior outdoor sales area

As shown on *Exhibit III.A.1: Proposed Architectural Renderings*, *Exhibit III.A.2: Proposed Architectural Renderings with Vestibules* and *Exhibit III.A.3: Proposed Retail Architectural Renderings*, the architecture will be designed to provide visual interest consistent with the community's identity, character, and scale. Architectural treatment, similar to that provided to the front facade, shall be provided to the sides and rear of the building to mitigate any negative view from adjacent properties and/or streets and the buildings shall have exterior building materials and colors that are aesthetically pleasing and compatible with materials and colors that are used in adjoining neighborhoods. The uses envisioned for the retail pads include but are not limited to: restaurant, coffee shop, and personal service.



Exhibit III.A.1: Proposed Architectural Renderings



FRY'S WEST ELEVATION (HOUGHTON ROAD)
SCALE: 1/8" = 1'-0", TYP.



FRY'S SOUTH ELEVATION
SCALE: 1/8" = 1'-0", TYP.



FRY'S EAST ELEVATION
SCALE: 1/8" = 1'-0", TYP.



FRY'S NORTH ELEVATION
SCALE: 1/8" = 1'-0", TYP.

PROVISIONARY
DRAWING
12-01-2016



507 E. 400th St.
Orem, UT 84057
801.225.1600
www.stickleby.com

DRAWN	JOM
DATE	12/01/2016
SCALE	
JOB #	
SHEET	



Exhibit III.A.2: Proposed Architectural Rendering with Vestibules



FRY'S WEST ELEVATION (HOUGHTON ROAD)
SCALE: 1/16" = 1'-0", TYP.



FRY'S SOUTH ELEVATION
SCALE: 1/16" = 1'-0", TYP.



FRY'S EAST ELEVATION
SCALE: 1/16" = 1'-0", TYP.



FRY'S NORTH ELEVATION
SCALE: 1/16" = 1'-0", TYP.

PRELIMINARY
DRAWING
10-22-2016

Stickley
design group architects
architecture • interior design • planning

501 N. AZUL WAY
TUCSON, ARIZONA 85748
520-290-0263 P.H.
520-891-1742 M.O.B.I.I.
www.stickleydesign.com

DRAWN	JDM
DATE	10/23/2016
SCALE	
JOB #	



B. Proposed Land Uses

The 22nd and Houghton PAD proposes a single zoning district based on a modified C-1 Zone to allow for commercial development. *Exhibit III.B.1: Conceptual Land Use Plan identifies* the two designations on the property: open space and commercial. *Exhibit III.B.2: Illustrative Site Plan depicts* a site plan primarily for illustrative purposes only. There are a great number of variations of that plan that could ultimately be utilized on this Property. The plan is intended to show the overall concept for the Property as a means of providing direction for traffic and civil engineering studies, relationship of possible structures to surrounding neighborhoods, the ratio of necessary parking and possible on-site traffic circulation. It is not to be considered an actual proposed development plan.

This document provides regulations relating to uses, physical character and intensity of development on the Property. Permitted uses for the entire property shall include all uses that are listed as permitted or as special exception uses in the C-1 zone of the City of Tucson Unified Development Code (UDC), except as modified in this document. Where the PAD varies from the UDC or other relevant City standards, the PAD shall control. Where the PAD is silent, the UDC provisions for the C-1 zone and other relevant city standards shall control. All development on the Property must be in compliance with the PAD upon full build-out.

1. Commercial

As identified on *Exhibit III.B.1: Conceptual Land Use Plan and Exhibit III.B.2. Illustrative Site Plan*, the PAD will feature a principal tenant (Fry's Food and Drug Store) and secondary tenants located in two separate building pads. These pads may include retail and restaurant uses, including but not limited to a drive-through window. A fueling station with an accompanying kiosk and outdoor display area associated with the Fry's Food and Drug Store is also proposed.

2. Open Space


As identified on *Exhibit III.B.1*, approximately 4.1 acres will be set aside as open space around the perimeter of the property, with the majority interfacing between the existing single family residential and the subject property. The goal of the open space areas within the PAD is to create a visual screen between the single-family residential properties and the subject property as well as create visual diversity and interest and/or passive recreation opportunities. The open space will create a continuous area of natural vegetation around the Property with at least 20% of the site (3.2 AC) situated in a natural buffer between the existing neighborhood to the north and east of the site. The remainder of the open space (between 0.9 and 1.3 acres) will be provided along the western boundary of the site (adjacent to the Houghton Road Greenway) and the 22nd Street frontage, creating a total open space of a minimum of 25% of the site. This area will be revegetated using a mix of native and low water use, regionally appropriate plants, and will be adjacent to the newly replanted areas within the recently completed Houghton Road improvements. In addition to the aesthetic benefits of softening, screening and beautifying the edge of the property, this area completes a continuous



open space ring around the property, interrupted only minimally with necessary access points along Houghton and 22nd Street.



Exhibit III.B.1: Conceptual Land Use Plan



LEGEND

- SHOPPING CENTER DEVELOPMENT AREA = 11.7 AC
- TOTAL CONSOLIDATED OPEN SPACE = 4.1 AC (MINIMUM 25% OF TOTAL SITE AREA)
- TOTAL OPEN SPACE PROVIDED IN RIGHT-OF-WAY = 0.99 AC

NOTES:

SITE AREA = 16.2 ACRES

*** AS SHOWN ABOVE, 0.9 ACRES OF COMMUNITY COMMERCIAL OPEN SPACE SATISFIES THE MINIMUM 25% OPEN SPACE REQUIREMENT PER THE HOUGHTON EAST NEIGHBORHOOD PLAN. ADDITIONAL OPEN SPACE (UP TO 1.3 ACRES) MAY BE PROVIDED DURING FINAL DEVELOPMENT PLAN PROCESS.

THE INTENTION OF THIS EXHIBIT IS TO ILLUSTRATIVELY DEMONSTRATE HOW THE SITE MEETS THE OPEN SPACE REQUIREMENT. ACTUAL FIGURES AND BOUNDARIES WILL BE DETERMINED DURING THE FINAL DEVELOPMENT PLAN PROCESS.




Exhibit III.B. 2: Illustrative Site Plan



NOTES:
Total Site Acreage = 16.2

THIS EXHIBIT WAS CREATED USING THE MOST RECENT AVAILABLE BOUNDARIES, ROAD ALIGNMENT, AND EASEMENT DATA PROVIDED BY THE DIFFERENT GOVERNMENTAL ENTITIES AND ENGINEERING FIRMS AND IS FOR PLANNING PURPOSES ONLY. FINAL AREA TOTALS BASED ON ENGINEERED DATA MAY VARY FROM THOSE SHOWN ON THIS EXHIBIT.



C. Development Standards

For the purpose of setback requirements and other development standards, the PAD shall be considered as a single parcel regardless of the ultimate parcel configuration within the PAD area. All new development within the PAD shall conform to applicable building, fire and other applicable safety standards. The commercial uses shall be based upon Section 4.8-4: Permitted Uses- Commercial and Mixed Use Zones of the Unified Development Code for C-1 uses.

1. Permitted Uses

- a. Agricultural Land Use Group
 1. Community Garden, subject to: Section 4.9.2.B
 2. Urban Farm, subject to: Section 4.9.2.E
- b. Civic Use Group
 1. Civic Assembly
 2. Cultural Use (Government Owned and Operated Only)
 3. Educational Use: Elementary and Secondary Schools, subject to: Sec. 4.9.3.D.1 – 7 and 4.9.13.O
 4. Educational Use: Postsecondary Institution, subject to: Sec. 4.9.3.E and 4.9.13.O
 5. Educational Use: Instructional School, subject to: Sec. 4.9.13.O
 6. Membership Organization
 - o Postal Service (government owned and operated only)
 7. Protective Service (government owned and operated only)
 8. Religious Use, subject to: Sec. 4.9.13.O
- c. Commercial Services Use Group
 1. Administrative and Professional Office, subject to: Sec. 4.9.13.O
 2. Animal Service, subject to: Sec 4.9.4.D.1, 2, 3, & 4 and 4.9.13.O
 3. Artisan Residence, subject to: Sec. 4.9.4.E.1, .2, .3, .4, & .5 and 4.9.13.O
 4. Automotive – Minor Service and Repair, subject to: Section 4.9.4.F.2, 3, 4 & 5
 5. Commercial Recreation, subject to: Sec. 4.9.13.O
 6. Communications, subject to: 4.9.13.O and 4.9.4.I.2, .3, .4a or .4b
 - o All components and wires shall be integrated into the building design with limited exposure
 - o Antennas and appurtenances shall not exceed:
 - 4 feet above the maximum building height of 26 feet for Principal tenant; and
 - 6 feet above the maximum building height of 20 feet for all other retail buildings.
 7. Day Care, subject to: Sec. 4.9.13.O
 8. Entertainment, subject to: Sec 4.9.4.C.3 and 4.9.13.O
 9. Financial Service, subject to: Sec. 4.9.4.L.1 & 3 and 4.9.4.13.O
 10. Food Service with a Microbrewery as an accessory use to a Food Service, subject to: Sec 4.9.4.M.1 and 4.9.4.13.O



- No smoking patios or amplified music within 150' of the north or east property lines
- 11. Medical Service – Extended Health Care, subject to: Sec. 4.9.13.O
- 12. Medical Service – Major, subject to: Sec. 4.9.13.O
- 13. Medical Service – Outpatient, subject to: Sec 4.9.4.O.2 & 4.9.13.O
- 14. Parking
- 15. Personal Service, subject to: Sec 4.9.4.T.1 and 4.9.13.O
- 16. Research and Product Development, subject to: Sec. 4.9.13.O
- 17. Technical Service, subject to: Sec 4.9.W.1 and 4.9.13.O
- 18. Trade Service and Repair, Minor, subject to: Sec 4.9.4.X.2 and 4.9.13.O
- 19. Traveler’s Accommodation, Lodging with Alcoholic Beverage Service as an accessory use, subject to: Sec. 4.9.13.O
- d. Industrial Use Group
 - 1. Household goods donation center, subject to: 4.9.5.G.2, 6- 12, 4.9.13.A.2, B-D, and 4.9.13.O
- e. Recreation Use Group
 - 1. Parks and Recreation
- f. Residential Use Group, Family Dwelling:
 - 1. Duplex
 - 2. Single Family Detached
 - 3. Home Occupation as an accessory use to any permitted Family Dwelling, subject to: Sec. 4.9.7.D
 - 4. Flexible Lot Development, subject to: 8.7.3
 - 5. Group Dwelling
 - 6. Residential Care Services, Adult Care or Physical and Behavioral Health Unlimited Number of Residents, subject to: Sec. 4.9.7.J.3.d, .4, & .8 and 4.9.13.O
 - 7. Residential Care Services, Rehabilitation Service - Children’s Facility (maximum 10 residents), subject to: Sec. 4.9.7.J.1, 3.a, .4 & 4.9.13.O
- g. Retail Trade Use Group
 - 1. Food and Beverage Sales, subject to: Sec 4.9.9.A
 - Outdoor sales and display of products will be conducted within the vestibule
 - Hours of operation will be limited from 6 am to 12 midnight.
 - 2. General Merchandise Sales, subject to: Sec 4.9.9.B.1
 - Outdoor sales and display of products will be conducted within the vestibule
 - Outdoor sales are permitted within service station area.
 - Hours of operation will be limited from 6 am to 12 midnight.
 - The Property is limited to a maximum of 12 fuel dispensing locations.
 - Hours of operation with a manned employee for the fuel dispensing station is from 6 am to 12 midnight. Self-service at the individual pump locations will be open 24 hours.
 - Outdoor patio dining
 - 3. Seasonal Sales and Farmers Markets as an accessory use to any permitted principal use in every land use group, subject to: Sec. 4.9.9.A. 12.a-e



- h. Storage Use Group
 - 1. Hazard Material Storage as an accessory use to any permitted principal use in every land use group, subject to: Sec. 4.9.11.A.1, .5, &.9 and 4.9.13.O
 - 2. Personal Storage, subject to: Sec. 4.9.10.C.and 4.9.13.O
- i. Utilities Use Group
 - 1. Distribution System, subject to: Sec. 4.9.11.A.1, .5, & .9 & 4.9.13.O
 - 2. Renewable Energy Generation, subject to: Sec. 4.9.11.B and 4.9.13.O
- j. Wholesaling Use Group
 - 1. Business Equipment Supply and Wholesaling, subject to: Sec 4.9.13.P
 - 2. Food and Beverage Wholesaling subject to: Sec 4.9.13.P

2. Prohibited Uses

a. Prohibited Uses

The following primary land uses shall be prohibited within the PAD.

- 1. Adult Rehabilitation
- 2. Cemetery
- 3. Golf Course
- 4. Large Retail Establishment
- 5. Shelter Care
- 6. Stand-Alone Wireless Communication Towers
- 7. Multifamily Development

3. Open Space Permitted Uses

Typical uses include, but not limited to, unimproved land, that is set aside, dedicated, or reserved in perpetuity for public or private enjoyment. The permitted uses may also include but not limited to the following uses. All disturbance associated with these uses must be revegetated in accordance with *Section III.F: Conservation Open Space*.

- a. Retaining Walls
- b. Screening Walls
- c. Revegetation
- d. Riparian Mitigation
- e. Recreation Use Group
 - 1. Parks and Recreation
 - 2. Trails
 - 3. Open Space



D. Development Standards

1. Property Development

Table III.D.1: Development Area Standards

	Non-Residential
Minimum Site Area	none
Maximum FAR	none
Maximum Lot Coverage	none
Minimum Perimeter Yard	<ul style="list-style-type: none"> • Minimum 100 feet adjacent to north boundary • Minimum 100 feet adjacent to east boundary • 3 times the height of building exterior wall adjacent to Houghton Road right-of-way line • 40 feet adjacent to 22nd Street existing right-of-way line
Screening Requirements	<ul style="list-style-type: none"> • A 6- to 8-foot masonry wall*, wrought iron fence, or combination of masonry and wrought iron fence will be installed along the north and east property boundaries as selected by each adjacent property owner along their specific individual boundary and the PAD. <p>*Design subject to DRC approval.</p>
Minimum Building Separation	Per Building Code

2. Building Height Standards

The maximum building height for the principal tenant (grocery store) is 26 feet to the top of the roofline with ultimate height of 30 feet to top of parapet for ornamental features. All other retail buildings proposed on-site will be limited to 20 feet to the top of the roofline, with an ultimate height of 30 feet for ornamental features, functional elements and 26 feet for mechanical features.

3. Parking Standards

The project will be parked in accordance with UDC requirements, Section 7.4.4. Required Number of Motor Vehicle Parking Spaces and Section 7.4.4.a for Mixed Use Development. The total number of required spaces for mixed use development is 90% of the sum of the amount required for each separate principal use in Section 7.4.4.B. The square footage of Entertainment, Food Service (i.e., restaurants), and/or Alcoholic Beverage Service (i.e., bars) uses may not be included in the calculation for multiple or mixed use parking requirements. Vehicular parking spaces are not required for patio square footage, such as outdoor seating, farmer’s markets and other outdoor retail displays. The developer shall report to the Planning and Development Services Director the ability to use cool pavement techniques or other heat island mitigation



best practices. If determined that the inclusion of cool pavement techniques and other heat island mitigation best practices are cost prohibitive for the entire site, the acting PDSO director shall determine the portions of the site to be retrofitted that will yield the most benefit for pedestrians.

Vehicle use areas shall be constructed utilizing materials and construction techniques in accordance with recommendations of the geotechnical engineer and concurrence from City of Tucson. Per Figure 7.4.6-A of the UDC, the minimum two-way PAAL shall be 24 feet wide.

Accessible parking will be provided in accordance with the requirements noted in the 2012 IBC Chapter 11 and the ICC A117.1-2009. Accessible spaces and “Van Accessible” spaces will connect to the accessible route as required by ICC A117.1-2009 Edition. Newly constructed and modified sidewalks, detectable warnings and curb ramps will comply with accessibility requirements as required.

4. Scenic Route Standards

Houghton Road is designated as a Scenic Route. The following provisions of the Scenic Corridor Zone (SCZ) apply to any portion of all real properties or parcels that are within four hundred (400) feet of the future right-of-way line of Houghton Road. These provisions supersede the provisions identified in Article 5, Section 5.3 Scenic Corridor Zone of the Unified Development Code and Section 5.3.11.

a. Preservation and Reestablishment of Vegetation

- i. A 30-foot wide buffer adjacent to the MS&R right-of-way line of Houghton Road is proposed for the purposes of this Scenic Corridor Zone. This 30-foot-wide buffer is proposed in addition to the 10-foot multi-use path and landscape buffer within the ROW in accordance with the right-of-way improvements along Houghton Road as shown on *Exhibit III.B.2: Illustrative Site Plan*. Additional plants indigenous to the Property will be added to this area. The proposed Riparian Mitigation Plan will occur along this scenic buffer area as the priority area (approximately 0.4 acres), as this area will contain drainage.
- ii. Modifications to the existing drainageway within the SCZ may occur in accordance with the City of Tucson Floodplain Ordinance.

b. Structure Height

In accordance with SCZ requirements, the maximum height of a structure is one-third the distance of the structure from the Houghton right-of-way line not to exceed a 30-foot building height. The building heights proposed along Houghton Road are a maximum of 20-feet.



5. Loading

The principal tenant (grocery store) loading area will be depressed 4-feet and screened with a 9-foot wall for a total 13-foot screen. Once the truck enters the loading dock, the door to the dock opens and then the product is unloaded inside of the loading dock. All other loading areas will be screened in accordance with Section 7.6 of the UDC standards, Landscaping and Screening.

Deliveries shall be prohibited between 12:00 am and 6:00 am. All delivery trucks shall turn off back up alarms during deliveries. If the Occupational Safety and Health Administration provisions require back up alarms be on, an acoustical analysis shall be performed to determine if mitigation measures are required. If mitigation measures are deemed necessary, a mitigation plan shall be established and approved by the DRC and the acting City of Tucson Planning and Development Services director. All truck idling is prohibited within 300 feet of residential properties. Trucks shall not be left idling between the hours of 6:00 pm and 6:00 am. Delivery trucks are required to automatically turn off after two minutes of idling.

6. Solid Waste Disposal

All required Solid Waste and Recycle materials collection and storage shall be located and screened, to allow for safe access and maneuverability within the development. Enclosures for the storage of waste containers shall be designed in accordance with the Unified Development Code, Section 7.15: for solid waste and recycle disposal collection and storage. The setback for these facilities from existing residential shall be a minimum of 50 feet from the northern and eastern property lines. Trash pickup shall be limited to between 6:00 am and 12:00 am.

7. Hours of Operation

The Property is subject to hours of operation limited to 6 am to 12 am.

8. Lighting & Security

Lighting will be installed in accordance with the City of Tucson Dark Sky Ordinance. It will be downward directed with zero bleed off onto adjacent properties. Parking lot lighting is proposed for a maximum 25 feet in height. At the rear of the grocery store, lights will be installed as low as possible, preferably facing downward within the proposed rear walls, providing the minimal lighting necessary for safety while minimizing the impact on the adjacent homes. A light dimming plan shall be approved by the Design Review Committee to ensure the site is appropriately lit while maintaining compliance with the Dark Skies Ordinance and minimizing visual impacts. An electronic security monitoring system for the public parking areas will be incorporated on the site.

9. Walls

Perimeter walls are allowed up to 8 feet without additional approvals. The developer will work with the Saguaro National Park DRC representative to design the wall to balance wildlife movement opportunities with the surrounding property owners' desire for privacy and security.



The developer shall report to the PDSO director the ability to add a second perimeter wall along the edge of the proposed grading limits of the project separating the open area and developed areas along the north and east sides. The requested walls shall be built on top of the proposed retaining walls and/or grading edge. Said walls shall be between 6' and 8' high measured from the lowest finished grade of the retaining walls or finished grade of the proposed walls. If it is the determination of the PDSO director that the cost of the added walls is prohibitive, the walls shall be installed only along portions of the site that offer the most protection to avoid negative interaction of wildlife and users of the development.

E. Drainage Plan

1. Response to Hydrologic Characteristics


The proposed land uses will include impervious surfaces associated with buildings, parking areas, and access lanes, while providing open space in the form of landscape areas, water harvesting basins, and natural areas. Since the Property is over an acre in size and proposing a commercial use, both on-site detention and retention will be required to reduce the developed condition volumes to at, or below, the existing condition rate volumes for the design storms.

The grading of the Property will direct runoff overland within the Property and toward curb cuts around the perimeter of the developments paved drives or parking areas outletting to the proposed diversion channels and/or to low points within the parking field to catch basins. Catch basins will collect the runoff and convey the storm water via an underground storm pipe system to proposed underground retention areas. Proposed retention will be the underground system (*See Exhibit III.E: Preliminary Grading and Drainage Plan*).

The water harvesting techniques will include: directing surface flow from the parking areas into the landscaping areas, using structures to capture runoff for later use, dispersing run-off into the soils by increasing the amount of exposed surface area and constructing French drains, utilizing mulch to maximum extent possible to reduce evaporation and retain moisture in the soil. Decomposed granite (DG) is prohibited in water harvesting areas due to its ability to clog soil pores and reduce infiltration rates. The use of drywells may be added to the water harvesting techniques if needed to obtain required drain down times of 12 to 24 hours. A drainage report has been submitted under a separate cover.



Exhibit III.E: Preliminary Grading & Drainage Plan



SUSTAINABILITY ENGINEERING GROUP
SEG
8200 E GILDING DR #101 SCOTTSDALE, ARIZONA 85260
WWW.A2SEEG.COM TEL: 480.988.7208

fray's
Fry's Food Stores of Arizona
10325 & 10395 E 22ND STREET
TUCSON, AZ 85748
Phone: (520) 997-1884
Fax: (520) 715-5805

Kroger Co.
The Kroger Co.
10325 & 10395 E 22ND STREET
TUCSON, AZ 85748
Phone: (520) 715-5817
Fax: (520) 715-5805

PROJECT: FRY'S NEW STORE #642
LOCATION: HOUGHTON ROAD & 22ND STREET, TUCSON, AZ 85748

DESIGNED BY: [Signature]
CHECKED BY: [Signature]
SCALE: 1" = 50'

DATE: 10-05-2016
SHEET NO.: C3.00

REVISIONS:

NO.	DATE	DESCRIPTION
1		
2		
3		
4		

JOB NO.: 141042
SHEET TITLE: PRELIMINARY GRADING & DRAINAGE PLAN

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND THE PROPERTY OF SUSTAINABILITY ENGINEERING GROUP. AND SHALL REMAIN THEIR PROPERTY. THE USE OF THIS DRAWING SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH IT WAS PREPARED AND PUBLICATION THEREOF IS EXPRESSLY LIMITED TO SUCH USE.



F. Open Space

1. Open Space Development Standards

A minimum of 20% of the Property as identified on *Exhibit III.B.1 and Exhibit III.B.2* will be preserved as consolidated open space, with a target of 25-28% of the site when the buffers adjacent to the Houghton and 22nd Street frontages are included. Generally, the open space along the north and east property boundaries, representing 20% of the site, will remain natural, with some minor exceptions for disturbance required for wall installation. Other open space along the street frontages will be revegetated to recreate a natural state.

- Per neighborhood input, some of the open space areas along the north and eastern borders may be supplemented with additional vegetation to provide additional screening between the project site and adjoining properties. This will also be a receiving area for mitigation plantings.
- A masonry wall up to 8' high will be installed along the north and east property boundaries.
- Areas graded due to installation of screening walls and retaining walls will be revegetated using native and low water use, regionally adapted plants.
- Water harvesting and retention will be incorporated to the greatest extent feasible without materially impacting vegetation that is intended to remain in place.
- Native and low water use, regionally adapted plants will be utilized throughout the development, including within bufferyards and parking lot islands.
- The developer shall establish a plan with consultation from Saguaro National Park to reduce, to the degree practical, harmful interactions between staff and functions of the development and surrounding wildlife.

2. Riparian Standards

This section shall modify Technical Standards 4.02.0.0, Floodplain, Wash and Environmental Resource Zone (ERZ) Standard to achieve the intent expressed within the PAD. The specific sections include, but are not limited to the following:

- 4-02.2.5.A - Development Restrictions. Impacts as shown in the PAD are allowed.
- 4.04.2.5.B –Environmental Resource Report. Determination of mitigation requirements shall be based on a modified Environmental Resource Report process (to be agreed upon by City of Tucson staff and the developer). The modified process will at a minimum include on-site evaluation (quantity and quality) of the areas of Pima County Xeroriparian habitat (coinciding with the 100-year Floodplain) that will be disturbed.
- 4-02.3.0 - Review (No SAC or STAC Review). The PAD Review process shall serve as the review for the riparian mitigations plans.
- The Property shall be permitted to impact existing Regulated Areas and Protected Riparian Area (PRA) as needed and be allowed to provide



mitigation for impacts to the Regulated Area and PRA on-site. On-site mitigation areas may be located within the Open Space.

3. Riparian Resources

The Property contains 100-year floodplain and Xeroriparian area (*See Exhibit III.F.3.a Riparian Resources*).


The 100-year floodplain begins near the center of the Property and flows toward Houghton Road, ending at the culvert under the road. As shown on Exhibit III.F, the Xeroriparian habitat is found near the Houghton Road culvert, due to the pooling of water near the roadway. A plant inventory, per the Floodplain, Wash, and ERZ Standard of the Technical Manual was conducted on June 2, 2016. The actual limits of the Xeroriparian habitat, per the plant inventory, are shown on *Exhibit III.F.3.a*. The actual Xeroriparian habitat area is approximately 0.9 acres in size.

As shown on *Exhibit III.F.3.b*, the proposed Riparian Mitigation Plan will contain approximately 0.9 acres of mitigation area. Mitigation will occur along Houghton Road as the priority area (approximately 0.4 acres), as this area will contain drainage areas. Any additional mitigation will occur within the open space on the north side of the Property (second priority area, approximately 0.5 acres).

These mitigation areas will serve a dual purpose. They will maintain the riparian nature of the current existing riparian area. They will also provide additional landscape buffering and visual enhancement along Houghton Road and adjacent to existing properties to the north.



Exhibit III.F.3.a: Riparian Resources



- 100-YEAR FLOODPLAIN
- EXISTING PIMA COUNTY XERORIPARIAN "C"
- 100-YEAR FLOODPLAIN WITH LIMITS OVER 100 CFS
- INVENTORY RIPARIAN PLANT
- ACTUAL RIPARIAN AREA
- PAD BOUNDARY

THIS EXHIBIT WAS CREATED USING THE MOST RECENT AVAILABLE BOUNDARIES, ROAD ALIGNMENT, AND EASEMENT DATA PROVIDED BY THE DIFFERENT GOVERNMENTAL ENTITIES AND ENGINEERING FIRMS AND IS FOR PLANNING PURPOSES ONLY. FINAL AREA TOTALS BASED ON ENGINEERED DATA MAY VARY FROM THOSE SHOWN ON THIS EXHIBIT.


0' 50' 100' NORTH

PROJECT:BDU-01 DATE:08/03/16
FILE NAME:BDU-01-RIPARIAN_EXHIBIT_080316.DWG

THE PLANNING CENTER
a division of TPC Group, Inc.
1105 Church St. Suite 6320 Tucson AZ 85701



Exhibit III.F.3.b: Riparian Mitigation Plan



LEGEND	
	RIPARIAN MITIGATION AREA (1ST PRIORITY): 18,000 SF
	RIPARIAN MITIGATION AREA (2ND PRIORITY): 22,000 SF

CREATED USING THE MOST RECENT AERIAL, ROAD ALIGNMENT, AND EASEMENT DATA. TOTALS BASED ON ENGINEERED DATA. SEE SHOWN ON THIS EXHIBIT.
 PROJECT: BDU-01 DATE: 07/13/16
 FILE NAME: BDU-01-RIPARIAN_080216.DWG



G. Landscape Program

1. Streetscape

The Property is surrounded by two major public roadways, Houghton Road and 22nd Street. As shown on *Exhibit III.G.: Landscape Border Plan*, 30-foot wide scenic corridor landscape borders will be provided adjacent to the Houghton Road scenic route. The 30-foot landscape border will be supplemented with additional native and low water use plants as well as riparian mitigation. A 10-foot wide landscape border will be provided along PAD boundary along 22nd Street. A 30-inch screen will be located along all parking areas.

2. Parking Area & Pedestrian Path Landscape

The landscape program for parking area landscape shall adhere to the following requirements:

- Pedestrian Paths from Houghton Road should shade at least 65 to 70% of the sidewalks/paths during the major part of the day with canopy trees or other shading devices
- Parking Areas
 - Tree Quantities: (1) tree shall be provided for every (4) parking spaces.
 - Tree Species: Medium size trees of native or low water use species, such as Palo Verdes, Mesquites, Hybrids or similar species shall be used.
- In accordance with UDC 7.6.6 such that all hard surfaces drain towards minimum 6" to 9" depressed water harvesting or retention areas

3. Landscape/Screening borders adjacent to residential uses

The PAD borders the Rancho Del Este residential subdivision to the east and north of the Property. There are no existing screens along most of these boundaries. A large area of open space will be provided along both boundaries. The east boundary consists of a 60 to 95-foot open space borders and the north boundary consists of a 40 to 110-foot open space border. Screening from existing residential areas will be accomplished with an 8-foot screen walls along the north and east boundary with openings for wildlife movement. The 40 to 110-foot landscape borders along these two boundaries will be revegetated with planted with trees, shrubs, and accent plants to efficiently screen the property from adjacent uses as well as provide for riparian mitigation.



Exhibit III.G: Landscape Borders



BRENTWOOD HOUGHTON & 22ND

NOTES:
 TOTAL OPEN SPACE = 4.1 AC
 TOTAL NEIGHBORHOOD SHOPPING CENTER = 12.1 AC
 TOTAL ACREAGE = 16.2 AC

THIS EXHIBIT WAS CREATED USING THE MOST RECENT AVAILABLE BOUNDARIES, ROAD ALIGNMENT, AND CASPERMENT DATA PROVIDED BY THE DIFFERENT GOVERNMENTAL ENTITIES AND ENGINEERING FIRMS AND IS FOR PLANNING PURPOSES ONLY. FINAL AREA TOTALS BASED ON ENGINEERED DATA MAY VARY FROM THOSE SHOWN ON THIS EXHIBIT.

0' 50' 100' NCP91
 PROJECT: 20U-01 DATE: 07/28/16
 FILE NAME: 141042C05.DWG



H. Circulation Plan

1. Access Points

As shown on Exhibit III.H on page 66, primary access to the Property will be provided by Houghton Road and 22nd Street. There are four proposed access driveways to the proposed development. Access #1 and Access #2 are located on Houghton Road, while the other three access driveways Access #3, and Access #4 are proposed to be located off 22nd Street. The first proposed access, Access #1, will allow right and left turns into the development from Houghton Road, but westbound vehicles will only be allowed to make a right out of the property. A left turn lane and separate northbound right turn lane are proposed for this access. Access #2 is proposed to be a right in/right out access only. A separate northbound right turn lane is proposed for this access, that will be shared with a bus bay per the City of Tucson planned improvements to Houghton Road. Of the three proposed accesses onto 22nd Street, Access #3 is also proposed to be a right in/right out access with a dedicated westbound right turn lane, while Access #4 is proposed to be full access driveways with an eastbound left turn lane and a separate westbound right turn lane.

2. Planned Improvements

Houghton Road and 22nd Street were recently improved. Improvement plans included Houghton Road widening to become a 6-lane roadway with a divided median in the has three thru lanes, two left-turn lanes and a separate right turn lane in both the northbound and southbound directions. 22nd Street was also improved at the intersection with Houghton Road to have one thru lane, two left turn lanes and a separate right turn lane in both eastbound and westbound directions. In addition, there is a proposed bus shelter pad location within their planned right-turn lane along Houghton Road. Sun Tran service currently does not serve this section of Houghton Road, but it is planned for a bus pullout at the northeast corner of 22nd and Houghton. If the pullout is modified or removed due to future construction, an alternative bus pullout area (shared right-turn lane) and shelter pad will be required at the time of development plan. The City of Tucson Department of Transportation has placed a five-year moratorium for all new cuts along Houghton Road and at the intersection of Houghton Road and 22nd Street. However, limited permission has been granted from the Department of Engineering (refer to *Appendix D: Houghton Road and 22nd Street Intersection Future Modification Letter*) allowing the developer to make necessary curb cuts to access the site prior to the expiration of the five-year moratorium period.

3. Traffic Volumes

A Traffic Impact Analysis generated by Stantec has been submitted under a separate cover. *Table III.H.3* identifies the trip generation provided by this report for the PAD development.



Table III.H.3: Proposed Use-Trip Generation

ITE Land Use code	Type		24-hour Two Way Volume	Peak AM- In	Peak AM- Out	Peak PM- In	Peak PM- Out
850	Supermarket	96	11655	240	147	551	530
826	Specialty Retail Center	10	443	0	0	12	15
944	Gasoline Service Station	10	1686	62	60	69	69
934	Fast Food Restaurant with Drive through	4.2	2084	97	93	71	66
Total			15868	400	300	704	680
Internal Trip Reduction			2380	60	45	106	102
Grand Total			13488	340	255	598	579

Source: Stantec, 2016

4. Level of Service

The signalized intersection of 22nd Street and Houghton Road currently functions at a Level of Service (LOS) B under the existing conditions and lane configuration. The City of Tucson is currently improving Houghton Road, including the intersection with 22nd Street. These improvements will be completed before the 2018 Full Build-Out Conditions and the new geometrics were used to model Background and Horizon Conditions. With the improved intersection and the addition of the 22nd Street and Houghton Road PAD Development, the 22nd Street and Houghton Road intersection will continue to function at a LOS B, with minor differences in delay times to the individual movements.

5. Pedestrian Circulation

The proposed on-site pedestrian connections provide an amenity for future users of the PAD. Pedestrian multi-use trails along Houghton Road, public sidewalks, bike routes and pedestrian walkways will create an interconnected system to the various uses within the site. The Property shall provide pedestrian accessibility, safety, and convenience to reduce traffic impacts and enable the development to project a friendly, inviting place. The main interior pedestrian walkway connecting from Houghton Road to the principal tenant shall be at least six feet wide with an adjacent five-foot-wide landscape strip.



The following standards will be applied to the PAD District to ensure safe pedestrian access within and throughout the Property:

- Pedestrian Paths from Houghton Road should shade at least 65 to 70% of the sidewalks/paths during the major part of the day with canopy trees or other shading devices
- Sidewalks shall be provided along the full length of any building where it adjoins a parking lot.
- Pedestrian walkways will be provided from proposed buildings to individual parking areas via pedestrian crosswalks.
- Connections will be made from parking lots to the closest public sidewalk adjacent to the Property
- At each point that a designated on-site pedestrian walkway crosses a parking lot, street or driveway, the walkway will be clearly visible to pedestrians and motorists using one or more of the following methods:
 - A change in paving material, paving height or paving color;
 - A painted crosswalk;
 - Signage; or
 - Median walkway buffered by landscaping
 - Any other method approved by the City of Tucson which meet the intent of this section.
- New sidewalks will be constructed to City of Tucson Standards along Houghton Road and 22nd Street if not already constructed as part of the recent Houghton and 22nd road improvements.
- All pedestrian connections will be constructed to ADA (Americans with Disabilities Act) accessibility standards.



Exhibit III.H.1: Circulation Concept



LEGEND

- 5' PUBLIC EASEMENT
- HOUGHTON GREENWAY
- PRIMARY PEDESTRIAN ACCESS
- SECONDARY PEDESTRIAN ACCESS
- ACCESS POINTS

THIS EXHIBIT WAS CREATED USING THE MOST RECENT AVAILABLE BOUNDARIES, ROAD ALIGNMENT, AND EASEMENT DATA PROVIDED BY THE DIFFERENT GOVERNMENTAL ENTITIES AND ENGINEERING FIRMS AND IS FOR PLANNING PURPOSES ONLY. FINAL AREA TOTALS BASED ON ENGINEERED DATA MAY VARY FROM THOSE SHOWN ON THIS EXHIBIT.

0' 50' 100' NGS/N
 PROJECT:BDU-01 DATE:07/28/16
 FILE NAME: 141042CBS.DWG



I. Phasing Schedule

The following standards shall be applied to development of the Property along with the infrastructure required to serve that portion of the PAD development in accordance with market demands and Traffic Study submitted separately. The PAD is anticipated to be completed in one phase with full buildout in 2018. Detention and retention will be provided in accordance with the master hydrology/drainage report.

J. Cultural Resources

A review of Arizona State Museum records revealed that the Property has not been previously surveyed for cultural resources. Because the Property has not yet been inspected for archaeological resources, the Arizona State Museum recommends an on-the-ground cultural resource study be conducted prior to any ground disturbing activities. Historic or prehistoric features or artifacts discovered during future ground disturbing activities should be reported to the City of Tucson Historic Preservation Officer. Pursuant to A.R.S. 41-865 the discovery of human remains and associated objects found on private lands in Arizona must be reported to the Director of Arizona State Museum.

K. Water Conservation Standards

Conservation standards will be accomplished via low water use plants, efficient irrigation and rainwater harvesting.

1. Low Water Use Plants

The plant palette will consist of predominately low water use, native and regionally adapted plants. The plants will be located relative to their functionality and the uses associated with the zones within which they are planted. The use of low water use plants in locations appropriate with their species characteristics provides for the conservation of potable water while assuring the survivability and long term health of such plant material.

2. Irrigation

Plants requiring irrigation shall be irrigated by means of an efficient underground drip irrigation system. Underground drip systems reduce water evaporation and waste, thereby conserving water. The irrigation system will be controlled by a programmable controller which can be used to adjust irrigation schedules. The use of different seasonal irrigation schedules reduces the amount of water applied during cooler and wetter periods. Irrigation systems shall be fitted with irrigation controllers and shall be capable of monitoring and responding to plant water needs through the use of soil moisture gauges, tensiometers, weather stations and/or evapotranspiration data. The technology chosen should be capable of preventing the irrigation system from running if sufficient soil moisture is present to support the vegetation. All systems shall include rain shut-off devices.



3. Rainwater Harvesting

A water harvesting plan will be prepared at time of development plan submittal in compliance with Development Standards 10-03, illustrating 50 percent of estimated landscape water budget is met by water harvesting techniques. It will incorporate UDC 7.6.6 such that all hard surfaces drain towards minimum 6" to 9" depressed water harvesting or retention areas.

A number of passive rainwater harvesting techniques will be employed to direct surface water and capture rainfall for the benefit of the landscape: curb cuts, flush curbs, recessed planting areas, minimized compaction of planting areas and semi-pervious pavers.

4. Heat Island Mitigation

Several features within the PAD will be used to offset the heat island effect created by the Planned Area Development. Twenty percent of the Property will be designated as open space. Open space areas will contain large number of trees and vegetation and both organic and inorganic ground cover. Interior landscaping is not included in this designation and will further reduce heat absorption and shade paved areas. Trees and vegetation will be installed at building perimeters. Parking areas will include one shade tree for every four parking stalls. Shade trees will be planted along the 22nd Street right-of-way. Rainwater harvesting will be implemented, further reducing the heat island effect. The color palette for large areas with solar exposure will reduce the heat island effect. Roof tops, concrete sidewalks and areas of inorganic ground cover will be limited to light colors (white, light grey, beige, gold, and tan).

L. Pima County Wastewater Reclamation

The owner/developer shall obtain written documentation from the Pima County Regional Wastewater Reclamation Department (PCRWRD) that treatment and conveyance capacity is available for any development within the rezoning area, no more than 90 days before submitting any tentative plat, site plan, sewer improvement plan or request for building permit for review. Should treatment and/or conveyance capacity not be available at that time, the owner/development shall have the option of funding, designing and constructing the necessary improvements to Pima County's public sewerage system at his or her sole expense or cooperatively with other affected parties. All such improvements shall be designed and constructed as directly by the PCRWRD.



22nd & Houghton Planned Area Development (PAD)

IV. Implementation & Administration

City of Tucson

A. Design Review Committee

The Design Review Committee (DRC) shall consist of one (1) member from the developer, one (1) member from the Property consultant team, and one (1) member from the surrounding neighborhoods and/or neighborhood associations. The DRC will ensure conformance with the building elevations as shown in Exhibit III.A.1 through Exhibit III.A.3 or will review and approve any substantial modifications to building elevations. Approval will require an affirmative vote of the majority of committee members. A copy of the self-certification will be provided to the City of Tucson at the time of plan submittal advising whether the architectural and landscape design conforms to the Houghton & 22nd PAD Design Guidelines.

In addition to the voting members listed above, a non-voting representative of Saguaro National Park shall sit on the DRC to:

1. Review the design of the proposed wall along the northern and eastern property lines to ensure that wildlife movement and site drainage have been adequately considered to minimize potential adverse impacts caused by the development and
2. Work with the developer to create a plan that reduces, to the degree practical, harmful interactions between the staff and functions of the development and surrounding wildlife.

The DRC shall remain in place through 100% of the initial build-out of the development. Beyond this point, the Committee's function will survive through the Homeowners Associations of the residential subdivision or through the property owners' association of the commercial center, at their respective discretion.

B. Design Standards

Prior to development of any area within Houghton and 22nd PAD, development and design standards will be submitted as an extension of this document. These standards will follow the owner's vision to create a quality neighborhood shopping center. The guidelines will provide the framework for the design and character of Houghton and 22nd Planned Area Development and address the following goals:

- A common theme and design elements will be established that will be used throughout the Property. They will cover unifying site design elements, including streetscape design, signage, materials, colors and architectural styles and will be reviewed and approved by the design review committee established by the Master Developer. Guidelines should be clear, concise and enforceable.
- Address adjacent neighborhoods and provide for transitions at the edges of the property.
- Ensure new development does not adversely impact existing neighborhood character by complying with the Compatible Design policies of the HENP.



- Ensuring compatibility with existing Southwestern architectural styles and building materials of adjacent land uses.
- Provide consistency with the PAD and the intentions of the document.

C. Interpretations and Amendments

1. Interpretation

The regulations and guidelines provided within this PAD supersede existing regulations within the City of Tucson Unified Development Code. If an issue arises regarding definitions, conditions, standards and/or situations not addressed in this PAD, those in the UDC or other COT regulations shall prevail, as interpreted by the COT Zoning Administrator.

2. Amendments

Amendments to this PAD may be necessary over time to respond to the changing market demands, or financial conditions, or to respond to the unanticipated needs of new users. Non-substantial changes to the PAD shall be approved pursuant to UDC Section 3.5.5.I and include the following:

- Modifications to the permitted and secondary uses that do not change the overall intent of the PAD.
- Modifications to tax code parcel boundaries, including changes to interior boundaries or combining parcels. (Except that changes to the PAD perimeter boundary may not be considered a minor amendment or non-substantial changes to the PAD).
- Modifications to the proposed site plan provided the Development Standards set forth in the PAD are maintained.
- Any other items not expressly defined as substantial based on UDC Section 3.5.5.I

Substantial changes (as defined in UDC Section 3.5.5.I), are subject to the amendment application process outlined in UDC Section 3.5.5.I.2.



Bibliography

Aerial Photographs, Pictometry, 2014.

Balanced and Critical Basin Map, Pima County.

Plan Tucson, City of Tucson General & Sustainability Plan, ratified 2014.

City of Tucson GIS, TDOT Map Center, 2016.

City of Tucson Unified Development Code, 2016

FEMA Flood Insurance Rate Map, Pima County, Arizona.


Institute of Transportation Engineers, Trip Generation Manuals, 7th Edition, Volumes 1 & 3, 2003

MapGuide, Pima County Department of Transportation.

Stormwater Detention/Retention Manual, City of Tucson

USGS Topographic Map, Jaynes Quadrangle.





22nd & Houghton Planned Area Development (PAD)

V. Appendix

City of Tucson

Appendix A: Neighborhood Shopping Center

The proposed neighborhood shopping center development will serve the immediate area within a two- to three-mile radius. As shown on *Exhibit.A.1: Existing Food and Drug Stores*, there is a Fry's Food and Drug Store located at 22nd Street and Harrison Road., which is proposed for closure and releasing upon zoning approval of the new Fry's location (anchor store) within 22nd and Houghton PAD). The new Fry's location at 22nd Street and Houghton will capture this service area and improve their ability to be more competitive with the current market of grocery stores.

Exhibit.A.2: Existing Fry's Locations illustrates the existing Fry's locations throughout eastern Tucson and displays a three-mile service area around each store. Many of the service areas overlap, indicating that some customers within a store's three-mile service area may only patronize one particular store. Given that many of the existing store's service areas will overlap the proposed Fry's Food and Drug Store service area, it is assumed that the customers within the three-mile radius closest to the new store will patronize the new store and other customers will continue to shop at the store they accustomed to using.

In accordance with the Houghton East Neighborhood Plan (HENP) the development of non-residential uses is to be located at the major intersections along Houghton Road, including the intersection of 22nd Street and Houghton. The HENP provides the following definition for Neighborhood Commercial:

“Neighborhood Commercial: Low-intensity commercial uses serving neighborhood retail and service needs.”

The HENP also provides the following definition for Neighborhood Services:

“Public, semi-public, and commercial services which meet neighborhood needs, such as schools, churches, banks, and grocery stores.”

The International Council of Shopping Centers and the Urban Land Institute, in the *Dollars & Cents of Shopping Centers*, provides the following definition of a neighborhood shopping center:

"The neighborhood shopping center provides merchandise for daily living needs -- convenience goods like food, drugs, hardware and personal service. A supermarket is the principal tenant in this type of shopping center".

In summary, the PAD proposal is for neighborhood shopping center with the principal tenant being a grocery store. The primary offerings are groceries and secondary offering is pharmacy and health and beauty items typically found in drug stores. The secondary tenants include an associated Fry's gas station with kiosk and two retail building pads. The retail uses may include, but not limited to, personal service type uses as well as restaurant and/or coffee shop. The PAD proposal is in line with the above definitions and will service the surrounding neighborhoods for their convenience needs.



Exhibit Appendix A.1: Existing Food & Drug Stores


Grocery Stores Tucson, AZ 1/31/2014



COMMERCIAL RETAIL ADVISORS, LLC



Exhibit Appendix A.2: Existing Fry's Locations



FRY'S LOCATIONS

0' 3000' 6000'
SCALE: 1" = 6000'
PROJECT: BDU-01 DATE: 03/17/16
FILE NAME: Frys_w_Buffers.mxd

THE PLANNING CENTER
a division of TPC Group, Inc
110 S Church Ste 6320 Tucson AZ 85701



Appendix B: Public Sewer Improvement Plans




PUBLIC SEWER IMPROVEMENT PLAN TO SERVE 22ND STREET BAPTIST CHURCH

10325 E. 22ND ST., TUCSON, AZ 85748

LEGEND

FEATURE	NEW	EXISTING
SURVEY BENCH MARK		⊙
SURVEY MONUMENT		●
RIGHT OF WAY		---
MONUMENT & CONST E LINE		---
CONTOUR LINE - MAJOR	---50---	---50---
CONTOUR LINE - MINOR	---51---	---51---
A.C. PAVEMENT		
CONCRETE CURB		
BUILDING EXTERIOR WALL		
OVERHEAD UTILITY LINE		---OH---
POWER POLE		●
LIGHT POLE	✱	
COMMUNICATION PEDESTAL		⊞
UTILITY PEDESTAL		⊞
GAS LINE		---G---
SANITARY SEWER LINE	---S---	---S---
SANITARY SEWER HCS		---HCS---
SANITARY SEWER MANHOLE	⊙	⊙
SANITARY SEWER CLEANOUT	⊙	⊙
FIRE HYDRANT	⊙	⊙
FIRE DEPARTMENT CONNECTION	⊙	⊙
WATER LINE	---W---	---W---
WATER METER	⊙	⊙
WATER VALVE	⊙	⊙
RECLAIMED WATER LINE		---RW---
RECLAIMED WATER MANHOLE		⊙
SLOPE ARROW		



SEWER LAYOUT/OVERVIEW MAP



LOCATION MAP
SCALE: 3" = 1 MILE
A PORTION OF THE SECTION 13, 1-14-S, R-15-E
GILA AND SALT RIVER MERIDIAN, PIMA COUNTY, ARIZONA

OWNER/DEVELOPER
22ND STREET BAPTIST CHURCH
CONTACT : ASHLEY EVANS
ADDRESS : 6620 E. 22ND ST., TUCSON, AZ 85710
PHONE : (520) 269-3213

CIVIL ENGINEER
GRENIER ENGINEERING, INC.
CONTACT : RICHARD MACIAS, P.E.
ADDRESS : 5524 E. 4TH STREET,
TUCSON, AZ 85711
PHONE : (520) 326-7082
FAX : (520) 326-7508
EMAIL : rmacias@greniereng.com

SHEET INDEX
SHT 1 COVER SHEET
SHT 2 SEWER NOTES
SHT 3 PLAN & PROFILE



UTILITY NOTE
EXISTING UTILITIES ARE SHOWN BASED ON ABOVE GROUND LOCATION AND UTILITY BASE MAPS. THE LOCATIONS SHOWN HEREON SHOULD BE CONSIDERED APPROXIMATE. THERE MAY BE ADDITIONAL UTILITIES PRESENT WHICH ARE NOT SHOWN ON UTILITY BASE MAPS. THE CONTRACTOR SHALL FIELD LOCATE EXISTING UTILITIES IN ACCORDANCE WITH SEWER NOTE No. 3 PRIOR TO CONSTRUCTION.

AS-BUILT CERTIFICATION:
I HEREBY CERTIFY THAT THE AS-BUILT ANNOTATIONS PROVIDED ON THIS DRAWING WERE BASED ON AN AS-BUILT SURVEY CONDUCTED UNDER MY SUPERVISION AND ACCURATELY DEPICTS EXISTING FIELD CONDITIONS TO THE BEST OF MY KNOWLEDGE AND BELIEF.
WARREN D. THOMPSON *Warren D. Thompson* 10/2/15
REGISTERED LAND SURVEYOR DATE
16908 9/30/16
REGISTRATION NUMBER EXPIRES

ACCEPTED
Francisco Galindo 2/19/15
PIMA COUNTY REGIONAL WASTEWATER RECLAMATION DEPARTMENT DATE
Shirley C. Tims 2/20/15
DDOT (FOR LOCATION IN R.O.W. ONLY) DATE



REF #: DLU14-007 REV#1
G-2015-002

GRENIER ENGINEERING, INC.
 Structural & Civil Engineering Consultants
 5524 East 4th Street, Tucson, Arizona 85711
 Phone: 520.326.7082 - Fax: 520.326.7508

COVER SHEET

**PUBLIC SEWER IMPROVEMENT PLAN FOR
22ND STREET BAPTIST CHURCH**

A PORTION OF SECTION 13, T14S, R15E,
GUSHAM, PIMA COUNTY, ARIZONA

Job Number: 014932	Sheet Number: 1
Designed By: RM	Scale: N/A
Drawn By: RM	Revised: 01-21-15
Checked By: RM	Sheet Index: 1
Date: 01-21-15	Sheet 1 of 3

G-2015-002



SEWER NOTES

- ALL DESIGN STANDARDS, MATERIALS AND WORKMANSHIP FOR PUBLIC SANITARY SEWERS SHALL BE IN ACCORDANCE WITH THE PIMA COUNTY REGIONAL WASTEWATER RECLAMATION DEPARTMENT (PCRWWD) ENGINEERING DESIGN STANDARDS 2012 (EDS 2012) AND THE STANDARD SPECIFICATIONS AND DETAILS FOR CONSTRUCTION 2012 (SSDC 2012). SAID DOCUMENTS ARE AVAILABLE THROUGH THE PCRWWD WEBSITE (www.pima.gov/www/eng/des_std.htm).
- BASIS OF ELEVATIONS: THE BASIS OF ELEVATIONS FOR THIS PROJECT IS THE CITY OF TUCSON (COT) BENCHMARK No. 883-E BEING A CHISELED "X" ON THE NORTH END OF THE TOP OF THE HEADWALL ON THE EAST SIDE OF HOUGHTON ROAD, APPROXIMATELY 60- FEET SOUTH OF CALLE DE ESTE. SAID ELEVATION BEING 2227.84 (NAVD-88) PER COT FIELD BOOK 1989-E2, PAGE 5.
- BASIS OF BEARINGS: THE BASIS OF BEARINGS FOR THIS PROJECT IS THE EAST LINE OF THE SOUTHEAST QUARTER OF SECTION 14, TOWNSHIP 14 SOUTH, RANGE 15 EAST, GILA AND SALT RIVER MERIDIAN, PIMA COUNTY ARIZONA. SAID BEARING BEING NORTH 00°34'40" WEST, AS SHOWN HEREON.
- THE CONTRACTOR SHALL CALL "BLUE STAKE" (1-800-782-5348) A MINIMUM OF TWO (2) BUSINESS DAYS PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL KEEP ALL "BLUE STAKE" REQUESTS UP-TO-DATE AND COMPLY WITH APPLICABLE ARIZONA REVISED STATUTES (A.R.S.), TITLE 40, CHAPTER 1, ARTICLE 6.3, SECTION 40-360.22 PERTAINING TO "BLUE STAKE". ERRORS IN "BLUE STAKE" SHALL BE IMMEDIATELY REPORTED TO THE ENGINEER.
- THE CONTRACTOR SHALL VERIFY LOCATION AND ELEVATIONS OF ALL EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. CALL "BLUE STAKE" (1-800-782-5348) A MINIMUM OF TWO (2) BUSINESS DAYS PRIOR TO EXCAVATING.
- THE CONTRACTOR SHALL FIELD VERIFY EXISTING SEWER ELEVATIONS AND ALIGNMENTS PRIOR TO CONSTRUCTION AND IMPLEMENTATION; VERIFICATION MAY REQUIRE POT-HOLING.
- HOUSE OR BUSINESS CONNECTION SEWERS (HCS OR BCS) ARE NOT PART OF THE PUBLIC SANITARY SEWER CONVEYANCE SYSTEM. PRIVATE CONNECTION SEWERS CONSTRUCTED PRIOR TO JANUARY 2006 ARE NOT REQUIRED TO BE BLUE STAKED. ANY HCS/BCS ENCOUNTERED DURING CONSTRUCTION SHALL BE PROTECTED, REPAIRED, OR REROUTED, AS THE SITUATION DICTATES PER PCRWWD SSDC 2012, DETAIL RWRD 400 AND AT NO EXPENSE TO THE PROPERTY OWNER OR PCRWWD.
- PROVIDE A LIST OF LOTS THAT REQUIRE PRIVATE BACKWATER VALVES OR A NOTE INDICATING THAT NO PRIVATE BACKWATER VALVES ARE REQUIRED FOR THIS PROJECT.
- ANY ACTIVITY THAT MIGHT AFFECT THE SANITARY SEWER SYSTEM (MATERIALS ENTERING THE SYSTEM, CONVEYANCE AND TREATMENT) REQUIRES APPROVAL AND/OR PERMIT BY PCRWWD PRIOR TO ANY ACTIVITY.
- SEWER CONSTRUCTION SHALL NOT COMMENCE UNTIL (A) PIMA COUNTY DEPARTMENT OF ENVIRONMENTAL QUALITY (PCDEQ) HAS ISSUED A CERTIFICATE OF "CONSTRUCTION AUTHORIZATION" FOR THIS PROJECT AND (B) THE CONTRACTOR HAS OBTAINED A PUBLIC SEWER CONSTRUCTION PERMIT FROM PCRWWD (520-724-6369) (C) A PRE-CONSTRUCTION MEETING WITH THE ASSIGNED PIMA COUNTY PROJECT FIELD INSPECTOR IS SCHEDULED AT LEAST THREE (3) FULL WORKING DAYS PRIOR TO THE START OF SEWER CONSTRUCTION. FLOW MANAGEMENT PLANS SHALL BE SUBMITTED TO FIELD ENGINEERING THIRTY (30) DAYS PRIOR TO THE PRE-CONSTRUCTION MEETING.
- THE CONTRACTOR SHALL MAKE FULL PAYMENT OF THE INSPECTION FEES AND OBTAIN A PCRWWD SEWER CONSTRUCTION PERMIT FROM THE PIMA COUNTY SEWER CONSTRUCTION PERMIT SECTION A MINIMUM OF THREE (3) FULL BUSINESS DAYS PRIOR TO COMMENCING ANY SEWER CONSTRUCTION ACTIVITIES. FIVE (5) SETS OF THE CONSTRUCTION PLANS, SPECIFICATIONS, AND SPECIAL PROVISIONS (IF APPLICABLE) SHALL BE SUBMITTED WITH THE SANITARY SEWER CONSTRUCTION PERMIT APPLICATION. FIELD ENGINEERING REQUIRES A MINIMUM OF 5 BUSINESS DAYS NOTIFICATION (520-740-2651). NO WORK SHALL BE PERFORMED IN ANY CASE WITHOUT A PCRWWD CONSTRUCTION PERMIT.
- IMMEDIATELY REPORT ANY OF THE FOLLOWING TO EITHER PCRWWD FIELD ENGINEERING (520-740-2651) OR PCRWWD CONVEYANCE DIVISION (520-724-3500): ANY RELEASE OF SEWAGE, ANY DAMAGE TO THE PUBLIC SANITARY SEWAGE SYSTEM, OR THE DROPPING OF DEBRIS INTO THE PUBLIC SANITARY SEWAGE SYSTEM. ON WEEKENDS, HOLIDAYS, OR BETWEEN 5:00 P.M. AND 7:00 A.M., IMMEDIATELY CALL PCRWWD CENTRAL CONTROL ROOM AT 520-443-6048 AND REQUEST A PCRWWD REPRESENTATIVE TO BE DISPATCHED TO THE SITE. TAKE IMMEDIATE ACTION TO CONTAIN THE SANITARY SEWAGE OVERFLOW (SSO) FROM THE SEWER SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS TO REPAIR THE SYSTEM, FOR ALL EXPENSES TO MITIGATE THE RELEASE AND TO DISINFECT THE RELEASE AREAS AND FOR ANY REGULATORY PENALTIES LEVIED ON PCRWWD BECAUSE THE SSO ENTERED A NATURAL DRAINAGE WAY OR STORM WATER DRAINAGE SYSTEM. THE CONTRACTOR SHALL REPAIR ALL DAMAGE AS DIRECTED AND APPROVED BY PCRWWD.

SEWER NOTES CONTINUED

- THE INSPECTION OF THE CONTRACTOR'S WORK BY AN AGENCY AND/OR PCRWWD STAFF SHALL IN NO WAY RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, CONSTRUCTION PLANS AND/OR SPECIFICATIONS. IF THE ENGINEER OF RECORD OR PCRWWD STAFF FAIL TO POINT OUT A DEFECT, DEFICIENCY OR ERROR IN THE WORK FROM LACK OF DISCOVERY OR FOR ANY OTHER REASON, IT SHALL IN NO WAY PREVENT LATER REJECTION OR RELIEVE THE CONTRACTOR OF PERFORMING CORRECTIONS TO THE UNSATISFACTORY WORK WHEN DISCOVERED. THE CONTRACTOR SHALL NOT FILE A CLAIM FOR LOSSES SUFFERED DUE TO ANY NECESSARY REMOVALS OR REPAIRS RESULTING FROM THE UNSATISFACTORY WORK.
- THE CONTRACTOR SHALL COMPLY WITH APPLICABLE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS AT ALL TIMES AND PCRWWD MANHOLE ENTRY GUIDELINES.
- ALL ROUGH GRADING, INCLUDING FILL, SHALL BE COMPLETED PRIOR TO THE INSTALLATION OF SANITARY SEWERS TO A MINIMUM OF 4 FEET OVER THE TOP OF THE SEWER PIPE AND COMPACTION AS INDICATED ON THE PLANS OR AS OTHERWISE DIRECTED BY PCRWWD.
- BEDDING, SHADING, AND TRENCH BACKFILL COMPACTION SHALL BE IN ACCORDANCE WITH SSDC DETAIL NO. RWRD-104, OR AS SHOWN ON THE PLANS. SHOULD GROUND WATER OR UNANTICIPATED SOIL CONDITIONS BE ENCOUNTERED, THE BEDDING SHALL BE MODIFIED BY THE ENGINEER OF RECORD AND APPROVED BY PCRWWD.
- SANITARY SEWER CONSTRUCTION SHALL START AT THE LOWEST DOWNSTREAM POINT AND PROGRESS UPSTREAM, REGARDLESS OF THE STATIONING SHOWN ON THE PLANS. IF NOT, THE CONTRACTOR SHALL PROVIDE AN OUT OF SEQUENCE LETTER FOR APPROVAL BY PCRWWD.
- THE HORIZONTAL AND VERTICAL SEPARATION BETWEEN PUBLIC WATER MAINS AND PUBLIC SEWER LINES SHALL COMPLY WITH A.A.C. R18-5-502 AND S.D. RWRD-108.
- ACCORDING TO THE REVISED "BLUE STAKE LAW" (ARS 40-360.21 THROUGH 40-360.32), THIS PROJECT IS SUBJECT TO THE NEW SERVICE LATERAL DESIGN AND CONSTRUCTION REQUIREMENTS PER SUBSECTION 5.3.5 OF THE PCRWWD EDS 2012 AND SSDC 2012 S.D. RWRD-401 AND RWRD-404.
- NEW PUBLIC SEWER FACILITIES MUST BE TESTED, INSPECTED AND AUTHORIZED FOR DISCHARGE BY PCRWWD AND AEDD PRIOR TO DISCHARGING INTO THE EXISTING PUBLIC SANITARY SEWER.
- AS-BUILT SEWER PLANS ARE REQUIRED FOR FINAL ACCEPTANCE OF SEWER CONSTRUCTION BY PCRWWD AND SHALL CONFORM TO SUBSECTION 1.4.7 OF THE PCRWWD SSDC 2012.
SUBMIT:
- ONE PDF DOCUMENT OF THE AS-BUILT PLAN ON CD (ADEQ).
- ONE SET OF 24"x36" AS-BUILT PLANS FOLDER TO AN 8.5"x11" SIZE (ADEQ).
- ONE ROLLED SET OF 24"x36" AS-BUILT PLANS (RWRD).
- ONLY PLANS ACCEPTED BY PCRWWD SHALL BE USED FOR THE INSTALLATION OF SANITARY SEWER FACILITIES. PLANS ACCEPTED BY PCRWWD REQUIRING REVISION SHALL BE RESUBMITTED FOR REVIEW AND RE-ACCEPTANCE BY PCRWWD PRIOR TO START OF THE REVISED WORK.
- SEWER CONSTRUCTION WILL NOT BE ACCEPTED BY PCRWWD IF IT INCLUDES ADDITIONAL WORK NOT PROVIDED IN THE APPROVED SET OF PLANS. SEE PCRWWD SSDC 2012, SUBSECTION 1.4.5 OF THE REGARDING THE APPROVAL OF FIELD CHANGES.
- CONTRACTOR SHALL MAINTAIN ACCESS TO ALL SANITARY SEWER MANHOLE STRUCTURES AT ALL TIMES.
- ALL LANDSCAPING LOCATED WITHIN TEN (10) FEET HORIZONTALLY OF THE PUBLIC SANITARY SEWER AND MANHOLES AND/OR WITHIN THE PUBLIC SEWER EASEMENTS SHOWN HEREON SHALL BE IN ACCORDANCE WITH THE PLANTING GUIDELINES CONTAINED WITHIN PCRWWD EDS 2012, SUBSECTION 7.7.
- ALL STORM WATER POLLUTION PREVENTION PLAN (SWPPP) MEASURES SHALL BE INSTALLED SO AS TO PREVENT ALL STORM WATER, CONSTRUCTION WATER, FUELS, CHEMICALS, OR LIQUIDS TO BE DIRECTED INTO OR ONTO ANY SANITARY SEWER FACILITIES. PROTECTION OF SANITARY SEWER FACILITIES SHALL BE A PART OF THE APPROVED CONSTRUCTION SWPPP AND BEST MANAGEMENT PRACTICES. PROTECTION DEVICES SHALL BE INSTALLED AND MAINTAINED AROUND ALL POTENTIALLY AFFECTED SANITARY SEWER FACILITIES WITHIN THE PROJECT LIMITS. ADDITIONAL MEASURES SHALL INCLUDE BUT NOT BE LIMITED TO THE USE OF RAM STOPPERS AND MANHOLE COVERS AS DEEMED NECESSARY BY PCRWWD.

SEWER NOTES CONTINUED

- ALL PROJECT ACTIVITIES MUST BE KEPT WITHIN THE PROJECT AREAS. A CAUTION MUST BE NOTED CONCERNING HUMAN BURIALS. ARCHAEOLOGICAL CLEARANCE RECOMMENDATIONS DO NOT EXEMPT THE DEVELOPMENT FROM COMPLIANCE WITH STATE BURIAL PROTECTION LAWS. IN THE EVENT THAT HUMAN REMAINS, INCLUDING HUMAN SKELETAL REMAINS, CREMATIONS, AND/OR CEREMONIAL OBJECTS AND FUNERARY OBJECTS ARE FOUND DURING EXCAVATION OR CONSTRUCTION, GROUND DISTURBING ACTIVITIES MUST CEASE IN THE IMMEDIATE VICINITY OF THE DISCOVERY. STATE LAWS ARS 41-865 AND ARS 41-844 REQUIRE THAT THE ARIZONA STATE MUSEUM BE NOTIFIED OF THE DISCOVERY AT 520-621-4795 SO THAT CULTURAL GROUPS WHO CLAIM CULTURAL OR RELIGIOUS AFFINITY TO THEM CAN MAKE APPROPRIATE ARRANGEMENTS FOR THE REPAIRATION AND REBURIAL OF THE REMAINS. THE HUMAN REMAINS WILL BE REMOVED FROM THE SITE BY A PROFESSIONAL ARCHAEOLOGIST PENDING CONSULTATION AND REVIEW BY THE ARIZONA STATE MUSEUM AND THE CONCERNED CULTURAL GROUPS.
- SURVEY CUT SHEETS SHALL BE DEVELOPED IN ACCORDANCE WITH SUBSECTION 3.2.3(A)(1) OF THE PCRWWD SSDS 2012. CERTIFIED CUT SHEETS SHALL BE SUBMITTED TO THE PCRWWD FIELD ENGINEER PRIOR TO COMMENCEMENT OF SEWER CONSTRUCTION. THE CUT SHEETS ARE FOR THE PROJECT FILE AND COMMENCEMENT OF SEWER CONSTRUCTION WILL NOT BE DELAYED DUE TO REVIEW OF THE DELIVERABLE. ANY ERRORS OR EMISSIONS RESULTING IN IMPROPER SEWER CONSTRUCTION SHALL NOT BE THE RESPONSIBILITY OF PCRWWD. REFER TO SUBSECTION 3.2.3(A)(6) FOR ALIGNMENT VERIFICATION REQUIREMENTS INCLUDING THE SPACING REQUIREMENTS FOR GRADE STAKES.
- SURVEY LAYOUT AND SURVEY CONTROL SHALL BE PERFORMED BY, OR UNDER THE DIRECT SUPERVISION OF, A REGISTERED LAND SURVEYOR (RLS) REGISTERED IN THE STATE OF ARIZONA. PRIOR TO THE START OF SURVEY ACTIVITIES, THE INDIVIDUAL OR COMPANY RESPONSIBLE FOR SURVEY LAYOUT AND CONTROL SHALL CONTACT THE PIMA COUNTY DEPARTMENT OF TRANSPORTATION, SURVEY SECTION, DANIEL TREMBLAY, RLS, SURVEY MANAGER, AT 520-740-2629 TO ARRANGE A MEETING TO REVIEW SURVEY CONTROL, (HORIZONTAL AND VERTICAL), TO BE UTILIZED ON THE PROJECT.
- FOR FLOW MANAGEMENT PLAN REQUIREMENTS SEE THE PCRWWD SSDS 2012, SECTION 2. CALL REGIONAL WASTEWATER FIELD ENGINEERING AT 520-740-2651 REGARDING ALL QUESTIONS INVOLVING THE PREPARATION OF FLOW MANAGEMENT PLANS. PCRWWD SSDC 2012, SUBSECTION 2.2.1 APPLIES TO ANY PROJECT THAT REQUIRES TRENCHING WITHIN SIX (6) FEET HORIZONTALLY AND / OR TWO (2) FEET VERTICALLY OF AN EXISTING PUBLIC SEWER LINE. PRECEDING ANY WORK THAT MAY AFFECT A LIVE SEWER, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO: (A) IDENTIFY AND INCLUDE ALL FLOW MANAGEMENT COSTS IN THE CONSTRUCTION BID AND (B) PROVIDE A FLOW MANAGEMENT PLAN THIRTY (30) DAYS PRIOR TO A PRE-CONSTRUCTION MEETING.
- FOR PROJECTS REQUIRING A FLOW MANAGEMENT PLAN, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO (A) IDENTIFY AND INCLUDE ALL FLOW MANAGEMENT COSTS IN THE SEWER CONSTRUCTION BID SUBMITTED WITH THE PUBLIC SEWER PERMIT APPLICATION, AND (B) PROVIDE A FLOW MANAGEMENT PLAN (FMP) AT LEAST THIRTY (30) DAYS PRIOR TO THE PRE-CONSTRUCTION MEETING WITH PCRWWD FIELD ENGINEERING PRIOR TO BEGINNING SEWER CONSTRUCTION. FIELD ENGINEER WILL REVIEW THE FMP WITHIN 10 BUSINESS DAYS TO ACCOMMODATE REVIEW AND REVISION CYCLES. REFER TO SECTION 2 OF THE PCRWWD SSDC 2012. FOR ANY QUESTIONS REGARDING FLOW MANAGEMENT, PLEASE CONTACT PCRWWD FIELD ENGINEERING AT 520-740-2651.
- THE CONTRACTOR SHALL FURNISH, OPERATE AND MAINTAIN ALL EQUIPMENT AND LABOR NECESSARY TO PROVIDE CONTINUOUS 24 HR/DAY SANITARY SEWER SERVICE TO ALL PARTIES TRIBUTARY TO A LIVE SANITARY SEWER TO WHICH A CONNECTION IS TO BE MADE. THE PCRWWD CONVEYANCE SECTION SHALL BE NOTIFIED AT (520-724-3500) A MINIMUM OF TWO (2) BUSINESS DAYS PRIOR TO COMMENCING ANY CONSTRUCTION ACTIVITIES THAT COULD EITHER ADVERSELY IMPACT THE FLOW WITHIN A LIVE SANITARY SEWER SYSTEM, OR INVOLVE CONNECTION TO ANY PUBLIC SANITARY SEWER. THE CONTRACTOR'S ATTENTION IS DIRECTED TO SECTION 2 OF THE PCRWWD SSDC 2012.
- THE WORDS "PIMA COUNTY SANITARY SEWER" SHALL BE IMPRINTED ONLY ON COVERS OF MANHOLES WHICH ARE TO BE PART OF THE PIMA COUNTY REGIONAL WASTEWATER RECLAMATION (PUBLIC) SANITARY SEWER CONVEYANCE SYSTEM. SEWER MANHOLE COVERS ON CONVEYANCE SYSTEMS TO BE OWNED AND OPERATED BY ANYONE OTHER THAN PIMA COUNTY SHALL HAVE CAST INTO THEM THE WORDS "PRIVATE SEWER".
- IT IS THE SEWER CONTRACTOR'S RESPONSIBILITY TO ADJUST OR RECONSTRUCT ALL SANITARY SEWER MANHOLES TO FINISHED GRADE. ALL FRAMES AND COVER ADJUSTMENTS ARE TO BE IN ACCORDANCE WITH THE PCRWWD SSDC 2012, DETAIL RWRD 211, 212, 304 OR 305 (AS APPLICABLE) AND DETAIL RWRD 306. WHILE ADJUSTING THE MANHOLE TO FINISHED GRADE, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT FRAMES AND COVERS ARE CLEANED OF ANY AND ALL ATTACHED MATERIALS (ASPHALT, CONCRETE, ETC.) AND THAT ANY VENT HOLES ARE OPEN AND CLEAR OF OBSTRUCTIONS. IF THE FRAME AND COVER ARE DAMAGED OR CANNOT BE COMPLETELY CLEANED, A NEW FRAME AND COVER ARE TO BE PUT INTO PLACE. COSTS ASSOCIATED WITH THESE ACTIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR. REFER TO PCRWWD SSDC 2012, DETAIL RWRD 213 - 218 FOR FRAME AND COVER REQUIREMENTS.

SEWER NOTES CONTINUED

- EXISTING PRESSURE SEWERS AND ABANDONED GRAVITY SEWER MAIN LOCATIONS WILL BE IDENTIFIED AND MARKED PER PCRWWD SSDC 2012, DETAIL RWRD 503.
- THE CONTRACTOR SHALL SUPPLY A CERTIFICATION(S) FROM THE PIPE MANUFACTURER/LINER THAT STATES THAT THE PIPE AND THE LINING MEET THE CURRENT STANDARDS AND SPECIFICATIONS OF THE PIMA COUNTY WASTEWATER MANAGEMENT DEPARTMENT. THIS CERTIFICATION SHALL THEN GO ON TO STATE SPECIFICALLY THE FOLLOWING THINGS:
 - ALL DUCTILE IRON PIPE AND FITTINGS HAVE A SP-2000W, A POLYETHYLENE (PE), A COMBINATION OF POLYETHYLENE (PE) AND FUSION BONDED EPOXY (FBE) OR APPROVED EQUAL INTERIOR LINING OF 40 MILS (35 MILS MINIMUM) IN THE BARREL AREA, 10 MILS MINIMUM IN THE BELL AREA AND 10 MILS MINIMUM ON THE EXTERIOR OF THE SPIGOT END.
 - EACH PIECE OF PIPE AND EACH FITTING HAVE BEEN CHECKED FOR HOLIDAYS UTILIZING A TESTING VOLTAGE OF 7500 VOLTS WITH A DRY CONDUCTIVE PROBE IN THE BARREL AREA AND A TESTING VOLTAGE OF 67 1/2 VOLTS WITH A WET SPONGE IN BOTH THE BELL AREA AND THE EXTERIOR OF THE SPIGOT END AND THERE ARE NONE.
 - THE SP-2000W, PE OR PE/FBE LINING EXTENDS FROM THE BOTTOM OF THE GASKET SOCKET IN THE BELL TO A POINT ON THE EXTERIOR OF THE SPIGOT END OF THE PIPE WHERE THE NEXT PIPE GASKET WOULD OVERLAP THE LINING.
 - ALL SP-2000W, PE OR PE/FBE USED MEETS THE CURRENT SPECIFICATIONS SET BY PIMA COUNTY WASTEWATER MANAGEMENT FOR THIS MATERIAL.
 - THE MAXIMUM DRY FILM THICKNESS IN THE GASKET SEAT AREA AND ON THE EXTERIOR OF THE SPIGOT END IS 16 MILS.
- IF THE CONTRACTOR MAKES A FIELD CUT OF SP-2000W, PE OR PE/FBE LINED PIPE, HE SHALL PROPERLY PREPARE THE SURFACE OF THE PIPE TO RECEIVE A PROTECTIVE COATING OVER THE END OF THE PIPE WHICH SHALL CONSIST OF SP-2000W OR APPROVED EQUAL. THE INTERIOR SURFACE THAT IS BEING OVERLAPPED SHALL BE ROUGHED UP TO PRODUCE A 3 TO 5 MIL PROFILE OVER IT AND CLEANED IN ACCORDANCE WITH THE COATING MANUFACTURER'S INSTRUCTIONS. THE EXTERIOR SURFACE SHALL BE Sanded AND CLEANED IN ACCORDANCE WITH THE COATING MANUFACTURER'S INSTRUCTIONS. THE END RESULT OF THIS PROCESS IS TO SECURE PROPER ADHESION FOR THE NEW SP-2000W OR APPROVED EQUAL COATING. THE COATING SHALL THEN BE APPLIED AND ALLOWED TO PROPERLY DRY BEFORE PIPE ASSEMBLY. IN ALL CASES, AS A MINIMUM, A 10 MIL COATING OF SP-2000W OR APPROVED EQUAL SHALL BE APPLIED TO THE PIPE END AND SHALL OVERLAP THE ORIGINAL SP-2000W, PE OR PE/FBE LINING BY A MINIMUM OF FOUR INCHES AND EXTEND AROUND THE END OF THE PIPE AND ALONG THE OUTSIDE OF THE PIPE A MINIMUM OF TEN INCHES. THE MAXIMUM DRY FILM THICKNESS IN THE GASKET SEAT AREA AND ON THE EXTERIOR OF THE SPIGOT END IS 15 MILS. THE SP-2000W, PE, PE/FBE OR APPROVED EQUAL USED SHALL MEET THE CURRENT SPECIFICATIONS OF PIMA COUNTY WASTEWATER MANAGEMENT.
- THE FOLLOWING INFORMATION AS A MINIMUM WILL BE SHOWN ON THE EXTERIOR OF EACH PIECE OF DUCTILE IRON PIPE:
 - NAME OF LINING APPLICATOR
 - NAME OF LINING
 - THICKNESS OF LINING
 - DATE OF LINING APPLICATION
 - CLASS OF DUCTILE IRON PIPE
 - NAME OF DUCTILE IRON PIPE MANUFACTURER
 - DATE OF DUCTILE IRON PIPE MANUFACTURE
- ALL DUCTILE IRON PIPE THAT IS SUPPLIED SHALL NOT HAVE ANY EXTERIOR COATING UNLESS CALLED FOR ON THE CONSTRUCTION PLANS, THE CONSTRUCTION SPECIFICATIONS OR AS CALLED FOR IN THE NOTES LISTED ABOVE (SUCH AS ON THE EXTERIOR 10 INCHES OF THE SPIGOT END OF THE PIPE).



DATE	10/02/15
BY	SEWER ASBUILT


SEWER NOTES
PUBLIC SEWER IMPROVEMENT PLAN FOR
22ND STREET BAPTIST CHURCH
A PORTION OF SECTION 13, T14S, R15E,
G&SRM, PIMA COUNTY, ARIZONA

Sheet Number:	014632
Issued By:	RM
Drawn By:	AR/RM
Checked By:	RM
Date:	01-21-15
Scale:	N/A 1/2"=1'-0"
Sheet Name:	2
Sheet:	2 of 3



REF #: DLU14-007 REV#1
G-2015-002

G-2015-002



TDOT BACKFILL NOTES

- FOR WORK WITHIN THE CITY RIGHT-OF-WAY:
 - THE CONTRACTOR MUST OBTAIN AN EXCAVATION PERMIT AND BARRICADING PERMITS FROM THE CITY OF TUCSON TRANSPORTATION ENGINEERING DIVISION PRIOR TO ANY WORK IN THE CITY PUBLIC RIGHT-OF-WAYS.
 - THE CONTRACTOR MUST MEET WITH THE CITY'S RIGHT-OF-WAY INSPECTOR PRIOR TO ANY WORK IN THE PUBLIC RIGHT-OF-WAY.
 - ALL BACKFILL, WITHIN THE CITY OF TUCSON RIGHT-OF-WAY, ABOVE THE UTILITY SHADING SHALL BE CONDUCTED IN ACCORDANCE TO THE CITY OF TUCSON TRANSPORTATION STANDARD DETAILS, SPECIFICATIONS, AND AS DIRECTED BY THE CITY OF TUCSON RIGHT-OF-WAY INSPECTOR AND CITY ENGINEER.
 - ALL PAVEMENT PATCHING, WITHIN THE CITY OF TUCSON RIGHT-OF-WAY, SHALL BE CONDUCTED IN ACCORDANCE TO THE CITY OF TUCSON TRANSPORTATION STANDARD DETAILS, SPECIFICATIONS, AND AS DIRECTED BY THE CITY OF TUCSON RIGHT-OF-WAY INSPECTOR AND CITY ENGINEER.
 - IN ACCORDANCE TO THE CITY OF TUCSON STANDARDS, PERMANENT PAVEMENT PATCHING SHALL BE WARRANTED FOR 5-YEARS, PAVEMENT PATCH'S FAILING WITHIN THIS PERIOD SHALL BE REPAIRED/REPLACED AT NO COST TO THE CITY OF TUCSON.

UTILITY NOTE:
CAUTION!!! FIBER OPTICS AND GAS
EXISTING UTILITIES ARE SHOWN BASED ON ABOVE GROUND LOCATION AND UTILITY BASE MAPS. THE LOCATIONS SHOWN HEREON SHOULD BE CONSIDERED APPROXIMATE. THERE MAY BE ADDITIONAL UTILITIES PRESENT AND/OR RECENT UTILITY RELOCATIONS WHICH ARE NOT SHOWN ON UTILITY BASE MAPS. THE CONTRACTOR SHALL FIELD LOCATE EXISTING UTILITIES IN ACCORDANCE WITH SEWER NOTE No. 4 PRIOR TO CONSTRUCTION.



KEYNOTES

- NEW 4' DIAMETER PUBLIC SEWER MANHOLE PER STANDARD DETAIL RWRD 205.
- INSTALL TEMPORARY FLUG AND SECURE WITH A CHAIN TO A MANHOLE STEP. PLUS TO INCLUDE CONTRACTOR'S COMPANY'S NAME. FLUG TO BE REMOVED AFTER ADEQ APPROVAL OF CONSTRUCTION AND POST-PAVING INSPECTION.
- INSTALL CONCRETE COLLAR AROUND MANHOLE PER STANDARD DETAIL RWRD 212.
- INSTALL BLOCK-OUT TO THE EAST PER STANDARD DETAIL RWRD 203
- REMOVE AND REPLACE PAVEMENT PER PG/OT STANDARD DETAIL 216
- NEW 8" PRIVATE HCS PER STANDARD DETAIL RWRD 401.
- CONSTRUCT NEW MANHOLE OVER EXISTING SEWER PER RWRD SD 303.
- INSTALL WATERTIGHT FRAME AND COVER PER RWRD SD 214.
- IF CONSTRUCTION BEGINS BEFORE THE HOUGHTON RD IMPROVEMENTS (1-2013-006), CONTRACTOR SHALL INSTALL A STABILIZED SURFACE TREATMENT FOR THE PUBLIC SEWER PORTION PER RWRD SD 109 & 111.

FLOW MANAGEMENT DATA


CONTRACTOR TO PROVIDE A WASTEWATER FLOW MANAGEMENT PLAN PER WASTEWATER FLOW MANAGEMENT PLAN GUIDELINES SSDC 2012 SECTION 2.

BCS AS-BUILT INFORMATION

CLEANOUT #	NORTHING	EASTING	DISTANCE TO DOWNSTREAM MANHOLE @
1	441,003.36	1,053,921.49	35.14

MANHOLE AS-BUILT INFORMATION

MH No.	STATE PLANE COORDINATES (AZ CENTRAL) NAD 83 INTERNATIONAL FEET	
	NORTHING	EASTING
1	441,001.75	1,053,792.08
2	441,002.92	1,053,886.35



GRENIER ENGINEERING, INC.
Structural & Civil Engineering Consultants
8524 East 4th Street, Tucson, Arizona 85711
Phone: 520.326.7052 - FAX: 520.326.7508



SEWER AS-BUILT - 10/02/15

DATE	10/02/15
BY	WARREN D. THOMPSON
CHECKED BY	WARREN D. THOMPSON
DATE	10/02/15

PUBLIC SEWER PLAN AND PROFILE
PUBLIC SEWER IMPROVEMENT PLAN FOR
22ND STREET BAPTIST CHURCH
A PORTION OF SECTION 13, T14S, R1E,
GASORI, PINA COUNTY, ARIZONA
15' FROM THE EAST LINE OF HOUGHTON RD TO THE WEST LINE OF 22ND STREET

Job Number: 014032
Designed By: RM
Drawn By: RM/RM
Checked By: RM
Date: 01-21-15
Scale: N/A
Rev: 1"=20'

Sheet Number: **3**
Sheet 3 of 3

REF #: DLU14-007 REV#1
G-2015-002



Appendix C: Water Master Plan




WATER NOTES:

- TUCSON WATER STANDARD DETAIL No. 105, "GENERAL CONTRACT NOTES," SHALL APPLY TO AND BECOME AN INTEGRAL PART OF THIS CONTRACT. ALL DESIGN STANDARDS, MATERIALS, AND WORKMANSHIP ARE TO BE IN ACCORDANCE WITH TUCSON WATER STANDARD SPECIFICATIONS AND DETAILS, 2001 EDITION AND ENGINEERING DIRECTIVES AND POLICIES.
- CONSTRUCTION WATER FOR PRESSURE TESTING, CHLORINATING AND FLUSHING SHALL BE PROVIDED THROUGH THE EXISTING WATER SYSTEM AND SHALL COST \$_____ PLUS TAX. CONSTRUCTION WATER FOR TRENCH BACKFILL AND COMPACTION AND OTHER CONSTRUCTION NEEDS SHALL BE THROUGH AN APPROVED METERED WATER SOURCE OBTAINED FROM TUCSON WATER CUSTOMER SERVICE DIVISION UNDER A SEPARATE PERMIT/AGREEMENT.
- THIS WATER SYSTEM IS DESIGNED TO ACCOMMODATE 2500 GPM FLOW FOR 7 HOURS.
- AT THE TIME OF PLAN APPROVAL, THIS DEVELOPMENT IS LOCATED WITHIN "Z" ZONE. MINIMUM DESIGN PRESSURES FOR THIS DEVELOPMENT ARE AS FOLLOWS:
 1. STATIC PRESSURE: 55.0 psi
 2. PEAK DAY PRESSURE: 55.0 psi
 3. PEAK DAY + FIRE FLOW: 55.0 psi
 DUE TO WATER SYSTEM OPERATIONAL VARIANCES PRESSURE WILL VARY AS MUCH AS 10 PSI +/-
- 2,272 L.F. OF NEW PIPELINE (EXCLUDING WATER SERVICE LINE 2" AND LESS IN DIAMETER) WILL BE INSTALLED FOR THIS PROJECT. A PIPELINE INSPECTION FEE OF \$7.00 PER LINEAR FOOT OF PIPELINE INSTALLED WILL BE ASSESSED PRIOR TO ISSUANCE OF "NOTICE TO PROCEED".

- EFFECTIVE AUGUST 11, 2003 PAYMENT OF THE WATER SYSTEM EQUITY FEE IS REQUIRED AT THE TIME OF WATER METER APPLICATION, PER ORDINANCE No. 5942, AMENDMENT TO THE TUCSON CODE, SECTION 27-36.
- EFFECTIVE MONDAY, JULY 9, 2007, THE GAP WATER RESOURCE FEE SHALL BE ASSESSED IN ADDITION TO THE SYSTEM EQUITY FEE FOR ALL NEW POTABLE WATER METER CONNECTIONS.
- AFTER JANUARY 4, 2014, THE CONTRACTOR SHALL FURNISH AND INSTALL ALL PIPE, FITTINGS, APPURTENANCES OR ANY OTHER MATERIALS TO BE IN CONTACT WITH POTABLE WATER IN ACCORDANCE WITH THE LEAD-FREE REQUIREMENTS DERIVED BY THE "REDUCTION OF LEAD IN DRINKING WATER ACT OF 2011" AMENDING SECTION 1417 OF THE SAFE DRINKING WATER ACT.
- THIS PROJECT WILL BE REQUIRED TO USE AUTOMATIC METER READING (AMR) EQUIPMENT. THE DEVELOPER WILL BE HELD RESPONSIBLE FOR THE CARE AND MAINTENANCE OF THE AMR METER, TRANSMITTER AND METER BOX. THE ADDITIONAL COST OF THE AMR EQUIPMENT WILL BE DETERMINED AT THE TIME OF METER APPLICATION IN ACCORDANCE WITH CHAPTER 27, SECTION 35 OF THE CITY OF TUCSON CODE.
- THE RESPONSIBLE PARTY FOR FIRE SERVICE BILLING IS THE OWNER/DEVELOPER AS CALLED OUT ON THE PLAN.
- NEW WATER MAIN SHALL BE INSTALLED WITH 44" OF MINIMUM COVER PER S.D. 105, UNLESS OTHERWISE INDICATED ON THESE PLANS.
- ALL FITTINGS SHALL BE RESTRAINED PER TUCSON WATER STANDARD DETAIL 600, UNLESS RESULTS OF APPROVED ENGINEERING CALCULATIONS ARE PROVIDED. FOR PIPE 16" AND GREATER IN DIAMETER APPROVED ENGINEERING CALCULATIONS MUST BE DOCUMENTED IN THIS PLAN.
- THE OWNER SHALL IDENTIFY TUCSON WATER (CITY OF TUCSON) AGAINST ANY AND ALL DAMAGE TO PRIVATE FACILITIES LOCATED IN PUBLIC WATER EASEMENTS.



LOCATION MAP
 LOCATED IN SECTION 13, T14S, R15E, GASBNA, PIMA COUNTY, ARIZONA
 BAND 2
 LAT: 32° 1' 10.4" - 110.7"
 SOURCE: PIMA COUNTY MAPCORDE




OWNER/DEVELOPER
 BRENTWOOD DEVELOPMENTS
 5000 STANFORD RANCH ROAD, STE. 210
 ROCKLIN, CA 95765
 ATTN: BRAD GROTTHITZ
 PHONE: (916) 759-4265
 FAX: (916) 433-4181

CIVIL ENGINEER
 STANLEC CONSULTING SERVICES INC.
 5151 E. BROOKING BLVD., STE. 400
 TUCSON, AZ 85711
 ATTN: WARREN D. THOMPSON, P.E.
 PHONE: (520) 750-7474
 FAX #: (520) 750-7470

BASIS OF BEARINGS
 THE BASIS OF BEARING FOR THIS SITE IS THE SOUTH LINE OF THE SW 1/4 OF SECTION 13, T14S, R15E AS SHOWN ON THE SUBDIVISION PLAT OF "RANCHO DEL ESTE", BK. 27 OF MAP AT PG 2.
 S&D BEARING = N 89°58'10" W

BASIS OF ELEVATION/BENCH MARK
 THE BASIS OF ELEVATION FOR THIS SITE IS A 2" BRASS CAP IN HANDHOLE LOCATED AT THE SOUTHWEST CORNER OF SECTION 13, T14S, R15E, BEING THE CENTERLINE INTERSECTION OF SOUTH HOUGHTON ROAD AND 22ND STREET.
 S&D ELEVATION = 2841.45 (NAVD 88 DATUM)



SITE MAP
 SCALE: 1"=60'

Stanlec Consulting Services Inc.
 5151 E. Brooking Blvd., Ste. 400
 Tucson, AZ
 05711-3712
 TEL: 520.750.7474
 FAX: 520.750.7470
 www.stanlec.com
 Stanlec Job# 14130700-01159

The Contractor shall verify and be responsible for all dimensions, lot area, and elevations - any errors or omissions shall be reported to Stanlec without delay. The Contractor shall verify and be responsible for all dimensions, lot area, and elevations - any errors or omissions shall be reported to Stanlec without delay. The Contractor shall verify and be responsible for all dimensions, lot area, and elevations - any errors or omissions shall be reported to Stanlec without delay.

NO.	BY	DATE	REVISION	APPR.	DATE
1	WDT	10/21/15	Grade Changes for footings for Home/Unit	WDT	10/21/15
2	WDT	5/21/15	8" to 12" stub @ Access	WDT	5/21/15
3	WDT	5/15/15	Change High-Density Polyethylene to 15233	WDT	5/15/15
4	WDT	5/15/15	Change High-Density Polyethylene to 15233	WDT	5/15/15

TUCSON WATER

ACCEPTED: [Signature] DATE: 3-10-15


CITY OF TUCSON FIRE DEPARTMENT

ACCEPTED BY THE CITY OF TUCSON WATER DEPARTMENT, NEW DEVELOPMENT UNIT, FOR SUBSEQUENT CONFORMANCE WITH STANDARD SPECIFICATIONS AND DETAILS. DATE: 03/15/15

PRELIMINARY MASTER WATER PLAN
 IN SECTION 13, T14S, R15E, GASBNA
 CITY OF TUCSON, PIMA COUNTY, ARIZONA

DESIGNED BY	DATE	CHECKED BY	DATE	SHEET	OF
WDT	03/15	TAL	03/15	1	6
TAL	03/15	WDT	03/15		
WDT	03/15				





SERVICE WORK

CODE	ADDRESS	PIPE SIZES & QUANT. (IN FEET)
M	METER NUMBER & SIZE	3/4" 1" 1 1/2" 2"
1	N HOOD S. HOUGHTON RD	
R	11570625	72

Stantec
 Stantec Consulting Services Inc.
 515 E Broadway Blvd., Ste. 400
 Tucson, AZ 85711-3712
 Tel. 520.760.7474
 Fax. 520.760.7470
 www.stantec.com
 Station 404 38130907-201.150

TUCSON WATER
 CITY OF TUCSON
 WATER DISTRIBUTION SYSTEM TO SERVE BRENTWOOD DEVELOPMENT
 FRY'S STORE - NEC 22ND & HOUGHTON


PRELIMINARY MASTER WATER PLAN
 IN SECTION 13, T14S, R15E GASRM
 CITY OF TUCSON, PINA COUNTY, ARIZONA

DESIGNED BY: HDT DATE: 03/15
 DRAWN BY: JAL DATE: 03/15
 CHECKED BY: HDT DATE: 03/15

FIELD BOOK NO.:
 SHEET 2 OF 6
 PLAN NO.:
 SCALE: 1"=60'
 PN

NO.	BY	DATE	REVISION	APPD.	DATE
1	WBT	5/15/15	Change Hydr. Direction on Houghton Rd. 2nd 1, 2, 4, 3		





SEE SHEET W08 OF W28 FOR WATER MAIN PLAN & PROFILE

STA 198+92±, 6± RT. TO STA 198+93±, 53± LT. 59± REMOVE AND DISPOSE 10" AND SMALLER NON CA PIPE STA 198+93±, 53± LT. REMOVE & DISPOSE EXIST FIRE HYDRANT, CONCRETE THRUST BLOCK PER W-610

VALVE COVER TO MATCH PROP TOP OF CURB ELEV.

STA 200+30±, 21± RT. 87± DI (CL 350) VALVE BCC, FLG X MJ STA 200+30±, 65± LT. 65± 1-FIRE HYDRANT PER W-500

CONCRETE THRUST BLOCK PER W-610


HOUGHTON RD CONST E

HOUGHTON RD

FIRE HYDRANT AT STA 200+30

NEW RIGHT-OF-WAY

EXISTING RIGHT-OF-WAY



Stantec
 Stantec Consulting Services Inc.
 5151 E. Broadway Blvd., Ste. 400
 Tucson, AZ 85711-3712
 Tel: 520.750.7474
 Fax: 520.750.7470
 www.stantec.com
 Stantec Adv. 151.301097-201.150

NO OTHER LOG SHOULD BE ON OR OFF FOR THE BLUE PRINTS
 1-800-782-5348
 BLUE PRINT CENTER

NO.	BY	DATE	REVISION	APPD.	DATE
1	WDT	5/15/15	Change their Direction on Houghton Rd. Shts 1, 2 & 3	WDX	5/16/15



TUCSON WATER


CITY OF TUCSON
 WATER DISTRIBUTION SYSTEM TO SERVE BRENTWOOD DEVELOPMENT
 FRY'S STORE - NEC 22ND & HOUGHTON

PRELIMINARY MASTER WATER PLAN
 IN SECTION 1.3, 114S, R15E G4SRM
 CITY OF TUCSON, PIMA COUNTY, ARIZONA

DESIGNED BY	WDT	DATE	03/15	CHECKED BY	TZN	DATE	03/15	SCALE	1"=2'	SHEET	3 OF 6
DRAWN BY	WDT	DATE	03/15	SCALE	1"=20'	PLAN NO.	PN				

PN _____
 DWG. FILE: 07067C-HW03.DWG





SEE SHEET W23 OF W28 FOR LATERAL WATER MAIN PLAN & PROFILE

SEE SHEET W09 OF W28 FOR LATERAL WATER MAIN PLAN & PROFILE

Sta 50+00.00 22nd St E-
Sta 205+88.80 Houghton Rd E
N= 140679.61
E= 153824.19
PH# 2393
N 140690.606
E 153923.782
STA 50+99.58
TOP ELEV. 2837.482
OFF 10.18

PH# 2392
N 140690.647
E 154423.630
STA 55+99.51
TOP ELEV. 2848.932
OFF 6.10

MATCHLINE STA 45+00
SEE SHEET W12

MATCHLINE STA 56+00
SEE SHEET W14

STA 45+00±, 20± LT. TO STA 51+40±, 10± LT. 645± REMOVE & DISPOSE 10± & SMALLER CA PIPE

STA 45+00±, 0± LT. TO STA 46+02±, 0± LT. 102± 8" DI (CL 350)


STA 49+14±, 0± RT. (CONNECTION TO PIPE) 70± 1" CU PIPE
STA 48+97±, 55± RT. (LOCATION OF ARV)
1-1" ARV PER W-330

SEE SHEET W10 OF W28 FOR LATERAL WATER MAIN PLAN & PROFILE

STA 53+25±, 8± LT. TO 75± LT.
1- 8" x 8" TAPPING TEE & VALVE
42.6± 8" PVC (C900)
20 L.F. 8" DIP (CI 350)
2- 8" x 45° BENDS
(ALL RESTRAINED)
STUB & BLOCK AT R.O.W.

SERVICE WORK				
CODE	ADDRESS	PIPE SIZES & QUANT. (IN FEET ±)		
M	10215 E. 22ND STREET	¾" 1" 1½" 2"		
R	39769250	1"	55	
S	Sta 48+65 (lrr)	2"		70

45+00 46+00 47+00 48+00 49+00 50+00 51+00 52+00 53+00 54+00 55+00 56+00



NEW 6-10" x 8" REBC
INV. 2826.95

PH# 2385
TOP ELEV. 2827.07

STA 46+02±, 0± RT.
8" 45° BEND (VT)
INV. 2830.68±

STA 45+94±, 0± RT.
R. 45° BEND (VT)
INV. 2822.12±

NEW 8" DI WATER MAIN
END PVC WATER MAIN BEGIN DI WATER MAIN


Stantec Consulting Services Inc.
3151 E. Broadway Blvd., Ste. 400
Tucson, AZ 85711-3712
Tel. 520.750.7474
Fax. 520.750.7470
www.stantec.com
Stantec Job #101067-2011-0



The Contractor shall verify and be responsible for all dimensions. DO NOT SCALE the drawing - any errors or omissions shall be reported to Stantec within 48 hours. The Copyright to all design and drawings on this property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.



NO.	BY	DATE	REVISION	APPD.	DATE



WATER DISTRIBUTION SYSTEM TO SERVE BRENTWOOD DEVELOPMENT FRY'S STORE - NEC 22ND & HOUGHTON


PRELIMINARY MASTER WATER PLAN
IN SECTION 13, T14S, R15E GASRM CITY OF TUCSON, PIMA COUNTY, ARIZONA

APPROVED BY:	DATE:	SCALE:	SHEET:
WDT	03/15	1"=40'	4 OF 6
TAL	03/15	1"=40'	PN
WDT	03/15	1"=40'	PN

PN

DWG. FILE: 07067C-W004.DWG







DWG. FILE: 07067C-MW05.DWG


PN





2850


2840



2860

2850

2840



2870

2860

Stantec

Stantec Consulting Services Inc.
 5151 F. Broadway Blvd., Ste. 400
 Tucson, AZ 85711-3712
 Tel. 520.750.7474
 Fax. 520.750.7470
 www.stantec.com
 Stantec A/E/C 191307007-201.150

NO RECORDS SHOWN ABOVE THIS DATE FOR THIS PROJECT

1-800-782-5348
 BLUE STAKE CENTER

The Contractor shall verify and be responsible for all dimensions. We will make the drawing - any errors or omissions shall be corrected by Stantec without delay. The Contractor shall make and keep on file all records of this project. Stantec, Incorporated or one of its previous names shall not be held responsible for any errors or omissions.

NO.	BY	DATE	REVISION	APPRO.	DATE
1	WDT	5/11/15	8" to 12" stub @ Access		5/10/15
2	WDT	5/15/15	Change from 8" to 12" stub @ Access		5/10/15

TUCSON WATER

CITY OF TUCSON
 WATER DISTRIBUTION SYSTEM TO SERVE
 BRENTWOOD DEVELOPMENT
 FRY'S STORE - NEC 22ND & HOUGHTON

PRELIMINARY MASTER WATER PLAN

IN SECTION 13, T14S, R15E, GASRM
 CITY OF TUCSON, PIMA COUNTY, ARIZONA

REVISION BY: WDT 03/15
 DATE: 03/15
 SCALE: 1"=40'
 SHEET: 6 OF 6

APPROVED BY: WDT 03/15
 DATE: 03/15
 SCALE: 1"=40'
 SHEET: PN

PN

DWG. FILE: 07067C-MW06.DWG



**Appendix D: Houghton Road and 22nd Street Intersection Future
Modifications**





CITY OF
TUCSON

DEPARTMENT OF
TRANSPORTATION

September 11, 2015

R. Craig Finfrock, CCIM, CRX
Commercial Retail Advisors, LLC
5420 E. Broadway Blvd., Suite 200
Tucson, AZ 85711

Re: Houghton Road and 22nd Street Intersection Future Modifications

Dear Mr. Finfrock,

Left turn access and median opening modifications at the referenced intersection may be approved for the northeast corner of 22nd Street and Houghton Road intersection. Some details need to be finalized before approval can be given. The details need to be identified by a Traffic Impact Analysis (TIA).


Upon approval, the steps to physically make the modifications will require approved engineered drawings, a Private Improvement Agreement (PIA), and a right-of-way (ROW) permit. The work can be done during or after the 5-year pavement no-cut moratorium that will be in place upon completion for the Houghton Road Corridor Improvements between Broadway Boulevard and 22nd Street.

It is our desire to get the best use out of the new pavement as possible before its life is affected by cutting it. Therefore, we shall require that any modifications affecting the pavement be done when the development is under construction and not before. Special conditions are added to the pavement replacement requirements when the pavement is disturbed during the 5-year pavement no-cut moratorium.

Utility service sizes and locations are based upon an approved development plan and require utility service agreements with the respective utility company. The utility companies will typically do their own work and seek their own ROW permits.

Let us know if you have further questions.

Sincerely,



Frederick Felix, P.E.
City Engineer

Cc: Daryl W. Cole

Mr Brad Griffith
Brentwood Development
5800 Stanford Ranch road, Suite 210
Rocklin, CA 93765

Ashley Evans
22nd St Baptist Church of Tucson, Inc
6620 E 22nd St
Tucson, AZ 85710

ENGINEERING DIVISION
P.O. BOX 27210 • TUCSON, AZ 85726-7210
(520) 791-5100 • FAX (520) 791-4239
www.cityoftucson.org

